

FY 2020/2021 QC Category No. 1
STATEWIDE INSPECTION GUIDELIST
Clearing and Grubbing

1. Clearing and Grubbing limits are established according to contract documents. [Spec. 110-2]
2. Stumps, roots, and other debris within roadway are removed and standard clearing and grubbing meets requirements shown in contract specifications sections 110-2.1 through 110-2.4.
3. Check location of selective clearing and grubbing areas designated in contract documents. Ensure the Engineer's instructions for both removal areas and preservation areas for brush and trees have been carried out in the selective clearing and grubbing areas. [Spec. 110-3]
4. Burning of debris must be in accordance with applicable laws, ordinances, permits and regulations. [Spec. 110-9.2]
5. Existing buildings, including foundations are removed to accommodate new construction. [Spec. 110-5]
6. Ensure that, except as specified otherwise in the contract documents, the Contractor takes ownership of and disposes of all removed materials. [Spec. 110-9.1 to 110-9.5]
7. For miscellaneous operations such as plugging abandoned water wells, landscape areas, terrain leveling and mailbox adjustment, ensure the Contractor meets the requirements specified. [Spec. 110-10]
8. Meet the requirements of Spec. 110-11 and 110-12 on method of measurement and basis of payment for clearing and grubbing. Monthly progress estimates should be made as stated in the Construction Project Administration Manual (CPAM) [Section 5.11.5].