

**FY 2020/2021 QC Category No. 14A
STATEWIDE INSPECTION GUIDELIST
Performance Turf**

GENERAL

1. Ensure the Contractor establishes a growing, healthy, Performance Turf, with full coverage, over all areas designated on the plans. [Spec 570-1]
2. Ensure Performance Turf seed produces visible seedlings within 45 days of planting. [Spec 570-3.2]
3. Ensure the Performance Turf sod is cut no longer than 48 hours prior to placement. [Spec 570-3.3]
4. Ensure established Performance Turf is maintained by the Contractor until final acceptance. Performance Turf should be a growing, healthy, and vigorous stand of grass which has no bare spots greater than 1% of any given 1,000 square foot area. [Spec. 570-4]

Watering

1. Ensure the Contractor waters as needed to produce a healthy and vigorous stand of grass. [Spec. 570-3.6]

Fertilizing

2. Ensure that soil testing is performed in each representative area where Performance Turf is to be installed. The Contractor should apply site specific nutrients and application rates based on soil testing results. [Spec. 570-3.7]

The Performance Turf umbrella includes approved species of grass in methods of grass seeding, grass hydroseeding, wildflowers, creeping legumes, and sod of approved species