

**FY 2017/2018 QC Category No. 14A
STATEWIDE INSPECTION GUIDELIST
Performance Turf**

GENERAL

1. Assure that Contractor establishes a growing, healthy turf over all areas designated on plans. [Spec 570-1].
2. Assure that the sod is cut no longer than 48 hours prior to use. [Spec 570-3.3].
3. Assure established turf is maintained by the Contractor until final acceptance per spec. including no bare spots greater than one square foot or deformation caused by mowers or other contractor equipment. [Spec. 570-4].

Watering

4. Assure that Contractor waters as necessary to produce a healthy and vigorous stand of turf. [Spec. 570-3.6].

Fertilizing

5. Ensure that soil testing is performed and assure that Contractor uses proper rates based on soil testing results. [Spec. 570-3.7].