

**FY 2018/2019 QC Category No. 14A
STATEWIDE INSPECTION GUIDELIST
Performance Turf**

GENERAL

1. Ensure that Contractor establishes a growing, healthy turf over all areas designated on plans. [Spec 570-1].
2. Assure that the sod is cut no longer than 48 hours prior to use. [Spec 570-3.3].
3. Ensure established turf is maintained by the Contractor until final acceptance, including no bare spots greater than one square foot or deformation caused by mowers or other contractor equipment. [Spec. 570-4].

Watering

4. Ensure that Contractor waters as necessary to produce a healthy and vigorous stand of turf. [Spec. 570-3.6].

Fertilizing

5. Ensure that soil testing is performed and that the Contractor uses proper rates based on soil testing results. [Spec. 570-3.7].