Topic No.: 700-000-000 Effective: July 1, 2002 Construction Project Administration Manual Revised Date: April 7, 2025

Asphalt

Section 11.7

ASPHALT CONSTRUCTION INFORMATION FOR CONTRACTOR QUALITY CONTROL

11.7.1 Purpose

The purpose of this procedure is to describe the Department's role when reviewing and verifying Contractor Quality Control (QC) documentation, establishing waste asphalt quantities, and processing Resolution Reports for Asphalt Concrete (AC), Gradation, and Density Cores.

11.7.2 Authority

Sections 20.23(3)(a) and 334.048(3), Florida Statutes (F.S.)

11.7.3 Verification of Quality Control Documentation

Each Contractor is required to record the placement of asphalt on the Contractor's **Quality Control-Roadway Report (QCRR)**, **Form 675-030-20A – Automated Version** as the pavement operation progresses.

The Engineer will obtain the **QCRR** from the Contractor and collect all the asphalt tickets associated with the report. The Resident Office (RO) is responsible for ensuring all the information submitted in the **QCRR** is accurate, including but not limited to, verifying the G_{mm}/G_{sb} entered for the LOT, reviewing and randomly checking the quantities submitted by the QC Technician (also see **CPAM 11.6**), and ensuring the information on the tickets for each day's production match the report.

The contractor's QC personnel is responsible for making all necessary corrections within the *QCRR* if an error or failure is detected. The RO will make a notation of the correction in the "Comments" section in PrC. See <u>Attachment 11-7-3</u>.

NOTE 1: Mix Design information is available in the "Asphalt Mix Design Short Report" in MAC.

NOTE 2: See **QCRR Corrections** on the State Construction Office Website for instructions on corrections due to Materials Failure and Workmanship Issues.

Construction Project Administration Manual

Asphalt

Contractor and Department – Waste Asphalt Quantity 11.7.4 **Determination**

It is not necessary for the Contractor's truck driver to return to the plant to determine the quantity of "Waste" asphalt remaining in the truck. The Contractor's QC Technician and the Department's Verification Technician (VT) should concur on the estimated amount left in the truck based on one of the following methods:

(A) Spread Rate

Example:

Determine the waste tonnage with the following information:

- Last load of Asphalt = 21.35 Tons (from Ticket)
- Spread rate on the project = 75 Lbs/SY
- The paved area = 430 SY

Tonnage Used =
$$\frac{\left(\text{Spread Rate } \left(\frac{\text{Lbs}}{\text{SY}}\right) \left(\text{Area Paved } (\text{SY})\right)\right)}{2,000 \text{ Lbs/Ton}}$$

$$= \frac{(75 \text{ Lbs/SY})(430 \text{ SY})}{2,000 \text{ Lbs/Ton}}$$

$$= 16.125 \text{ Tons}$$
Waste Tonnage = Original Quantity – Quantity Used
$$= 21.35 - 16.125 = 5.2 \text{ Tons}$$

(B) **Visual Inspection**

A visual inspection of the remaining asphalt in the truck estimated to the nearest ¼ of a truck load.

Example:

1/4 of a truck load was remaining, which is approximately 5.3 Tons

Waste Tonnage =
$$\frac{\text{Ticket Tonnage}}{4} = \frac{21.35}{4} = 5.3 \text{ Tons}$$

Topic No.: 700-000-000 Effective: July 1, 2002 Construction Project Administration Manual Revised Date: April 7, 2025

Asphalt

11.7.5 Resolution Reports for AC Content, Gradation, and Density Cores

When the QC Technician's test results and the Department's VT's test results do not compare for a specified test, the QC test results are not verified. Therefore, Resolution Tests (RT) for all sublots in the LOT must be run for each property that does not compare. These RT results are then compared to the QC test results.

If the RT results compare to the QC test results, accept and pay on QC Test results.

If the QC Test Results do not compare (even if only one sublot QC and RT do not compare), accept and pay on RT report results. The cost of the Resolution Testing performed by the Department, that do not favor the QC test results, will be deducted from the Contractor's next progress estimate. The District Materials Office will provide the resolution results to the Project Administrator (PA) via email. Submit this email as backup documentation to support the deduction. See Attachment 11-7-1, for an example of an e-mail from the District Materials Office to the PA with the number of resolution tests and costs.

See <u>Attachment 11-7-2</u>, for an example of Resolution Testing Costs and <u>Attachment 11-7-3</u> for an example of reporting the cost of resolution testing in AASHTOware Project Construction (PrC).

Note 3: For FC 5 (Open Graded Friction Course), only AC Content and Gradation tests are subject to resolution testing.

Topic No.: 700-000-000 Effective: July 1, 2002 Construction Project Administration Manual Revised Date: April 7, 2025

Asphalt

Attachment 11-7-1

E-Mail from District Material's Office to the PA with No. of Tests and Costs

Daniel Day

From: Daniel Day

Sent: Thursday, May 21, 2015 @ 2:49 PM

To: Howard Jump (howard.jump@dot.state.fl.us)

Cc: J. Corley; Bill Blass; etc., etc.

Subject: FIN # 41109815201 LOT 6 Resolution Results

Howard,

Attached are the Resolution results for LOT 6 on the above-mentioned project. The Resolution results **DO NOT** compare with QC results. Therefore, acceptance and payment for the LOT with respect to density will be based on Resolution results.

Cost for the Resolution testing should be deducted from the monthly estimate (see below).

For each sublot, the Resolution results for average Roadway Gmb should replace the QC results for average Roadway Gmb, and most likely change the density value, Individual Pay Factor, and the Composite Pay Factor. Any new values should be compared to the Master Production Range as well as the criteria of 334-5.9.5 to determine acceptance.

- Please do not approve the QC or RT samples for this LOT. The resolution lab will approve these samples.
- •Resolution cost (- \$31.60 per core x 9 cores = \$284.40)

Thanks
Daniel Day
Assistant District Bituminous Manager
Florida Department of Transportation
100 N. Day Road (MS 20)
Deland, Florida 33333
380-555-5550 (Office)

Topic No.: 700-000-000 Effective: July 1, 2002
Construction Project Administration Manual Revised Date: April 7, 2025

Asphalt

Attachment 11-7-2 Resolution Testing Costs on Website

The cost of resolution testing, if performed by the Department and favors the VT results, will be deducted from the Contractor's next progress estimate.

The resolution testing fees are based on the year the Contract was let. For example, if a Contract was let in January 2010 and a resolution test was done in January 2011, the January 2010 year pricing index would be used.

Resolution Testing Costs can be found on the State Materials Office Website under Documents and Publications.

Resolution Testing Costs for Contracts Let Between 2024/2025 (PDF-187KB)
... Previous Years: 23/24 22/23, 21/22, 20/21, 19/20, 18/19, 17/18, 16/17, 15/16, 14/15, 13/14


(Note: Please use the resolution testing cost sheet for the Fiscal Year the Contract was let. If a specific test is not in the list on the subjected Fiscal Year cost sheet, then use the next FY list or until you see the test.)

Florida Department of Transportation		
Resolution Tes	ting Costs	
Year 2023-2024 Rates		
Bituminous Lab		
Test Name	Quantity	Test Cost
Bulk specific gravity of Compacted Bituminous Mixtures (FM 1-T166)	Per roadway core or gyratory pill	\$57.37
Ignition Oven Method (FM5-563)	Per asphalt content	\$137.09
Max specific gravity (FM1-T209)	Per average of two flasks	\$139.19
Superpave Gyratory Compaction (AASHTO T312-04)	Per pair of gyratory pills	\$107.00
Ignition Oven (FM 5-563) and Mechanical Analysis (FM1-T030)	Per gradation	\$207.50
Soil Lab Test Name	Quantity	Test Cost
Consolidation (AASHTO T 216)	Per sample	\$353.90
Direct Shear (AASHTO T 236)	Per sample	\$301.11
Dry Gradation (AASHTO T 27)	Per sample	\$71.39
Hydrometer (AASHTO T 88)	Per sample	\$132.98
LBR (FM 5-515)	Per sample	\$349.84
Liquid Limit (AASHTO T 89)	Per sample	\$57.01
Modified Proctor (AASHTO T 180)	Per sample	\$132.70
Moisture Content (AASHTO T 265)	Per sample	\$16.37
Organic (AASHTO T267)	Per sample	\$42.95

Topic No.: 700-000-000 Effective: July 1, 2002
Construction Project Administration Manual Revised Date: April 7, 2025

Asphalt

Attachment 11-7-3 Reporting Cost of Resolution Testing in PrC



Note the purpose of the test and the associated LOT number in the Comments field. In this case, it is 'Coarse Aggregate Gradation Resolution Test for Lot 6'. The cost of the Resolution Testing will be determined by the Materials Office as shown in the email in **Attachment 11-7-1**.