

## CHAPTER 6 LUMP SUM, SQUARE YARD & TRUCK MEASURED ITEMS REVIEW

Formatted: Suppress line numbers

### 6.1 PURPOSE

Formatted: Suppress line numbers

To delineate the District Final Estimates Office (DFEO ~~DFEM~~) reviewing procedure for each item of work performed to ensure accuracy, completeness, and compliance with the Contract Documents.

Formatted: Suppress line numbers

### 6.2 PROCEDURE

Formatted: Suppress line numbers

#### 6.2.1 ITEMS OF GENERAL CONSTRUCTION OPERATIONS

Formatted: Suppress line numbers

The order in which the specific items on a contract are reviewed depends on the project and the preference of the individual doing the reviewing. These procedures will generally follow the order in which the items of pay are described in the Standard Specifications. The details for final checking items in the first section of this chapter may be arranged in three categories according to their unit of measure.

Formatted: Suppress line numbers

(A) Some Lump Sum Items are: Mobilization, Maintenance of Traffic, and Detours.

Formatted: Suppress line numbers

(1) Does the proposal include a separate item of payment for these operations? If not, they are included for payment under other scheduled items of the overall contract where no separate payment will be made for them.

Formatted: Suppress line numbers

(2) If the final contract amount is different from the original contract amount, check the contract files for a Work Order (WO) or Supplemental Agreement (SA) or other authorization of lump sum adjustment.

Formatted: Suppress line numbers

(3) Material used in the construction of detours or maintenance of traffic lump sum shall not also be measured or paid for under any pay item. (**Article Section 9-2 of the Specifications**)

Formatted: Suppress line numbers

(4) Were the dimensions (scope) used for bidding the contract revised, resulting in an increase or decrease in cost to the Contractor which would require an adjustment? (**Article-Section 9-3 of the Specifications**)

Formatted: Suppress line numbers

- (5) Verify that all materials designated to remain the property of the Department and used by the Contractor during construction have been returned and stored as directed by the ~~Project Engineer (PE)~~ Project Engineer/Administrator (PEA).  
Formatted: Suppress line numbers
- (6) Check that charges for items not returned (signs, bridges, pipe culverts, etc.) have been reflected in the final estimate, when applicable.  
Formatted: Suppress line numbers
- (B) Truck Measured Items (volume or weight): Some examples of these pay items are Commercial Materials for Driveway Maintenance, Calcium Chloride for dust control, and sandbagging.  
Formatted: Suppress line numbers
  - (1) Check the authorization by the PE PA for the material used in construction.  
Formatted: Suppress line numbers
  - (2) Verify the manufacturer's certified capacity decal attached to each side of the truck.  
Formatted: Suppress line numbers
  - (3) Ensure that the truck measurement forms verify the quantity change due to sideboard addition. **(See Figure No. 6-1, and 6-1a)**.  
Formatted: Suppress line numbers  
Formatted: Font: Bold, Italic
  - (4) Check the Tabulation Forms:  
Formatted: Suppress line numbers
    - (a) Compare the truck number to the truck capacity.  
Formatted: Suppress line numbers
    - (b) Trucks with volume changes are assigned new numbers and properly counted.  
Formatted: Suppress line numbers
    - (c) Compare the Manual Summary in the Computation Book to ensure that all required tickets are included in the summary.  
Formatted: Suppress line numbers
    - (d) Computerized summary shall be checked for keypunch errors and error messages in output, and that all output is included in a folder the Computation Book, along with all required tickets, and referenced in the Computation Book.  
Formatted: Suppress line numbers
- (C) Square yard ~~or square meter~~ items: an example of some ~~Some~~ square yard pay items are Artificial Coverings and s ~~are Artificial Coverings, Temporary Mulching, Seeding, and Performance Turf and Sodding.~~  
Formatted: Suppress line numbers  
Formatted: Strikethrough
- (1) Check plans and documents for authorized limits of construction.  
Formatted: Suppress line numbers

- (2) ~~Spot~~ Check station to station calculation of length and width or verify field chained dimensions from final measurement field book, the Final Measured Miscellaneous Form (700-050-61) or latitude and departure sheet. (See Figure No. 6-2). Plan quantity items should not be measured, only changes are to be documented and measured.
- (3) ~~Spot~~ Check the mathematics of the area calculations and the transfer of the summary to the Computation Book.
- (4) Be sure additional temporary erosion control features are paid for as ~~extra work~~ unforeseeable work in accordance per **Section 104 of the Specifications**.
- ~~(5) Check for and prevent overlapping of these items with other items scheduled for payment elsewhere in the contract.~~

Formatted: Suppress line numbers

Formatted: Font: Italic

Formatted: Font: Not Bold

Formatted: Font: Italic

Formatted: Font: Not Bold

Formatted: Font: Italic

Formatted: Font: Bold, Italic

Formatted: Font: Bold, Italic

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

## 6.2.2 Clearing and Grubbing Construction Site

Formatted: Suppress line numbers

Items of clearing and grubbing, removal of trees, stumps, buildings, structures, ~~appurtenances~~ equipment, and flexible pavement for the preparation of the overall project site are covered in this section.

Formatted: Suppress line numbers

### (A) Clearing and Grubbing (Lump Sum):

Formatted: Suppress line numbers

- (1) This item is usually checked after the surface, base, and stabilization have been finalized.
- (2) Check plans thoroughly for change in limits.
  - (a) Grade changes increasing and decreasing lateral limits of construction.
  - (b) Beginning or end of project changes from original contract.
  - (c) Lateral ditches or outfall structures ~~that were~~ that was added or deleted.
- (3) Check SA's for lump sum adjustment of original quantity.
- (4) A lump sum pay item may be adjusted without ~~an~~ an Work Order or Supplemental Agreement SA, only where the Original Plan Quantity (OPQ) for a lump sum pay item is based solely on secondary units and is expressed

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Suppress line numbers

Formatted: Strikethrough

in those secondary units in the plans, the adjusted lump sum dollar amount is equal to:

$$\frac{\text{OPQ} + \text{change in OPQ}}{\text{OPQ}} \times \text{Original lump sum \$ amount.}$$

Formatted: Suppress line numbers

Note: The original quantity as shown in the plans must be verified by the ~~PE~~ PA and corrected, if necessary, before any adjustment is made.

Formatted: Suppress line numbers

- (5) When it is apparent that items such as Maintenance of Traffic, ~~or~~ Grading, etc., have been included in the lump sum price for clearing and grubbing, any adjustment in the final lump sum price shall be negotiated and documented by a Work Order or Supplemental Agreement SA.

Formatted: Suppress line numbers

(B) Clearing and Grubbing Borrow Areas (~~Per Acre/Hectare~~):

Formatted: Suppress line numbers

- (1) For borrow pits and material pits, do not perform any clearing and grubbing to within three (3) feet inside the right-of-way line. (~~Article~~ Section 110-2 of the Specifications)

Formatted: Suppress line numbers

- (2) If the Contractor has substituted pits, pay either the area actually cleared and grubbed or the area shown ~~in~~ the plans for the corresponding borrow area, whichever is smaller.

Formatted: Suppress line numbers

- (3) Haul routes shall not be included in area for payment.

- (4) Clearing and grubbing required only for the purpose of obtaining stabilizing material or sand clay will not be paid for separately.

Formatted: Suppress line numbers

- (5) Alteration of plan quantities should comply with conditions per ~~Article~~ Section 4-3 of the Specifications.

Formatted: Suppress line numbers

- (6) No separate payment will be made for clearing and grubbing borrow areas required to be furnished by the Contractor.

(C) Removal of Existing Structures (Lump Sum):

Formatted: Suppress line numbers

- (1) ~~Overruns~~ Changes in quantities are generally documented by a Work Order or Supplemental Agreement SA. ~~If secondary units are not provided in the plans.~~

Formatted: Suppress line numbers

Formatted: Strikethrough

- (2) Check plans and source records for possible duplication of area for payment under clearing and grubbing item. Formatted: Suppress line numbers
- (3) For partial removal, check replacement dimensions and calculation for comparison. Formatted: Suppress line numbers
- (4) Check salvage tickets/Invoices for material delivered to maintenance. Formatted: Suppress line numbers  
(DEP), ten (-), Formatted: Indent: Left: 0.5"
- (65) Leaving part of a structure shown to be removed or finding greater amounts than shown in the plans may necessitate an adjustment. Adjustments are usually made by ~~ana Work Order or Supplemental SA~~ Agreements. Formatted: Suppress line numbers  
Formatted: Strikethrough
- (D) Removal of Existing Pavement (Square yard): Formatted: Suppress line numbers
  - (1) Check special provisions, general notes, plans and soil survey to verify pavement type. -Generally removal is limited to rigid pavement, sidewalk, slope pavement, ditch pavement, curb and gutter, etc. Occasionally, removal of flexible pavement is set up as a pay item. This is done through the use of a special pay item number. Formatted: Suppress line numbers
  - (2) Check plans and source records for areas such as footings, foundations, etc., that are to be included in clearing and grubbing. Formatted: Suppress line numbers
  - (3) Delineate areas of removal on final plans to reveal possible overlaps or omissions. Formatted: Suppress line numbers
  - (4) Cross check with other replacement items such as sidewalk, curb and gutter, and traffic separators to confirm final pay areas. Formatted: Suppress line numbers
  - (5) Check final measurements and calculations as recorded in the final measurement field book, miscellaneous Tabulation forms, Miscellaneous Form (700-050-61) or latitude and departure sheets. (See Figure 6-2) Formatted: Suppress line numbers  
Formatted: Font: Bold, Italic
  - (6) Check PE's PA's verification of increased or decreased quantities in the computation book. Formatted: Suppress line numbers
  - (7) ~~The Daily Work Report~~ Daily Report of Construction may be useful when an item is shown on original plans to be removed, but no quantity is shown for removal. These records are not acceptable for final pay purposes. Formatted: Strikethrough  
Formatted: Suppress line numbers

- (8) Retaining walls, ~~and~~ drainage structures ~~and flexible pavement~~ are specifically not included in the work covered under removal of existing pavement. Section 110-7 of the Standard Specifications.

Formatted: Suppress line numbers

### 6.3 LIST OF FIGURES FOLLOWING THIS CHAPTER

Formatted: Suppress line numbers

- Figure No. 6-1 .....Truck Measured Sketch Sample
- Figure No. 6-1a .....Truck Measured Sketch Sample
- Figure No. 6-2 .....Latitude and DepartureFinal  
Measurements "Miscellaneous" Sample

Formatted: Suppress line numbers



**Figure 6-1a**

Formatted: Font: Bold  
 Formatted: Centered, Suppress line numbers

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION  
**TRUCK MEASURED SKETCH (Irregular Shape Bed)**

700-050-54B  
 CONSTRUCTION  
 10/08

TRUCK NO. \_\_\_\_\_ FIN. PROJECT ID. \_\_\_\_\_  
 CONTRACTOR \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 MEASURED BY \_\_\_\_\_ DATE \_\_\_\_\_


- A. Certified Capacity provided by Contractor Subarticle (9-1.5)  
 B. The example below is for verification purposes of the truck body capacity only.  
 C. Sideboards Added  
 D. Compare B to A

**CASE II**

**A. Certified Capacity** \_\_\_\_\_ C.Y.


Verification practice by field staff

**B. Truck Body Measure** [L<sub>1</sub>: \_\_\_\_\_ + L<sub>2</sub>: \_\_\_\_\_ ÷ 2] [H<sub>1</sub>: \_\_\_\_\_ + H<sub>2</sub>: \_\_\_\_\_ ÷ 2] W: \_\_\_\_\_  
 ( ) X ( ) X \_\_\_\_\_ / 27 x 98 % = \_\_\_\_\_ C.Y.



**D. Acceptable**  
 Yes  No

**C. Sideboard Measure** ( L x W x H ) / 27 = \_\_\_\_\_ C.Y.



**A + C = NEW TRUCK CAPACITY** \_\_\_\_\_ C.Y.



**Figure 6-2**

**Formatted:** Left, Indent: Left: 0", Suppress line numbers, Tab stops: Not at 6.5"  
**Formatted:** Font: (Default) Arial, 12 pt, Bold

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION  
**FINAL MEASUREMENTS "MISCELLANEOUS"**

700-050-61  
CONSTRUCTION  
12/07  
Page No. \_\_\_ of \_\_\_

