



Florida Department of Transportation

RON DESANTIS
GOVERNOR

605 Suwannee Street
Tallahassee, FL 32399-0450

KEVIN J. THIBAUT, P.E.
SECRETARY

January 29, 2019

MATERIALS BULLETIN NO. 01-19
DCE MEMORANDUM NO. 01-19
(FHWA Approved: 1/29/2019)

This Memo has Expired

**TO: DISTRICT MATERIALS AND RESEARCH ENGINEERS
DISTRICT CONSTRUCTION ENGINEERS**

Timothy J

FROM: Timothy Ruelke P.E., Director, Office of Materials
Amy Tootle, P.E., State Construction Engineer

Ruelke

Amy C Tootle

Digitally signed by Timothy J Ruelke
Date: 2019.01.29 17:08:31 -05'00'

Amy C Tootle
FL PE #66414
2019.01.29 15:59:41-05'00'

COPIES: Courtney Drummond, Amy Tootle, Ananth Prasad, Chad Thompson, Nick Finch, Jose Armenteros, Richard DeLorenzo, Patrick Carlton, Thomas Frank, Tim Counts

SUBJECT: ARGOS TAMPA SLAG PLANT - TAMPA, FL (SLAG01)

In order to prevent concrete placement delays on ongoing construction projects due to the shortage of slag cement from the Argos Tampa Slag Plant - Tampa, FL (SLAG01), concrete producers may request the Department to implement a modified mix design approval process. This memorandum will allow placement of concrete prior to receiving formal Department mix design approval, and is only applicable for replacing Argos Tampa Slag Plant (SLAG01) slag cement incorporated in currently approved concrete mix designs assigned to current projects. The Contractor/Producer assumes all risks involved for ensuring that plastic and hardened properties are in compliance with the specifications at the time of placement.

If the modified mix approval process is used, the following requirements must be met:

1. District Materials Office personnel will ensure the replacement mix contains the same component materials and quantities as the replaced mix and only cement substitution is permitted. The new mix must meet the same requirements as the old mix, including yield, plastic and hardened properties. Adjustments to weights according to specific gravity of replacement cement chosen will be permitted as long as the replacement mix equals the original mix regarding application and environmental conditions. All materials must be from an approved source.
2. District Materials Office personnel will submit the replacement mix design to the State Materials Office similar to the material substitution procedure found in Materials Manual, Section 9.2, Vol. II.
3. The State Materials Office will assign a new design mix number with the old design mix number referenced in the mix design comments.

MATERIALS BULLETIN NO. 01-19

DCE MEMORANDUM NO. 01-19

Page 2

4. At the first job-site placement of the new mix, for each project, the Concrete Producer's ACI certified technician or the Contractor's QC certified CTQP inspector will cast a minimum of three 4x8 cylinders to be tested at 28-days by the Concrete Producer's or the Contractor's qualified laboratory.
5. District Materials Office personnel will submit the Producer's 28-day results to the State Materials Office. Whenever overdesign strength is reached, the new design mix will be fully approved as a new stand-alone permanent mix for FDOT use.

This memorandum does not waive any specification requirements but simply allows an expedient means to approve mix designs. It is in effect until **July 31, 2019**. After that date, the normal mix design approval process will be in effect. It serves as a blanket approval to process this change as a no cost specification revision and shall be attached to the work order or supplemental agreement required for its processing.

Should you have any questions please contact Jose Armenteros, State Materials Office at 352-955-6666, or Pat Carlton, State Materials Office at 352-955-6676.

TR/ja