



Purpose

- Educate about structures construction
- Review Specifications and CPAM
- Much to know, remember, and keep track of so:

CPAM Sections

- 8.4 Shop and Erection Drawing Process
- 8.11 Contractor Initiated Submittals
- 10.2 Prestressed/Precast Concrete Components
- 10.3– Concrete Construction
- 10.4 Coatings & Asbestos Removal, Handling and Disposal and Structural Steel Coating Issues
- 10.6 Underwater Bridge Construction Inspection
- 10.7 Post-tensioned Bridges
- 10.9 Structural Steel & Miscellaneous Metal Components
- 10.10 Bridge Construction Issues that Must Involve State Construction Office Staff
- 10.11 General Structures Construction Issues

CPAM 8.4 Shop and Erection Drawings Process

- Nine (9) Item Shop Drawing Tracking Log (number, status, status of EOR review, etc.)
- Schedule of submittals required within 60 days of the start of contract
- At weekly progress meetings Contractor reports latest shop drawing priorities, updates

CPAM 8.4 Shop and Erection Drawings Process

11. Shop Drawings: A shop drawing is a drawing or set of drawings produced by the contractor, supplier, manufacturer, subcontractor, or fabricator for prefabricated components. Shop drawings also include all working drawings, erection plans, associated trade literature, material cut-sheets, calculations, schedules, erection manuals, geometry control manuals and other manuals and similar documents submitted by the Contractor to define some portion of the project work. The type of work includes both permanent and temporary works as appropriate to the project.

CPAM 8.11 Contractor Initiated Submittals

- 3 Categories of Submittal:
 - Request for information (RFI)
 - Request for Correction (RFC)
 - Request for Modification (RFM)
- Process/procedure covered in CPAM
- 17-item tracking log for each submittal

CPAM 10.3 Concrete Construction

- Spec. 400-21, Disposition of Cracked Concrete: <u>the</u> <u>number of cracks, average crack width, length of</u> <u>cracks taken into account</u>
- CPAM Section 10.3.5, Mass Concrete Control Plan (MCCP)
- CPAM Section 10.7, Crack and Joint Inspection of Post-Tensioned Bridges



CPAM 10.3 Concrete Construction

CPAM 10.3 Concrete Construction

- Crack inspection 3X: 1) after casting, 2) all dead loads, 3) all live loads
- Early discovery allows crack monitoring and correction of other components to prevent more cracks
- Crack Maps denoting length, width, depth, location
- Disposition of Cracks:
 - Structural or
 - Non-structural—Engineer makes the determination!

CPAM 10.4 Paint & Asbestos Removal, Handling & Disposal and Structural Steel Coating Issues

- Hazardous but also potentially hazardous waste:
 - Asbestos Containing Material (ACM)
 - Lead
- Coating Concerns:
 - Surface preparation
 - Bolts, caulking gaps and seams-stripe coating
 - Faying surfaces
 - Testing for chloride, sulfate and nitrate concentrations
 - Containment
- Discuss concerns at pre-operations meetings

CPAM 10.4 Paint & Asbestos Removal, Handling & Disposal and Structural Steel Coating Issues

- Blast media for paint removal/surface prep
- Ferrous (top)
- Steel grit (below)







CPAM 10.4 Paint & Asbestos Removal, Handling & Disposal and Structural Steel Coating Issues

Stripe coating of irregular surfaces



CPAM 10.4 Paint & Asbestos Removal, Handling & Disposal and Structural Steel Coating Issues

Containment and Coating/Metallizing

CPAM 10.6 Underwater Bridge Construction Inspection

- Initial inspection of voided concrete/cylinder piles
- Other pile types, Engineer makes decision
- Final underwater inspections for all projects by:
 - FDOT prequalified Consulting Firm (Maintenance)
 - FDOT Structures Maintenance


CPAM 10.9 Structural Steel and Miscellaneous Metal Components

- Records must be kept of:
 - Job Inspection Snug Tight Torque Test for Bolts
 - Rotational Capacity Test for Bolts (ROCAP)
 - Steel Girder Shear Connector Bend Test
- Fabrication schedule
- Consultant Inspection of fabrication
- Non-compliances of fabricated components



CPAM 10.9 Structural Steel and Miscellaneous Metal Components

CPAM 10.9 Structural Steel and Miscellaneous Metal Components





CPAM 10.9 Structural Steel and Miscellaneous Metal Components

CPAM 10.10 Bridge Construction Issues that Must Involve State Construction Office Staff

- Complex or Category II Bridge issues:
 - Steel
 - Segmental
 - Movable
 - Post-tensioned
- Changes to As-Built condition
- Modification of Plans
- Non-compliances of Steel/Prestressed items

CPAM 10.11 General Structures Construction Issues

- Notifying District Structures Maintenance Engineer of in-service dates and acceptance inspections
- As-Bid vs. As-Built Load Ratings-changes?
- Department-owned temporary bridging

Specification Sections

- 5 Control of the Work
- 346 Portland Cement Concrete
- 400 Concrete Structures
- 450 Precast Prestressed Concrete Construction
- 460 Structural Steel and Miscellaneous Metals
- Not all Structures Specs specifically addressed here

Spec 5—Construction Affecting Public Safety

- Construction Affecting Public Safety
 - Signed and sealed erection plan prior to erection
 - Daily inspections of structure
 - Specialty Engineer certification prior to opening facility below
- Signed and sealed stability calculations
- Table of Temporary Bracing Details

GE 3 OVERTURNING MOMENT AT EACH BRACE ⁶ (KIP-FT)
MOMENT AT EACH


Spec 5—Construction Affecting Public Safety



Spec 5— Construction Affecting Public Safety

Spec 346—Plastic Properties

- Every load requires water cement ratio (w/c) calculation
- Slump test when there is question of water contentconsistency must be observed for each truck
- When water is added at the site, truck must be retested
- Test trucks after rejected truck for slump—including the first adjusted truck and begin a new LOT
- Also included are temperature, air entrainment
- VT/CEI/Engineer verifies roughly once per four LOTs



Spec 346—Concrete Class, Sampling, Transit Time

- Department-approval of reduced sampling frequency
- Higher class concrete can be used for lower strength
- Transit Time is the time for all concrete to be discharged from the truck taken from when water is first introduced
- Placement Time of 15 minutes after Transit Time to get concrete to its final position; time extension may be requested

Spec 346— Delivery Ticket

			TITAN AN		NC		E	PINDES
		APPENDIX "A"					1	1232 2824
F.D.O.T. Concrete Deliver				ry Ticket Stru	ctural Concr	ete	9	Stratto
Financial Project No.		433108-6-52-01 Ticket /				79311		
Plant No.		93-363		Date		03/05/19		
Concrete Supplier		DELRAY R/M		Delivered to		PRINCE		
Phone Number		561-278-3984	-			Phone #:		
Address		1300 S. SWIN	TON AVE, DELRAY	3CH, FL 3344	4	Address:	ss: 1-95 NB ON PALMETTO PAR	
					Tarm	ac Mix No:	D4054400	
Truck	No	1 (DOT Class	-	DOT Mix No.	_		bic yardsThis
15060			CL IV		06-0544		Load:	
		Time Loaded		Mixing Revolutions			Cubic vards	
Allowable Jobsite Water Addition: 21.80 gal.		H:51 - 420		70		Today: 3.00		
		3:29 PM						
Chloride Test Result	8	122	0		Chioride Te	st Date		1/0/1900
Cement Type		TYPE I/II	1,760	LBS	APOLLO BEAC	4 - ING REND	Fly ash or Slag FLY/ASH	440
	DLEY - PENNSU		Amount			Source	Type	Amount LBS
		_	57 Rock			A	ir Entrainment Ad	
Coarse Agg.	87-339	1.4%	5,060	LBS	BASELA	ir entrainment		27
	Pit#	%Moisture	Amount		-	Source		Amount OZS
	05-045	5.6%	Ortona 3.480	LBS			Admixture 961R	132
Fine Agg	05-045 Pit#	5.6% %Moisture	3,480 Amount	LBS	BASE/1	Source	961R Type	132 Amount OZS
Batch Water GAL	Pit# Metered Wat		Total water	GAL		Source	Admixture	Amount OZS
50	3		53	53		BASE	0	0
ICE	0	GAL	Truck Water	0	GALS	Source	Type	Amount OZS
1012	-				0.40		Admixture	
						BASE	Туре	0 Amount OZS
Insurance of this tick Specification require	rments for Structur		concrete batched was	produced and	information re	corded in a	compliance with t	he Department
							RI	show
	CTOP Technician i		iber		Signature of	Plant Ope	rator	spin
	H TOP Technician i		iber	Number of 1	Signature of evolutions up			sjuur
Arrival Time at job Total Water added a	4:30	dentification Num	iber ided at the job site			on arrival a	t job site.	sjuw
Arrival Time at job Total Water added a gallons) Time concrete comp 4 : 4 7	4.30 1 job site (dentification Num	ided at the job site	Additional n	evolutions up	on arrival a	t job site.	3/~~~
Arrival Time at job Total Water added a gallons) Time concrete comp	4.30 1 job site (Admixtures ad (ounces)	ided at the job site	Additional n	evolutions up 125 iixing revolution r of revolution 165	on arrival a) ons with wa	t job site.	2

Issuance of this licket constitutes certification that the maximum specified water cementitious ratio as not exci compliance with Department specification requirements. ded and the batch was delivered and placed in


CC4A 016Q

236232068

Spec 346—Mass Concrete

- Mass Concrete Control Plan
- Temperature readings every 6 hours until:
 - Max temperature differential (35°F max) and
 - Max temperature (180°F max) and diminishes
- Controls remain until core temperature within 50°F of ambient
- Specialty Engineer must be engaged to advise if issues arise

Spec 346---Mass Concrete





Spec 346—Mass Concrete



Spec 400—Footing Placement

- Cofferdam preparation—seal concrete or precast "bathtub"
 - Water seepage
 - Standing water prior to concrete placement
 - Primary pump capacity plus backup pump
- 20 inch or less lift thickness when placing concrete
- Mass concrete monitoring devices protected during concrete placement




Spec 400-Deck Placement

- Placement sequence/ direction
- Screed demonstration
- Curing compound applied within 120 minutes of initial placement
- Compound spread rate/quantity reported to the Engineer
- Placement and maintenance of curing blankets (over barrier)




Spec 400—Deck Placement



Spec 400—Deck Placement

- Evaporation rate determined by:
 - Air temperature, relative humidity
 - Concrete temperature
 - Wind Velocity (15 mph max)
- If evaporation rate exceeds <u>0.1 lbs/ft²/hr</u> including:
 - Evaporation retarder
 - Water fogging
 - Chilled mix water
 - Wind screens



Specs 400/450— Camber

- Monthly camber estimates in the precast yard
- Camber tolerance of 1 inch from design camber in Plans
- Contractor takes appropriate actions (400-7.13.1) to get girder stirrups to "fit" with the deck

Specs 400/415/460/502— Rebar, SIP Forms, Shear Connectors

- Field welding permitted per Spec 460 if on the Plans
- No welding of SIP forms to flanges
- Bending of reinforcement with Engineer's permission
- Store rebar above ground
- Shear stud installation in the field with bend testing





Spec 6—Buy America

- Buy America applicable to steel incorporated in the finished work, not the temporary condition
- Not just for Projects with FHWA funding during Construction
- Included if the corridor had FHWA funding through PD&E
- Mill certs need state "Made in USA"

CMC STEEL SOUTH CA 310 New State Road Cayce SC 29033-3704		1	LINA CERTIFIED MILL TEST REPORT For additional copies call 800-637-3227			We hereby certify that the test are accurate and conform to the rep Richard S. Ray - CMC			
									Qu
).:2071956 I: REBAR 25MM (#8) 60'0" 420/60 ASTM A615-18e1 Gr 420/60 .TE: 11/11/2018 I: 11/10/2018 : 11/10/2018 / 071956D036		S O L D T O		S H P T O				Delivery#: BOL#: CUST PO#: CUST P/N: DLVRY LBS DLVRY PCS	
Character	istic	Value		Characteristic		Value			Characteristic
Yield Strength to Id Strength test 1 (Tensile Strength 1 Isile Strength 1 (mo Elongation to S :	netri est 1 etric)	0.41% 0.85% 0.013% 0.21% 0.27% 0.28% 0.12% 0.043% 0.000% 0.001% 0.001% 0.001% 0.001% 0.0015% 64.6ksi 446MPa 104.0ksi 717MPa 13%		Elongation Gage Lgth te Bend Te Rebar Deformation Avg. Sj Rebar Deformation Max. Rebar Deformation Max. Bend Test Diam	st 1 paci eigh Gap	0.063IN 0.161IN		"Material *100% m *EN1020- "Contains "Contains "Manufac of the pia "Meets th "Warning known to or other i	true of the material is fully killed alted and rolled in th 1:2004 3,1 compliant no weld repair no Metrcury contam tured in accordance rit quality manual e"Buy Americal" (are This productive harm. F #6Warnings.c.a.gov
				03/28/2019 21:39:2 Page 1 OF 1	23				

Specs 400/460/461-Bearings, Anchor Bolts

- Inspection of bearings for deformation and general condition
- Anchor bolt hole misalignment
- Expansion and contraction from temperature






Spec 460—Material

- The Department requires structural steel superstructures to be fabricated with weathering steel if 4 miles from the coast or greater
- Painting not required, reduction in maintenance costs over the life of the bridge
- Exceptions permitted but must be approved by the Chief Engineer, requiring justification by the District



Spec 460—Structural Steel and Miscellaneous Metals

Weathering steel girders




Spec 460—Bolting


- Turn-Of-Nut method
- ROCAP/Job-Inspection Snug Tight Torque performed in the field
- Bolt tightening sequence
- Erection Plan
- DTI's Direct Tension Indicators

Spec 460—Bolting

Bolt Tightening Sequence



The Sequence of Tightening is <u>CRITICAL</u> →Most rigid, to least rigid




Spec 460 Skidmore-Wilhelm Tension Calibrator

Spec 460—Turn of Nut Bolting



Spec 460— Bolting

 Checking Snug Tight Tension with a Calibrated Torque Wrench



Contractor's Engineer of Record

Work Type	Contractor's Engineer of Record	Department Approved Specialty Engineer	Specialty Engineer
Re-design	Yes	No	No
Cost Savings Initiative Proposal	Yes	No	No
Details of the permanent work not fully detailed in the plans	Yes	Yes	Yes
Design and details of the permanent work declared to be minor or non-structural including minor repairs	Yes	Yes	Yes
Design and details of the permanent work declared to be major or structural including major repairs	Yes	Yes*	No
Design and drawings of temporary works, such as falsework, formwork, etc.	Yes	Yes	Yes

*The work must also be checked by another Department Approved Specialty Engineer

Qualifications and Certifications



CTQP Concrete Field <u>Technician</u> - Level I



CTQP Concrete Field Inspector - Level II



CTQP Grouting Technician - Level I & 2



CTQP Post-Tensioning Technician - Level I & 2



ACI, PTI, and ASBI issue certifications for successful completion



ASBI Certification in Flexible Filler Injection



Technicians certified by these agencies



Not considered qualified for FDOT work until qualification by CTQP

Training and Reference Tools

- Office of Construction and CTQP Websites contain most structures construction training materials including piles and drilled shafts as downloads
 - <u>https://www.ctqpflorida.com/</u>
- Structures Related Websites:
- <u>State Construction Office, Structures Webpage</u>
 - (<u>http://www.fdot.gov/construction/</u>)
- <u>State Structures Design Office Website</u>
 - (<u>http://www.fdot.gov/structures/</u>)



Contact

- State Construction Structures Engineer
 - <u>david.wagner@dot.state.fl.us</u>
 - (850) 414-4141

Construction Structures Website:

• <u>https://www.fdot.gov/construction/structures/Structures.shtm</u>