



2025 CONSTRUCTION ACADEMY STRUCTURES SESSION





#### **PURPOSE**

- Target Audience: FDOT staff & Consultant Project Administrators
- Educate about structures construction
- Review Specifications and CPAM
- Review and Incorporate lessons learned



## IMPORTANT TERMS & DOCS

- Construction Project Administration Manual (CPAM)
- Standard Specifications for Road and Bridge Construction (Division I and II)
- FDOT Self Study Courses (Structures Inspection and Critical Construction Issues)
- EOR, CEOR, Department Approved Specialty Engineer, Engineer



## **CPAM SECTIONS**

- 8.4 Shop and Erection Drawing Process
- 8.11 Contractor Initiated Submittals
- 10.2 Prestressed/Precast Concrete Components
- 10.3 Concrete Construction
- 10.4 Coatings & Asbestos Removal, Handling and Disposal and Structural Steel Coating Issues
- 10.6 Underwater Bridge Construction Inspection
- 10.7 Post-tensioned Bridges
- 10.9 Structural Steel & Miscellaneous Metal Components
- 10.10 Bridge Construction Issues that Must Involve State Construction Office Staff
- 10.11 General Structures Construction Issues

### CPAM 8.4 SHOP AND ERECTION DRAWINGS PROCESS



- Nine (9) Item Shop Drawing Tracking Log (number, status, status of EOR review, etc.)
- Schedule of submittals required within
   60 days of the start of contract
- At weekly progress meetings
   Contractor reports latest shop
   drawing priorities, updates
- EOR QC checkprints required

11. Shop Drawings: A shop drawing is a drawing or set of drawings produced by the contractor, supplier, manufacturer, subcontractor, or fabricator for prefabricated components. Shop drawings also include all working drawings, erection plans, associated trade literature, material cut-sheets, calculations, schedules, erection manuals, geometry control manuals and other manuals and similar documents submitted by the Contractor to define some portion of the project work. The type of work includes both permanent and temporary works as appropriate to the project.

#### CPAM 8.4 SHOP AND ERECTION DRAWINGS PROCESS

			Table 5-1			
			d Review Requ			
Shop Drawing for:	Originated by Specialty Engineer Not Signed and Sealed	Originated by Detailer Not Signed and Sealed	Originated by Specialty Engineer Signed and Sealed	Originated by Contractor s EOR Signed and Sealed	Requires Review, QA/QC Check prints and disposition stamp by Design EOR	Requires Construction IPR and signed and sealed Certification Letter
Steel Fabrication Drawings		Originator			Reviewer	
Steel Erection Plan			Originator		Reviewer	
Geometry Control Manual				Originator	Reviewer	
Segmental Erection Manual				Originator	Reviewer	Reviewer <sub>5</sub>

#### SPECS 5-1.4.2 SHOP DRAWINGS SUBMITTAL AND REVIEW REQUIREMENTS


### **CPAM 8.11 CONTRACTOR INITIATED SUBMITTALS**

- Categories of Submittal:
  - Request for information (RFI)
  - Request for Correction (RFC)
  - Request for Modification (RFM)
  - Nonconformance Report (NCR; aka RFC)
  - Engineering Analysis Report (EAR)
- Process/procedure covered in CPAM
- 17-item tracking log for each submittal



### CPAM 10.3 CONCRETE CONSTRUCTION

- Spec. 400-21, Disposition of Cracked Concrete: the number of cracks, average crack width, length of cracks taken into account
- CPAM Section 10.3.5, Mass Concrete Control Plan (MCCP)
- CPAM Section 10.7, Crack and Joint Inspection of Post-Tensioned Bridges







### CPAM 10.3 CONCRETE CONSTRUCTION


#### CPAM 10.3 CONCRETE CONSTRUCTION

- 10.3.6: Crack inspection 3X: 1) after casting, 2) all dead loads, 3) all live loads
- Early discovery allows crack monitoring and correction of other components to prevent more cracks
- Crack Maps denoting length, width, depth, location
- Disposition of Cracks:
  - Structural or
  - Non-structural—Engineer makes the determination!


### CPAM 10.4 PAINT & ASBESTOS REMOVAL, HANDLING & DISPOSAL AND STRUCTURAL STEEL COATING ISSUES

- Hazardous but also potentially hazardous waste:
  - Asbestos inining Material (ACM)
  - Lead
- Coating Concerns:
  - Surface preparation
  - Bolts, caulking gaps and seams—stripe coating
  - Faying surfaces
  - Testing for chloride, sulfate and nitrate concentrations
  - Containment
- Discuss concerns at pre-operations meetings









CPAM 10.4 PAINT & ASBESTOS REMOVAL, HANDLING & DISPOSAL AND STRUCTURAL STEEL COATING ISSUES

CONTAINMENT

# CPAM 10.6 Underwater Bridge Construction Inspection


- Initial inspection of voided concrete/cylinder piles
- Other pile types, Engineer makes decision
- Final underwater inspections for all projects by:
  - FDOT prequalified Consulting Firm (Maintenance)
  - FDOT Structures Maintenance

# CPAM 10.9 Structural Steel and Miscellaneous Metal Components

- Records must be kept of:
  - Job Inspection Snug Tight Torque Test for Bolts
  - Rotational Capacity Test for Bolts (ROCAP)
  - Steel Girder Shear Connector (shear studs) Bend Test
- Fabrication schedule
- Consultant Inspection of fabrication
- Non-compliances of fabricated components

CPAM 10.9 STRUCTURAL STEEL AND MISCELLANEOUS METAL COMPONENTS





# CPAM 10.9 STRUCTURAL STEEL AND MISCELLANEOUS METAL COMPONENTS



CPAM 10.9 STRUCTURAL STEEL AND MISCELLANEOUS METAL COMPONENTS

# CPAM 10.10 Bridge Construction Issues that Must Involve State Construction Structures Engineer

- Complex or Category II Bridge issues:
  - Steel
  - Segmental
  - Movable
  - Post-tensioned
- Changes to As-Built condition
- Modification of Plans/ Cost Savings Initiatives
- Non-compliances of Steel/Prestressed items

# **CPAM 10.11 General Structures Construction Issues**

- Notifying District Structures Maintenance Engineer of inservice dates and acceptance inspections
- As-Bid vs. As-Built Load Ratings—changes?
- Department-owned temporary bridging

#### SPECIFICATION SECTIONS

- 5 Control of the Work
- 346 Portland Cement Concrete
- 400 Concrete Structures
- 450 Precast Prestressed Concrete Construction
- 460 Structural Steel and Miscellaneous Metals
- Not all Structures Specs specifically addressed here

# **Spec 5—Construction Affecting Public Safety**

- Construction Affecting Public Safety
  - Signed and sealed erection plan prior to erection
  - Daily inspections of structure
  - Specialty Engineer certification prior to opening facility below
- Signed and sealed stability calculations
- Table of Temporary Bracing Details




### SPEC 5—TEMPORARY BRACING

# Spec 346—Plastic Concrete Properties

- Every load requires water cement ratio (w/c) calculation
- Slump test when there is question of water content consistency must be observed for each truck
- When water is added at the site, truck must be retested
- Test trucks after rejected truck for slump—including the first adjusted truck and begin a new LOT
- Also included are temperature, air entrainment
- VT/CEI/Engineer verifies roughly once per four LOTs

### SPEC 346— PLASTIC PROPERTIES



# Spec 346—Concrete Class, Sampling, Transit Time


- Department-approval of reduced sampling frequency
- Higher class concrete can be used for lower strength
- Transit Time is the time for all concrete to be discharged from the truck taken from when water is first introduced
- Placement Time of 15 minutes after Transit Time to get concrete to its final position; time extension may be requested

gallons )  Time concrete completely discharged Time admisture added Total number of revolutions  4 4 7 Find American Stump  Finited Stump  Finited Stump  Finited Concrete temp  Finited Concrete temp  Finited Finited Concrete temp  Finited				500000000	IDIX "A"		7.10	inte Red
Part No.  Cencrete Supplier  DELRAY RIM.  Delivered to: PRINCE  Phone Number  561 278-3884  Address  1300 S. SWINTON AVE. DELRAY BCH. FL 33444  Address  Tamed Mix No: D4004460  Total No.  Total No.  Total No.  Total No.  DOT Class  Total No.  DOT Class  Total No.  Total No.  Total No.  Total No.  Total No.  Total No.  DOT Class  Total No.  DOT Class  Total No.  Total No.  Total No.  Total No.  Total No.  Total No.  DOT Class  Total Many Recorders  Total Many Recorders  Total No.  Clabe years The  Loed: 3.00  Allowable Johnson Water Addition:  21.80  Allowable Johnson Water Addition:  Total No.  Coarse Agg.  87-309  Total Y. PENNSUCO  Total Years  No.  Total No.					y Ticket Stru	actural Concrete	0.	mother
Cencrete Supplier Phone Number  1309 S. SWINTON AVE. DELRAY BCH. FL.33444  Address: 186 NO. PALMETTO PARK RICHT Tammac Mix No. 190544600  CL. IV. 06-0544  Lovet 3.00  Allowable Jobatia Water Addition: 3:29 PM  Time Looded Of Rooman Provided Trade of Park Date Private Plant Stage Addition: 3:29 PM  Today 3.00  Comerci Type UII 1,760  LBS  WOLD BLOCK HOLD BL	Financial Project No	b.	433108-6-52-0	11 2		Ticket #	11	79311
Phone Number    3691-278-3884   Phone #F   Address   150 NS OWN PALMETTO PARK RIGHT	Plant No.		93-363		15.	Date	0	3/06/19
Address	Concrete Supplier		DELRAY R/M			Delivered to: P	RINCE	
Truck No. 15060 CL IV 06-0544 Load: 3,00 Allowable Jobate Water Addition: Time Loaded 70 Today: 3,00 Allowable Jobate Water Addition: 3,29 PM Chloride Test Results 0 Chloride Test Date 17,00 Fy an or Slag. Type 17 YPE W1 1,760 WEDEY: PRINSUO 50 Force 17 Pg Amount LISS 18 Force 18 F	Phone Number		561-278-3984			Phone #:	10411607	
Truck No. 15060 CL IV 06-0544 Load 3.00  Time Loaded 3.00  Allocatios Jobatic Water Addition: 27.50 gas. Type IVI 1,760 LBS 4000000000000000000000000000000000000	Address		1300 S. SWIN	TON AVE, DELRAY B	CH, FL 3344	H Address: I-	95 NB ON PALM	ETTO PARK RIGHT
Truck No. 15060 CL IV 06-0544 Load 3.00  Time Loaded 3.00  Allocatios Jobatic Water Addition: 27.50 gas. Type IVI 1,760 LBS 4000000000000000000000000000000000000						Tarmac Mix No: D	4054400	
15060   CL IV   06-0544   Loud   3.00	True	ok No	1 .	IOT Class	T			vands This
Acceptance Sturns  Acceptance St								
Chronic Tereputits 0 Chronic T		-	Th	me Loaded	Mi	xing Revolutions	Cu	bic yards
Corrorat Type IVI 1,760 LBS Around Successful Type Around IVI LBS Around IV							Today:	3.00
Type IVI 1,769 LBS Amount LBS Ply and recision processes of the Store of Ply and recision Ply and recision processes of the Store of Ply and recision Ply and recision processes of the Store of Ply and recision			3					
Type   TYPE UII   1,769   LS	Chloride Test Resul	its		0			Fly ash or Slag	1/0/1900
Coarse Agg. 87-339 1-4% 5-5060 LBS 8-827 / Averagement Agriculture					LBS	APOLLO BEACH - BIG BEND	FLY/ASH 440	
Coarse Agg. 87:399 1.4% 5.060 LBS	М	EDLEY - PENNSU	co		_		Type Amount LBS Entrainment Admix	
Fire Agg 95-145 5.0% 3.460 LIS BASE Type A. It. D 9918 132  Batich Water GAL Metered Water CAL Metered Water CAL Total water GAL Source Type Amount OZS Source T	Coarse Agg.	87-339	1.4%		LBS			
Fise Agg 9 94-145 5-0% 3,489 USS RAFF 7 Pipe A R.D 9019 1 132  Ballon Wester GAL Metered Water GAL Total water GAL 5-3 BASF 0 0 0  ICE 0 QAL Truck Water 0 QAL Source Type Amount QZS BASF 0 0 0  BASF 0 0 0 0  BASF 0 0 0 0  BASF 0 0 0	Palling No. 1000.1	Pit #	%Moisture			Source		Amount OZS
Batch Water GAL Metered Water GAL 53 water GAL 53 Sale April Open Sale Additional Metered Water GAL 53 Sale Sale April Open Sale Additional Metered Water GAL 53 Sale Sale Sale O O O Sale Sale Sale Open Sale Sale O O O Sale Sale Sale Open Sale Sale O O O Sale Sale Sale Open Sale Sale Open Sale Sale Sale Sale Open Sale Sale Open Sale Sale Sale Sale Sale Sale Sale Sale	Fine Ann	05.045	5.6%		IBS	BASE/Torsi A. B. D.		132
So S S S S S S S S S S S S S S S S S S	-	Pil II	%Moisture		-		00.01	
Total Water added all job site  ( Administure added all job site  ( CTOP Technical medical policy and policy a			er GAL			DARE		
BASE Advisture  BASE Source Type Amount OZS  Insurance of this ticket constitutes certification that the concrete batched was produced and information recorded in compliance with the Department Specification requirements for Structural Concrete.  B65072155  CTOP Technican identification Number  Signature of Plant Operator  Amount Time all job bits  [ Administrates added at the job site   Additional maining revolutions with waster added.			CHI					
Source   Type   Amount   OZS	IGE	- 0	GAL	Frock water	- 0	GALS Source		AIRSUN OZS
Introduced of this licket constitutes certification that the concrete batched was produced and information recorded in complaince with the Department Specification requirements for Structural Concrete.  B865072155  CTOP Technician destillation Number  Annual Time all job Sets  CTOP Technician destillation Number  Annual Time all job Sets  Administrate added at job site (automatical structure) and the plot sets (counces)  Total Water added at job site (automatical structure) added to the job sets (counces)  Times concrete completely discharged  Times administrate added at the job sets (sold number of revolutions with water added to conceive temp)  Initial Sturp  Acceptance Sturp  Acceptance Sturp  Acceptance Sturp  Acceptance Sturp  Acceptance Sturp  Acceptance site temp  Acceptance with Ratio  37  Issuance of this licket constitutes certification that the maximum specified water cementitious ratio as not exceeded and the betch was delivered and placed a complainner with Department specification requirements.						67101	3200000000	
Amend Time at job 4 3	Insurance of this tic	xet constitutes certi	fication that the o	oncrete batched was p	roduced and	information recorded in cor	mpliance with the	Department
Total Water added at job site (authors)  Administrates added at the job site (authors)  Time concrete completely discharged Time administrate added Total number of revolutions  4.4.4.7.5 Initial Stump  Acceptance Air  Acceptance Air  Acceptance Concrete temp  Acceptance Concrete temp  Acceptance Air  Acceptance of this lickel constitutes critication that the maximum specified water comentitious ratio as not exceeded and the batch was delivered and placed a compliance with Department specification requirements.	Specification requir	rements for Structur	72155	= 1 =27	roduced and		mpliance with the	Department
pallons)  Trace conceles completely discharged  Life Acceptance Completely discharged  Trace administry added  Total number of recolutions  Life Acceptance Air  Statist Concrete temp  Acceptance Stump  Acceptance Air  Acceptance Air  Acceptance Concrete temp  Acceptance wire Ratio  37  Issuance of this licket constitutes certification that the maximum specified water commentious ratio as not exceeded and the balch was delivered and placed in complaince with Department specification requirements.	Specification requir	rements for Structur	72155	= 1 =27		Signature of Plant Operatevolutions upon arrival at j	mpliance with the	Department
H : 4 7  Initial Stump 4 0  Initial Air 1, 2 5  Initial Concrete temp  Acceptance Stump  4 Acceptance Air 2 Acceptance concrete temp  Acceptance Stump  4 Acceptance Air 2 Acceptance concrete temp  Acceptance wire Ratio  3 2  Issuance of this licket constitutes certification that the maximum specified water camentitious ratio as not exceeded and the belich was delivered and placed acceptance with Department specification requirements.	Specification requir	B650	al Concrete. 72155 dentification Num	ber	Number of r	Signature of Plant Operatevolutions upon arrival at j	npliance with the	Department
Initial Sturrey 4.77 Initial Air 7, 7.5 Initial concrete temp Solidal wird Ratio 3.2 Acceptance Sturrey 4.7 Acceptance Air 2.0 Acceptance concrete temp Acceptance wird Ballow 3.3 Acceptance of this locket constitutes certification that the maximum specified water committee us ratio as not exceeded and the ballow was delivered and placed a compliance with Department specification requirements.	Specification requirements  Arrival Time at job.  Total Water added:	B650	72155 dentification Num	ber	Number of r	Signature of Plant Operatevolutions upon arrival at j	npliance with the	Department
Acceptance Stump  Acceptance Air  Acceptance Air  Acceptance concrete temp  Acceptance with Ratio  3.7  Issuance of this ticket constitute conflication that the maximum specified water comentitious ratio as not exceeded and the batch was delivered and placed a complaince with Department specification requirements.	Arrival Time at job  Total Water added a	B650 CTOP Technician is at job site	72155 dentification Num  Admixtures add (ounces)	ber ded at the job site	Number of Additional n	Signature of Plant Operative of Plant operative of Plant operative at the Plant operations with water of Plant operations with water operations with water operations of Plant operations op	npliance with the	Department
Issuance of this licket constitutes certification that the maximum specified water cementitious ratio as not exceeded and the belich was delivered and placed a compliance with Department specification requirements.	Arrival Time at job  Total Water added agallons )  Time concrete comp	B650 CTOP Technician is at job site	72155 dentification Num  Admixtures add (ounces)	ber ded at the job site	Number of Additional n	Signature of Plant Operative of Plant operative of Plant operative at the Plant operations with water of Plant operations with water operations with water operations of Plant operations op	npliance with the	Department
Issuance of this licket constitutes certification that the maximum specified water cementitious ratio as not exceeded and the belich was delivered and placed a compliance with Department specification requirements.	Armval Time at job  Total Water added agallons )  Time concrete comm	B650 CTOP Technician is at job site	72155 dentification Num  Admixtures add ( ounces ) Time admixture	ber ded at the job site	Number of a	Signature of Plant Operar revolutions upon arrival at j \	not ob site.	Department
Issuance of this ticket constitute conflication that the maximum specified water comentitious ratio as not exceeded and the batch was delivered and placed in complaince with Department specification requirements.	Armval Time at job Total Water added agallons ) Time concrete community Time concrete concrete community Time concrete community Time concrete concrete community Time concrete concret	B650 CTOP Technician is at job site	72155 dentification Num  Admixtures add ( ounces ) Time admixture	ber ded at the job site	Number of a Additional ri	Signature of Plant Operar revolutions upon arrival at julians revolutions with water arrival at julians revolutions with water of revolutions.	nor added.	<u></u>
compliance with Department specification requirements.	Armval Time at job Total Water added agallons ) Time concrete community Time concrete concrete community Time concrete community Time concrete concrete community Time concrete concret	B650 CTOP Technician is  at job site [ pletely discharged	72155 dentification Num Admixtures adi ( ounces ) Time admixture	ber  ded at the job site  a added	Number of a Additional ri	Signature of Plant Operar revolutions upon arrival at julians revolutions with water arrival at julians revolutions with water of revolutions.	nor added.	<u></u>
	Armval Time at job  Total Water added agallons.)  Time concrete community  Limited Stump	B650 CTOP Technician is  at job site [ pletely discharged	72155 dentification Num Admixtures adi ( ounces ) Time admixture	ber  ded at the job site  a added	Number of a Additional ri	Signature of Plant Operar revolutions upon arrival at julians revolutions with water arrival at julians revolutions with water of revolutions.	nor added.	<u></u>

### SPEC 346—DELIVERY TICKET

### Spec 346—Mass Concrete

- Mass Concrete Control Plan
- Temperature readings every 6 hours until:
  - Max temperature differential (35°F max) and
  - Max temperature (180°F max) and diminishes
- Controls remain until core temperature within 50°F of ambient
- Specialty Engineer must be engaged to advise if issues arise




### SPEC 346—MASS CONCRETE



### SPEC 400—FOOTING PLACEMENT

- Cofferdam preparation—seal concrete or precast "bathtub"
  - Water seepage
  - Standing water prior to concrete placement
  - Primary pump capacity plus backup pump
- 20 inch or less lift thickness when placing concrete
- Mass concrete monitoring devices protected during concrete placement



## SPEC 400—DECK PLACEMENT

- Placement sequence/ direction
- Screed demonstration
- Curing compound applied within 120 minutes of initial placement
- Compound spread rate/quantity reported to the Engineer
- Placement and maintenance of curing blankets (over barrier)



SPEC 400— DECK PLACEMENT






Fig. 4.1—Nomograph for estimating the maximum potential rate of evaporation of the environment, assuming a water-covered surface in which the water temperature is equal to the concrete temperature (Menzel 1954; NRMCA 1960).

### SPEC 400—DECK PLACEMENT

- Evaporation rate determined by:
  - Air temperature, relative humidity
  - Concrete temperature
  - Wind Velocity (15 mph max)
- If evaporation rate exceeds <u>0.1</u>
   <u>lbs/ft<sup>2</sup>/hr</u> including:
  - Evaporation retarder
  - Water fogging
  - Chilled mix water
  - Wind screens



### SPECS 400/450— CAMBER

- Monthly camber estimates in the precast yard
- Camber tolerance of I inch from design camber in Plans
- Contractor takes appropriate actions (400-7.13.1) to get girder stirrups to "fit" with the deck



### SPECS 400/415/460/502— REBAR, SIP FORMS, SHEAR CONNECTORS

- Field welding per Spec 460 only if Engineer approval or if on the Plans
- No welding of SIP forms to flanges
- Bending of reinforcement with Engineer's permission
- Store rebar above ground on dunnage
- Shear stud installation in the field with bend testing



CMC STEEL SOUTH CAROLINA Cavce SC 29033-3704

For additional copies call 800-637-3227

HEAT NO.:2071956 SECTION: REBAR 25MM (#8) 60'0' SRADE: ASTM A615-18e1 Gr 420/ KOLL DATE: 11/11/2018 MELT DATE: 11/10/2018 Cert. No.: 11/10/2018 / 071956D030	50	S O L D	S H I P			Delivery#: BOL#: CUST PO#: CUST PIN: DLVRY LBS / HE/	
Characteristic  C Mn P S S Si Cu Cr Ni Mo V Cb Sn Al Ti N Yield Strength test 1 Yield Strength 1 (metric) Tensile Strength 1 (metric) Tensile Strength 1 (metric) Tensile Strength 1 (Elongation test 1	Value 0.41% 0.85% 0.013% 0.21% 0.22% 0.12% 0.12% 0.000% 0.011% 0.001% 0.001% 64.6ksi 717MPa 13%		Characteristic  Elongation Gage Lgth test 1  Bend Test 1  Rebar Deformation Avg. Spaci  Rebar Deformation Avg. Heigh  Rebar Deformation Max. Gap  Bend Test Diameter	0.6 0.0 0.1	 The Following is  *Material i *100% me *EN10204 *Contains *Contains *Manufact of the pla *Meels th *Warning, known to	true of the material representation of the material representation of the material representation of the dark of t	ne latest version ents of 23 CFR635.4 you to chemicals wi ause cancer, birth d
EMARKS :			03/28/2019 21:39:23 Page 1 OF 1		I to www.P	65Warnings.ca.gov	

### SPEC 6—BUY **AMERICA**

- Buy America applicable to steel incorporated in the finished work, not the temporary condition
- Not just for Projects with FHWA funding during Construction
- Included if the corridor had FHWA funding through PD&E
- Mill certs need state "Made in USA"




### SPECS 400/460/461— BEARINGS, ANCHOR BOLTS

- Inspection of bearings for deformation and general condition
- Anchor bolt hole misalignment
- Expansion and contraction from temperature

# Spec 460—Material


- The Department default material requirement for structural steel superstructures is weathering steel if 4 miles from the coast or greater
- If site conditions are acceptable, painting not required, reduction in maintenance costs over the life of the bridge
- Exceptions permitted but must be approved by the Chief
   Engineer, requiring justification by the District





### SPEC 460—STRUCTURAL STEEL AND MISCELLANEOUS METALS


WEATHERING STEEL GIRDERS



### SPEC 460—BOLTING

- Turn-Of-Nut method
- ROCAP/Job-Inspection Snug Tight Torque performed in the field
- Bolt tightening sequence
- Erection Plan
- DTI's Direct Tension Indicators

### SPEC 460— BOLTING




SPEC 460 SKIDMORE-WILHELM TENSION CALIBRATOR

SPEC 460—TURN OF NUT BOLTING



### SPEC 460— BOLTING

 Checking Snug Tight Tension with a Calibrated Torque
 Wrench



# CONTRACTOR'S ENGINEER OF RECORD

### Contractor's Engineer

This table provides brief clarifications to the works that are allowed to be performed by Contractor's Engineer of Record, Department Approved Specialty Engineer and Specialty Engineer as defined in Specification Section 1. For definitions, additional information and further clarifications refer to Specification Section 1.

Work Type	Contractor's Engineer of Record	Department Approved Specialty Engineer	Specialty Engineer
Re-design	Yes	No	No
Cost Savings Initiative Proposal	Yes	No	No
Details of the permanent work not fully detailed in the plans	Yes	Yes	Yes
Design and details of the permanent work declared to be minor or non-structural including minor repairs	Yes	Yes	Yes
Design and details of the permanent work declared to be major or structural including major repairs	Yes	Yes*	No
Design and drawings of temporary works, such as falsework, formwork, etc.	Yes	Yes	Yes

\*The work must also be checked by another Department Approved Specialty Engineer

# Qualifications and Certifications



CTQP Concrete Field Technician - Level I



CTQP Concrete Field Inspector - Level II



CTQP Grouting Technician - Level I & 2






ACI, PTI, and ASBI issue certifications for successful completion



ASBI Certification in Flexible Filler Injection





# Spec 462 & 960 – Post-Tensioning

- Old Specifications utilized preapproved PT systems which can still be found on FDOT's website: <u>Structures Design Office Post-Tensioning Jan 2016 Later Specifications</u>
- New approach relies on CEI/EOR to review PT shop drawings and test reports for each project.
- Components and systems detailed in the approved PT drawings MUST be adhered to with no substitutions (excluding local zone reinforcement)
- The sensitivity of PT system performance to the components and workmanship of installation require strict adherence to the approved PT shop drawings that MUST be enforced by the CEI

# Spec 462 & 960 – Post-Tensioning

- Current Specifications 462 have adopted a new dehumidification procedure to ensure standing water and moisture is removed from tendons utilizing flexible filler prior to tendon installation and flexible filler injection
- Key points to be aware of:
  - Ensuring the duct stays dry before and after tendon installation
  - Storage requirements for components
  - Ensure proper concrete consolidation around congested anchor regions with local zone reinforcing
  - Accurately install and position/support PT systems prior to concrete placement (duct supports, spiral positioning, etc.)
  - Ensure all Contractor field testing conducted prior to concreting; contractor inspections
  - Adhere to the time limitations outlined in 462 for time between tendon installation and filler injection as well as time between filler injection and pour-back construction
  - Mock-up requirements
  - Grout problems
  - Flexible filler problems

# **Training and Reference Tools**

- Office of Construction and CTQP Websites contain most structures construction training materials including piles and drilled shafts as downloads
  - <a href="https://www.ctqpflorida.com/">https://www.ctqpflorida.com/</a>
- Structures Related Websites:
- State Construction Office Training: Self Study
- State Construction Office, Structures Webpage
  - (http://www.fdot.gov/construction/)
- <u>State Structures Design Office Website</u>
  - (<u>http://www.fdot.gov/structures/</u>)



### Contact

- State Construction Structures Engineer
  - Alex.randell@dot.state.fl.us
  - (850) 414-4275

#### Construction Structures Website:

• <u>https://www.fdot.gov/construction/structures/Structures.shtm</u>