

## SECTION 102 MAINTENANCE OF TRAFFIC

### 102-1 Description.

Maintain traffic within the limits of the project for the duration of the construction period, including any temporary suspensions of the work. Construct and maintain detours. Provide facilities for access to residences, businesses, etc., along the project. Furnish, install and maintain traffic control and safety devices during construction. Furnish and install work zone pavement markings for maintenance of traffic (MOT) in construction areas. Provide any other special requirements for safe and expeditious movement of traffic specified in the Plans. MOT includes all facilities, devices and operations as required for safety and convenience of the public within the work zone.

Do not maintain traffic over those portions of the project where no work is to be accomplished or where construction operations will not affect existing roads. Do not obstruct or create a hazard to any traffic during the performance of the work, and repair any damage to existing pavement open to traffic.

### 102-2 Materials.

Meet the following requirements:

Bituminous Adhesive.....	Section 970
Temporary Retroreflective <del>aised</del> Pavement Markers.....	Section 990
Paint .....	Section 971
Removable Tape .....	Section 990
Glass Spheres .....	Section 971
Temporary Traffic Control Device Materials .....	Section 990
Retroreflective and Nonreflective Sheeting for Temporary Traffic Control Devices .....	Section 994

**102-2.1 Temporary Traffic Control Devices:** Use only the materials meeting the requirements of Section 990, Section 994, Design Standard Plans and the Manual on Uniform Traffic Control Devices (MUTCD).

**102-2.2 Detour:** Provide all materials for the construction and maintenance of all detours.

**102-2.3 Commercial Materials for Driveway Maintenance:** Provide materials of the type typically used for base, including reclaimed asphalt pavement (RAP) material, and having stability and drainage properties that will provide a firm surface under wet conditions.

### 102-3 Specific Requirements.

**102-3.1 Beginning Date of Contractor's Responsibility:** Maintain traffic starting the day work begins on the project or on the first day Contract Time is charged, whichever is earlier.

**102-3.2 Worksite Traffic Supervisor:** Provide a Worksite Traffic Supervisor who is responsible for initiating, installing, and maintaining all temporary traffic control devices as described in this Section and the Contract Documents. Provide all equipment and materials needed to set up, take down, maintain traffic control, and handle traffic-related situations. Use approved alternate Worksite Traffic Supervisors when necessary.

The Worksite Traffic Supervisor must meet the personnel qualifications specified in Section 105.

The Worksite Traffic Supervisor is to perform the following duties:

1. On site direction of all temporary traffic control on the project.
2. Is on site during all set up and take down, and performs a drive through inspection immediately after set up.
3. Is on site during all nighttime operations ensuring proper temporary traffic control.
4. Immediately corrects all safety deficiencies and corrects minor deficiencies that are not immediate safety hazards within 24 hours.
5. Is available on a 24 hour per day basis and present at the site within 45 minutes after notification of an emergency situation and is prepared to respond to maintain temporary traffic control or to provide alternate traffic arrangements.
6. Conducts daily daytime and weekly nighttime inspections of projects with predominately daytime work activities, and daily nighttime and weekly daytime inspections of projects with predominantly nighttime work activities of all traffic control devices, traffic flow, pedestrian, bicyclist, and business accommodations.

Advise the project personnel of the schedule of these inspections and give them the opportunity to join in the inspection as deemed necessary. Pedestrians are to be accommodated with a safe, accessible travel path around work sites separated from mainline traffic in compliance with the Americans with Disabilities Act (ADA) Standards for Transportation Facilities. Maintain existing or detour bicycle facilities satisfactorily throughout the project limits. Existing businesses in work areas are to be provided with adequate entrances for vehicular and pedestrian traffic during business hours.

The Department may disqualify and remove from the project a Worksite Traffic Supervisor who fails to comply with the provisions of this Section. The Department may temporarily suspend all activities, except traffic, erosion control and such other activities that are necessary for project maintenance and safety, for failure to comply with these provisions.

**102-3.3 Lane Closure Information System:** Approval for all lane closures, mobile operations, and traffic pacing operations is required. Submit routine requests fourteen calendar days in advance of planned lane closures, mobile operations, and traffic pacing operations at the following URL address: <https://lcis.dot.state.fl.us/> . Confirm at least once every two weeks that information entered within LCIS reflects current planned operations and update as necessary. For unforeseen events that require cancelling or rescheduling lane closures, mobile operations, and traffic pacing operations, revise the lane closure request as soon as possible.

#### **102-4 Alternative Traffic Control Plan.**

The Contractor may propose an alternative traffic control plan (TCP) to the plan presented in the Contract Documents. The Contractor's Engineer of Record must sign and seal the alternative plan and submit to the Engineer. Prepare the TCP in conformance with and in the form outlined in the current version of the [Department's Plans Preparation](#) [FDOT Design](#) Manual. Indicate in the plan a TCP for each phase of activities. Take responsibility for identifying and assessing any potential impacts to a utility that may be caused by the alternate TCP proposed by the Contractor, and notify the Department in writing of any such potential impacts to utilities.

Engineer's approval of the alternate TCP does not relieve the Contractor of sole responsibility for all utility impacts, costs, delays or damages, whether direct or indirect,

resulting from Contractor initiated changes in the design or construction activities from those in the original Contract Specifications, Design Plans (including TCPs) or other Contract Documents and which effect a change in utility work different from that shown in the Utility Plans, joint project agreements or utility relocation schedules.

The Department reserves the right to reject any alternative TCP. Obtain the Engineer's written approval before beginning work using an alternate TCP. The Engineer's written approval is required for all modifications to the TCP. The Engineer will only allow changes to the TCP in an emergency without the proper documentation.

## **102-5 Traffic Control.**

**102-5.1 Standards:** FDOT ~~Design~~ Standard Plans are the minimum standards for the use in the development of all TCPs. The MUTCD, Part VI is the minimum national standard for traffic control for highway construction, maintenance, and utility operations. Follow the basic principles and minimum standards contained in these documents for the design, application, installation, maintenance, and removal of all traffic control devices, warning devices and barriers which are necessary to protect the public and workers from hazards within the project limits.

**102-5.2 Maintenance of Roadway Surfaces:** Maintain all lanes that are being used for the MOT, including those on detours and temporary facilities, under all weather conditions. Keep the lanes reasonably free of dust, potholes and rutting. Provide the lanes with the drainage facilities necessary to maintain a smooth riding surface under all weather conditions.

**102-5.3 Number of Traffic Lanes:** Maintain one lane of traffic in each direction. Maintain two lanes of traffic in each direction at existing four (or more) lane cross roads, where necessary to avoid undue traffic congestion. Construct each lane used for MOT at least as wide as the traffic lanes existing in the area before commencement of construction. Do not allow traffic control and warning devices to encroach on lanes used for MOT.

The Engineer may allow the Contractor to restrict traffic to one-way operation for short periods of time provided that the Contractor employs adequate means of traffic control and does not unreasonably delay traffic. When a construction activity requires restricting traffic to one-way operations, locate the flaggers within view of each other when possible. When visual contact between flaggers is not possible, equip them with 2-way radios, official, or pilot vehicles, or use traffic signals.

**102-5.4 Crossings and Intersections:** Provide and maintain adequate accommodations for intersecting and crossing traffic. Do not block or unduly restrict any median opening, road or street crossing the project unless approved by the Engineer. Before beginning any construction, submit to the Engineer the names and phone numbers of persons that can be contacted when signal operation malfunctions.

**102-5.5 Access for Residences and Businesses:** Provide continuous access to all residences and all places of business.

**102-5.6 Protection of the Work from Injury by Traffic:** Where traffic would be injurious to a base, surface course, or structure constructed as a part of the work, maintain all traffic outside the limits of such areas until the potential for injury no longer exists.

**102-5.7 Flagger:** Provide flaggers to control traffic when traffic in both directions must use a single lane and in other situations as required. All flaggers must meet the personnel qualifications specified in Section 105.

**102-5.8 Conflicting Pavement Markings:** Where the lane use or where normal vehicle or pedestrian paths are altered during construction, remove all pavement markings (paint, tape, thermoplastic, ~~retroreflective~~ raised pavement markers, etc.) that will conflict with the adjusted

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

vehicle or pedestrian paths. Use of paint to cover conflicting pavement markings is prohibited. Remove conflicting pavement markings using a method that will not damage the surface texture of the pavement and which will eliminate the previous marking pattern regardless of weather and light conditions.

Remove all pavement markings that will be in conflict with “next phase of operation” vehicle pedestrian paths as described above, before opening to vehicle traffic or use by pedestrians.

Cost for removing conflicting pavement markings (paint, tape, thermoplastic, ~~retroreflective~~raised pavement markers, etc.) to be included in Maintenance of Traffic, lump sum.

**102-5.9 Vehicle and Equipment Visibility:** Equip all pickups and automobiles used on the project with a minimum of one Class 2 warning light that meets the Society of Automotive Engineers Recommended Practice SAE J595, dated November 1, 2008, or SAE J845, dated December 1, 2007, and incorporated herein by reference. Existing lights that meet SAE J845, dated March, 1992, or SAE J1318, dated April, 1986, may be used to their end of service life. The warning lights must be a high intensity amber or white rotating, flashing, oscillating or strobe light. Lights must be unobstructed by ancillary vehicle equipment such as ladders, racks or booms and be visible 360 degrees around the vehicle. If the light is obstructed, additional lights will be required. The lights must be operating when the vehicle is in a work area where a potential hazard exists, when operating at less than the average speed for the facility while performing work activities, making frequent stops or called for in the Plans or ~~Design~~Standard Plans.

Equip all other vehicles and equipment with a minimum of 4 square feet of retroreflective sheeting or warning lights.

**102-5.10 No Waiver of Liability:** Conduct operations in such a manner that no undue hazard results due to the requirements of this Article. The procedures and policies described herein in no way acts as a waiver of any terms of the liability of the Contractor or his surety.

## **102-6 Detours.**

**102-6.1 General:** Construct and maintain detour facilities wherever it becomes necessary to divert traffic from any existing roadway or bridge, or wherever construction operations block the flow of traffic.

**102-6.2 Construction:** Plan, construct, and maintain detours for the safe passage of traffic in all conditions of weather. Provide the detour with all facilities necessary to meet this requirement.

Where pedestrian facilities are detoured, blocked or closed during the work, provide safe alternate accessible routes through or around the work zone meeting the requirements of the ADA Standards for Transportation Facilities. When temporary walkway surfaces and ramps are required to be constructed, ensure surfaces are stable, firm, slip resistant, and kept free of any obstructions and hazards such as holes, debris, mud, construction equipment and stored materials.

When the Plans call for the Department to furnish detour bridge components, construct the pile bents in accordance with the Plans, unless otherwise authorized by the Engineer.

Provide two Contractor representatives, who will be directly involved in the erection of Department-owned temporary bridging, to attend a mandatory one-day training

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

session to be conducted at the Department's storage facility. No bridging will be released to the Contractor prior to the completion of this training.

Submit the following: company name, phone number, office address, project contact person, names of the representatives who will attend the training described above, project number, detour bridge type, bridge length, span length, location and usage time frames, to the Engineer at least 30 calendar days before the intended pick-up date, to obtain the storage facility location and list of components for the project. Upon receipt, the Engineer will, within 10 calendar days submit an approved material list to the Contractor and the appropriate Department storage yard.

Submit the name of the representative with authority to pick up components, to the Engineer at least 10 calendar days before the proposed pick-up date. The Department is not obligated to load the bridge components without this notice. Take responsibility and sign for each item loaded at the time of issuance.

Provide timber dunnage, and transport the bridge components from the designated storage facility to the job site. Unload, erect, and maintain the bridge, then dismantle the bridge and load and return the components to the designated storage facility.

Notify the Engineer in writing at least 10 calendar days before returning the components. Include in this notice the name of the Contractor's representative authorized to sign for return of the bridge components. The yard supervisor is not obligated to unload the bridge components without this notice.

The Department will provide equipment and an operator at the Department's storage facility to assist in loading and unloading the bridge components. Furnish all other labor and equipment required for loading and unloading the components.

The Department's representative will record all bridge components issued or returned on the Detour Bridge Issue and Credit Ticket. The tickets must be signed by a Department and a Contractor representative, after loading or unloading each truck to document the quantity and type of bridging issued or returned.

Bind together all bridge components to be returned in accordance with the instructions given by the storage facility. The yard supervisor will repack components that are not packed in compliance with these instructions. Upon request, written packing instructions will be made available to the Contractor, before dismantling of the bridge for return to the Department's storage facility.

Assume responsibility for any shortage or damage to the bridge components. Monies due the Contractor will be reduced at the rate of \$35.00 per hour plus materials for repacking, repairs or replacement of bridge components.

The skid resistance of open steel grid decking on the detour bridge may decrease gradually after opening the bridge to traffic. The Department will furnish a pneumatic floor scabbler machine for roughening the roadway surface of the detour bridge decking. Provide an air compressor at the job site with 200 cubic feet per minute capacity, 90 psi air pressure for the power supply of the machine, and an operator. Transport the scabbler machine to and from the Department's structures shop. Repair any damage to the scabbler machine caused by operations at no expense to the Department. Perform scabbling when determined necessary by the Engineer. The Department will pay for the cost of scabbling as Unforeseeable Work in accordance with 4-4.

Return the bridge components to the designated storage facility beginning no later than 10 calendar days after the date the detour bridge is no longer needed, the date the new

bridge is placed in service, or the date Contract Time expires, whichever is earliest. Return the detour bridging at an average of not less than 200 feet per week. Upon failure to return the bridge components to the Department within the time specified, compensate the Department for the bridge components not returned at the rate of \$5.00 per 10 feet, per day, per bridge, for single lane; and \$10.00 per 10 feet, per day, per bridge, for dual lane until the bridge components are returned to the Department.

**102-6.3 Construction Methods:** Select and use construction methods and materials that provide a stable and safe detour facility. Construct the detour facility to have sufficient durability to remain in good condition, supplemented by maintenance, for the entire period that the detour is required.

**102-6.4 Removal of Detours:** Remove detours when they are no longer needed and before the Contract is completed. Take ownership of all materials from the detour and dispose of them, except for the materials on loan from the Department with the stipulation that they are returned.

**102-6.5 Detours Over Existing Roads and Streets:** When the Department specifies that traffic be detoured over roads or streets outside the project area, do not maintain such roads or streets. However, maintain all signs and other devices placed for the purpose of the detour.

**102-6.6 Operation of Existing Movable Bridges:** The Department will maintain and operate existing moveable bridges that are to be removed by the Contractor until such time as they are closed to traffic. During this period, make immediate repairs of any damage to such structures caused by use or operations related to the work at no expense to the Department, but do not provide routine repairs or maintenance. In the event that use or operations result in damage to a bridge requiring repairs, give such repairs top priority to any equipment, material, or labor available.

**102-6.7 Special Detour:** A special detour is defined as a diversion or lane shift for vehicular traffic that requires temporary pavement.

## **102-7 Traffic Control Officer.**

Provide uniformed law enforcement officers, including marked law enforcement vehicles, to assist in controlling and directing traffic in the work zone when the following types of work is necessary on projects:

1. Directing traffic/overriding the signal in a signalized intersection.
2. When ~~Design~~ Standard Plans, Index ~~No.~~ 102-619 is used on freeway facilities (interstates, toll roads, and expressways) at nighttime for work within the travel lane.
3. When ~~Design~~ Standard Plans, Index ~~No.~~ 102-655 Traffic Pacing ~~for overhead work~~ is called for in the Plans or approved by the Engineer.
4. When pulling conductor/cable above an open traffic lane on limited access facilities, when called for in the Plans or approved by the Engineer.
5. When ~~Design~~ Standard Plans, Index ~~No.~~ 102-625 Temporary Road Closure 5 Minutes or Less is used.

## **102-8 Driveway Maintenance.**

**102-8.1 General:** Ensure that each residence and business has safe, stable, and reasonable access.

**102-8.2 Construction Methods:** Place, level, manipulate, compact, and maintain the material, to the extent appropriate for the intended use.

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

As permanent driveway construction is accomplished at a particular location, the Contractor may salvage and reuse previously placed materials that are suitable for reuse on other driveways.

## **102-9 Temporary Traffic Control Devices.**

**102-9.1 Installation and Maintenance:** Install and maintain temporary traffic control devices as detailed in the Plans, Index 102-600 of the ~~Design~~ Standard Plans and when applicable, in accordance with the approved vendor drawings, as provided on the Department's Approved Product List (APL). Erect the required temporary traffic control devices to prevent any hazardous conditions and in conjunction with any necessary traffic re-routing to protect the traveling public, workers, and to safeguard the work area. Use only those devices that are on the APL or meeting the requirements of the ~~Design~~ Standard Plans. Immediately remove or cover any devices that do not apply to existing conditions.

~~—————All temporary traffic control devices must meet the requirements of National Cooperative Highway Research Program Report 350 (NCHRP 350) or the Manual for Assessing Safety Hardware 2009 (MASH) and current FHWA directives. Manufacturers seeking evaluation must submit certified test reports showing that their product meets all test requirements set forth by NCHRP 350 or the MASH. Manufacturers seeking evaluation of Category I devices for inclusion on the APL shall include the manufacturer's self-certification letter. Manufacturer's seeking evaluation of Category II and Category III devices for inclusion on the APL shall include the FHWA WZ-numbered acceptance letter with attachments and vendor drawings of the device in sufficient detail to enable the Engineer to distinguish between this and similar devices. For devices requiring field assembly or special site preparation, vendor drawings shall include all field assembly details and technical information necessary for proper application and installation. Vendor drawings for Category III devices and automated flagger assistance devices (AFADs) must be signed and sealed by a Professional Engineer registered in the State of Florida. Manufacturers seeking evaluation of Category IV devices for inclusion on the APL must comply with the requirements of Section 990 and include detailed vendor drawings of the device along with technical information necessary for proper application, field assembly and installation.~~

The APL number is to be permanently marked on the device at a readily visible location. Sheeting used on devices is exempt from this marking requirement.

Notify the Engineer in writing of any scheduled operation that will affect traffic patterns or safety sufficiently in advance of commencing such operation to permit review of the plan for the proposed installation of temporary traffic control devices.

Assign an employee the responsibility of maintaining the position and condition of all temporary traffic control devices throughout the duration of the Contract. Keep the Engineer advised at all times of the identification and means of contacting this employee on a 24 hour basis.

Maintain temporary traffic control devices in the correct position, properly oriented, clearly visible and clean, at all times. All applicable temporary traffic control devices must meet the classification category of Acceptable as defined in the American Traffic Safety Services Association (ATSSA) Quality Guidelines for Temporary Traffic Control Devices and Features. Pedestrian longitudinal channeling devices (LCDs) must meet the classification category of Acceptable as defined in the Pedestrian LCD Evaluation Guide, which may be viewed at the following URL:

<http://www.fdot.gov/programmanagement/Implemented/URLinSpecs/files/LCDEvaluationGuide.pdf>. Immediately repair, replace or clean damaged, defaced or dirty devices. Traffic control

devices must not be cleaned while installed/used. Use of warning lights on any temporary traffic control device is prohibited, with the exception of the trailer mounted portable regulatory signs.

Employ an approved independent Channelizing Device Supplier (CDS) to provide and maintain the condition of the following non-fixed channelizing devices: drums, cones, vertical panels, barricades, tubular markers, and longitudinal channeling devices. Cones may be provided and maintained by the Contractor.

The CDS shall not be affiliated with the Contractor and shall be approved by the Engineer in accordance with 102-9.1.1. The CDS shall submit a monthly certification on letterhead that the channelizing devices mentioned above installed/used within the work zone meet classification category of Acceptable as defined in the Pedestrian LCD Evaluation Guide and the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features. The CDS shall submit the monthly certification on letterhead for channelizing devices installed/used within the work zone. The CDS certification shall include the following statement, "I certify that I have provided and maintained the following devices <list devices covered under the certification> in accordance with Pedestrian LCD Evaluation Guide and the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features." If the Contractor chooses to provide and maintain cones, the Contractor must submit a monthly Contractor certification on letterhead that all cones installed/used within the work zone meet acceptable standards as outlined in the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features. The Contractor certification shall include the following statement, "I certify that I have provided and maintained cones in accordance with the ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features."

#### **102-9.1.1 Approved Independent Channelizing Device Supplier (CDS)**

**Requirements:** Submit the following documents to the Engineer for independent CDS approval at the preconstruction conference. A CDS may elect to provide a one-time submittal of this information to the State Construction Office for review and pre-approval. Department approved CDSs are listed on the State Construction Office website. Inform the Engineer at the preconstruction conference of this approval.

1. A letter on company letterhead signed and dated by the owner of the company or company officer with the following information and statements:

a. The company's owners, stockholders, and officers.

b. A statement declaring that the company will not perform as a CDS on any project where there is common ownership, directly or indirectly, between the company and the Contractor.

c. A statement declaring that the company will furnish and maintain the condition of all channelizing devices with the exception of cones as required in 102-9.1 with its own forces.

d. A statement declaring at least five years of experience in providing channelizing device supplier services, with its own inventory of channelizing devices.

e. On a separate sheet, list a sample project history of the company's experience as a channeling device supplier for the five years declared in item 1(d) above including the following information:

1. Project name and number and a brief description of CDS work performed,

2. Beginning and ending date of CDS project activities,

3. Location of project (city, state),

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

4. Monetary amount of CDS work on project,  
5. Owner of project, contact person and phone number with area code,  
6. Name of Contractor (client) that the work was performed for and phone number with area code.

2. A maintenance plan for approval by the Department that outlines the frequency and methods for maintaining the condition of all channelizing devices, except cones owned and maintained by the Contractor, installed/used in the work zone.

**102-9.2 Work Zone Signs:** Furnish, install, maintain, remove and relocate signs in accordance with the Plans and [Design-Standard Plans](#), Index-~~No.~~ [102-600](#). Use signs that meet the material and process requirements of Section 994. Use Type IV sheeting for fluorescent orange work zone signs. Roll-up signs must meet the requirements of Type VI sheeting. Use Type IV or Type XI sheeting for all other work zone signs. Attach the sign to the sign support using hardware meeting the manufacturer's recommendations on the APL vendor drawings or as specified in the [Design-Standard Plans](#).

**102-9.2.1 Post Mounted Signs:** Meet the requirements of 990-8.

**102-9.2.2 Portable Signs:** Use only approved systems, which includes sign stands and attachment hardware (nuts, bolts, clamps, brackets, braces, etc.), meeting the vendor requirements specified on the APL drawings. Provide Federal Highway Administration's (FHWA) accepted sign substrate for use with accepted sign stands on the National Highway System (NHS) under the provisions of the NCHRP Report 350 "Recommended Procedures for the Safety Performance Evaluation of Highway Features."

**102-9.2.3 Barrier Mounted Signs:** If post mounting criteria cannot be achieved in accordance with [Design-Standard Plans](#), Index-~~No.~~ [102-600](#) and a barrier or traffic railing exists, use temporary sign criteria provided in [Design-Standard Plans](#), Index-~~No.~~ [11871700-013](#).

**102-9.3 Business Signs:** Provide and place signs in accordance with the Plans and [Design-Standard Plans](#), Index-~~No.~~ [102-600](#) series. Furnish signs having retroreflective sheeting meeting the requirements of Section 990.

**102-9.4 Project Information Signs:** Provide and place signs in accordance with the Plans and [Design-Standard Plans](#), Index-~~No.~~ [102-600](#) series. Furnish signs having retroreflective sheeting meeting the requirements of Section 990.

**102-9.5 Channelizing Devices:** Furnish, install, maintain, remove and relocate channelizing devices in accordance with the Plans and [Design-Standard Plans](#).

**102-9.5.1 Retroreflective Collars for Traffic Cones:** Use collars for traffic cones listed on the APL that meet the requirements of Section 990. Use cone collars at night designed to properly fit the taper of the cone when installed. Place the upper 6 inch collar a uniform 3-1/2 inches distance from the top of the cone and the lower 4 inch collar a uniform 2 inches distance below the bottom of the upper 6 inch collar.

Collars must be capable of being removed for temporary use or attached permanently to the cone in accordance with the manufacturer's recommendations. Provide a white sheeting having a smooth outer surface and that has the property of a retroreflector over its entire surface.

**102-9.5.2 Longitudinal Channelizing Devices (LCDs):** Use LCDs listed on the APL and meeting the requirements of Section 990 and the [Design-Standard Plans](#). LCDs must be interlocked except for the stand-alone unit placed perpendicular to a sidewalk. For LCDs requiring internal ballasting, an indicator that clearly identifies the proper ballast level will be

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

required. For LCDs requiring external ballasting, the ballasting methods must be detailed in the APL drawings including ballasting type and minimum weight.

Ensure that joints on the pedestrian LCDs are free of sharp edges and have a maximum offset of 1/2 inch in any plane.

Use alternating orange and white solid color vehicular LCDs. Vehicular LCDs may be substituted for drums, vertical panels, or barricades.

**102-9.6 Temporary Barrier:** Furnish, install, maintain, remove and relocate temporary barrier in accordance with the Plans and Standard Plans. Obtain and use precast temporary concrete barrier from a manufacturing plant that is on the Department's Production Facility Listing. ~~Producers seeking inclusion on the list shall meet the requirements of Section 105.~~ Temporary concrete barrier must meet the material and construction requirements of Section 521 unless noted otherwise in the ~~Design Standard Plans~~. Proprietary temporary concrete, steel, or water filled barrier used must be listed on the APL.

The maximum allowable height increase between consecutive temporary barrier units in the direction of traffic is 1 inch.

Temporary barrier ~~used on roadway sections~~ must comply with ~~Design Standard Plans, Index Nos. 412, 415 or 414~~ Index 102-100 or 102-120. ~~Temporary barrier used on bridge and retaining wall sections must comply with Design Standards, Index No 414.~~ Install temporary barriers as either anchored or freestanding as shown in the Plans or the Standard Plans. An anchored unit is defined as having at least one stake or bolt into the underlying pavement or bridge deck. All other units, including those with keeper pins, are considered freestanding.

Remove temporary asphalt pads and repair all attachment scars to permanent structures and pavements after barrier removal. Make necessary repairs due to defective material, work, or Contractor operations at no cost to the Department. Restore barrier damaged by the traveling public within 24 hours after notification as authorized by the Engineer.

~~Temporary water filled barrier used on roadway sections shall meet the NCHRP Report 350 TL-3 criteria or MASH TL-3 criteria and be listed on the APL.~~

~~Barriers meeting the requirements of Design Standards, Index Nos. 412, 415, or temporary water filled barriers listed on the APL will not be accepted as an alternate to barriers meeting the requirements of Design Standards, Index No. 414. Temporary steel barrier may be used as an alternative to Design Standards, Index No. 414. Temporary steel barrier shall meet the NCHRP Report 350 TL-3 criteria or MASH TL-3 criteria and be listed on the APL.~~

Trailer mounted barriers listed on the APL may be used at the option of the Contractor. Trailer mounted barriers listed on the APL must have an FHWA eligibility letter and be successfully crash tested in accordance with MASH TL-3 criteria. All trailer mounted barriers must be equipped with an APL listed truck mounted attenuator, an APL listed vehicle mounted arrow board and vehicle warning lights in accordance with this Section.

**102-9.6.2.1 Temporary Barrier Meeting the Requirements of ~~Design Standard Plans~~, Index ~~Nos. 102-412-120~~ and ~~102-414110~~:** Ensure the marking requirements of the respective Index are met.

**102-9.6.2.2: Proprietary Precast Temporary Concrete Barrier Fabricated prior to 2005:** The Contractor must submit a certification stating that all unmarked barrier units meet the requirements of the Specifications and the ~~Design Standard Plans~~. Certifications will be project specific and non-transferable.

**102-9.6.2.3 Proprietary Precast Temporary Concrete Barrier Fabricated in 2005 or later:** Ensure each barrier unit has permanent clear markings, showing

the manufacture date, serial number, manufacturer's name or symbol, and the APL number. Label the markings on a plate, plaque, or cast in the unit. Proprietary barrier fabricated prior to 2016 and marked with the "INDX 521" in lieu of the APL number will be permitted.

**102-9.7 Barrier Delineators:** Install barrier delineators on top of temporary barrier and vehicular LCDs meeting the requirements of ~~the Design Standards and~~ Section 705.

**102-9.8 Temporary Glare Screen:** Use temporary glare screens listed on the APL that meet the requirements of Section 990. Furnish, install, maintain, remove and relocate glare screen systems in conjunction with temporary barrier at locations identified in the Plans.

The anchorage of the glare screen to the barrier must be capable of safely resisting an equivalent tensile load of 600 pounds per foot of glare screen, with a requirement to use a minimum of three fasteners per barrier section.

When glare screen is utilized on temporary barrier, barrier delineators will not be required.

**102-9.9 Temporary Crash Cushion (Redirective or /Gating):** Furnish, install, maintain and subsequently remove temporary crash cushions in accordance with the details and notes shown in the Plans, ~~the Design Standard~~ Plans, and requirements of the pre-approved alternatives listed on the APL.

Temporary crash cushions can be either new or used functionally sound ~~devices~~ whether used or refurbished devices. Performance of intended function is the only condition for acceptance. All metallic components must be galvanized in accordance with Section 967.

Anchor abutting temporary barrier in accordance the Standard Plans or APL drawings, as required. ~~Un~~Bidirectional installations must have a transition panel installed between the crash cushion and the abutting barrier. Delineate the crash cushion in accordance with Section 544. Maintain the crash cushions until their authorized removal. Do not place any materials or equipment within the length of the crash cushion.

Remove temporary asphalt or concrete pads and ~~R~~repair all attachment scars to permanent structures and pavements after crash cushion removal. Make necessary repairs due to defective material, work, or Contractor operations at no cost to the Department. Restore crash cushions damaged by the traveling public within 24 hours after notification as authorized by the Engineer.

**102-9.10 Temporary Guardrail:** Furnish temporary guardrail in accordance with the Plans and ~~Design Standard~~ Plans. Meet the requirements of Section 536.

**102-9.11 Arrow Board:** Furnish arrow boards that meet the requirements of Section 990 as required by the Plans and ~~Design Standard~~ Plans to advise approaching traffic of lane closures or shoulder work. Ensure that the arrow board display panel is raised to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position. Type B arrow boards may be used on low to intermediate speed (0 mph to 50 mph) facilities or for maintenance or moving operations on any speed facility. Type C arrow boards must be used for all other operations on high-speed (50 mph and greater) facilities and may be substituted for Type B arrow boards on any speed facility.

**102-9.12 Portable Changeable Message Sign (PCMS):** Furnish PCMSs or truck mounted changeable message signs that meet the requirements of Section 990 as required by the Plans and ~~Design Standard~~ Plans to supplement other temporary traffic control devices used in work zones. Ensure that the PCMS display panel is raised to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position.

**102-9.13 Portable Regulatory Signs (PRS):** Furnish PRSs that meet the requirements of Section 990 as required by the Plans and ~~Design~~ Standard Plans. Ensure that the PRS sign panel is raised to a minimum mounting height of 7 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position.

Activate portable regulatory signs only during active work activities and deactivate when no work is being performed.

**102-9.14 Radar Speed Display Unit (RSDU):** Furnish RSDUs that meet the requirements of Section 990 as required by the Plans and ~~Design~~ Standard Plans to inform motorists of the posted speed and their actual speed. Ensure that the RSDU display panel is raised to a minimum mounting height of 5 feet from the bottom of the panel to the edge of the travel way elevation when in the upright position.

Activate the radar speed display unit only during active work activities and deactivate when no work is being performed.

**102-9.15 Temporary Signalization and Maintenance:** Provide temporary signalization and maintenance at existing, temporary, and new intersections including but not limited to the following:

1. Installation of temporary poles and span wire assemblies as shown in the Plans,

2. Temporary portable traffic signals as shown in the Plans,

3. Adding or shifting signal heads,

4. Trouble calls,

5. Maintaining intersection and coordination timing and preemption devices. Coordination timing will require maintaining functionality of system communications.

Restore any loss of operation within 12 hours after notification. Provide alternate temporary traffic control until the signalization is restored.

Provide traffic signal equipment that meets the requirements of the ~~Design~~ Standard Plans and 603-2. The Engineer may approve used signal equipment if it is in acceptable condition. Replacement components for traffic signal cabinet assemblies will be provided by the maintaining agency. For temporary signals used for lane closure operations on two-lane, two-way roadways meet the requirements in 102-9.21.

**102-9.16 Temporary Traffic Detection and Maintenance:** Provide temporary traffic detection and maintenance at existing, temporary, and new signalized intersections. Provide temporary traffic detection equipment listed on the APL. Restore any loss of detection within 12 hours. Ensure 90% accuracy per signal phase, measured at the initial installation and after any lane shifts, by comparing sample data collected from the detection system with ground truth data collected by human observation. Collect the sample and ground truth data for a minimum of five minutes during a peak and five minutes during an off-peak period with a minimum three detections for each signal phase. Perform the test in the presence of the Engineer.

**102-9.17 Truck Mounted Attenuators and Trailer Mounted Attenuators:** Furnish, install and maintain only those attenuators ~~that meet the requirements of NCHRP 350 or the MASH~~ listed on the APL.

~~Use truck mounted attenuators or trailer mounted attenuators, when called for in the Design Standards. Use attenuators listed on the APL. For posted speeds of 50 mph or greater, use either truck mounted attenuators or trailer mounted attenuators that meet TL-3 criteria (NCHRP or MASH). For posted speeds of 45 mph or less, use either truck mounted attenuators or trailer mounted attenuators that meet TL-2 or TL-3 criteria (NCHRP or MASH).~~

When attenuators are called for in the Plans or Standard Plans, use either a truck mounted attenuator or a trailer mounted attenuator ~~system designed and installed~~ in accordance with this Section and the manufacturer's recommendations.

Equip the attenuator cartridge with lights and reflectors in compliance with applicable Florida motor vehicle laws, including turn signals, dual tail lights, and brake lights. Ensure that lights are visible in both the raised and lowered positions if the unit is capable of being raised.

Install either alternating black with yellow or white with orange sheeting on the rear of trailer mounted attenuators and on truck mounted attenuators, in both the operating and raised position. Use Type III (work zone) or Type IV sheeting consisting of 4 or 6 inch wide stripes installed to form chevrons that point upward. All sheeting except black must be retroreflective.

Attenuators will not be paid for separately. Include the cost of the truck with either a truck mounted attenuator or a trailer mounted attenuator in Maintenance of Traffic, lump sum. Payment includes all costs, including furnishing, maintaining and removal when no longer required, and all materials, labor, tools, equipment and incidentals required for attenuator maintenance.

**102-9.18 Temporary Raised Rumble Strip Set:** Furnish, install, maintain, remove, and reinstall temporary raised rumble strips per the manufacturer's recommendations and in accordance with Design Standard Plans, Index ~~No. 102-603~~.

The temporary raised rumble strip may be either a removable polymer striping tape or a molded engineered polymer material.

**102-9.19 Automated Flagger Assistance Devices (AFAD):** Furnish, install, maintain, remove, and relocate AFADs in accordance with the Plans, Design Standard Plans, Index ~~No. 102-603~~, and APL vendor drawings. ~~Manufacturers seeking evaluation of their product for the APL must submit an application in accordance with Section 6 and include detailed vendor drawings showing typical application of the device in accordance with Design Standards, Index No. 603.~~

Position AFADs where they are clearly visible to oncoming traffic. AFADs may be placed on the centerline if they have been successfully crash tested in accordance with MASH TL-3 criteria. A gate arm is required in accordance with Section 990 if a single AFAD is used on the shoulder to control one direction of traffic.

The devices may be operated either by a single flagger at one end of the traffic control zone, from a central location, or by a separate flagger near each device location. Use only flaggers trained in accordance with Section 105 and in the operation of the AFAD. When in use, each AFAD must be in view of, and attended at all times by, the flagger operating the device.

Provide two flaggers on-site and use one of the following methods in the deployment of AFADs:

1. Place an AFAD at each end of the temporary traffic control zone, or
2. Place an AFAD at one end of the temporary traffic control zone and a flagger at the opposite end.

A single flagger may simultaneously operate two AFADs as described in (1) or a single AFAD as described in (2) if all of the following conditions are met:

1. The flagger has an unobstructed view of the AFAD(s),
2. The flagger has an unobstructed view of approaching traffic in both directions,

3. For two AFADs, the AFADs are less than 800 feet apart. For one AFAD, the AFAD and the flagger are less than 800 feet apart.

4. Two flaggers are available on-site to provide normal flagging operations should an AFAD malfunction.

AFADs may be either a remotely controlled Stop/Slow AFAD mounted on either a trailer or a movable cart system, or a remotely controlled Red/Yellow Lens AFAD.

Illuminate the flagging station when the AFAD is used at night. When the AFAD is not in use, remove or cover signs and move the AFAD device outside the clear zone or shield it with a barrier.

AFADs will not be paid for separately. AFADs may be used as a supplement or an alternate to flaggers in accordance with the Plans, ~~Design-Standard~~ Plans, Index ~~No. 102-603~~, and the APL vendor drawings. Include the cost for AFADs in Maintenance of Traffic, Lump Sum.

**102-9.20 Temporary Lane Separator:** Furnish, install, maintain, remove and relocate temporary lane separator in accordance with the Plans and ~~Design-Standard~~ Plans, Index ~~No. 102-600~~. Anchor the portable temporary lane separator with a removable anchor bolt. Use epoxy on bridge decks where anchoring is not allowed. Remove the epoxy from the bridge deck by hydroblasting or other method approved by the Engineer.

**102-9.21 Temporary Signals for Lane Closures on Two-Lane, Two-Way Roadways:** Furnish, install, maintain, remove, and relocate temporary signals for lane closure operations on two-lane, two-way roadways at the locations shown in the Plans. Temporary signals may be used, at the Contractor's option, as an alternate to flaggers for lane closure operations on two-lane, two-way roadways in accordance with ~~Design-Standard~~ Plans, Index ~~No. 102-606~~. Temporary signals can either be portable signals or span wire signals and must be listed on the APL.

## **102-10 Work Zone Pavement Marking.**

**102-10.1 Description:** Furnish and install work zone pavement markings for MOT in construction areas and in close conformity with the lines and details shown in the Plans and ~~Design-Standard~~ Plans.

Centerlines, lane lines, edge lines, stop bars, standard crosswalks, and turn arrows will be required in work zones prior to opening the road to traffic.

### **102.10.2 Painted Pavement Markings:**

**102-10.2.1 General:** Use painted pavement markings meeting the requirements of Section 710. Use standard paint unless otherwise identified in the Plans or approved by the Engineer.

### **102-10.3 Removable Tape:**

**102-10.3.1 General:** Use removable tape listed on the APL as shown in the Plans and meeting the requirements of 990-4.

**102-10.3.2 Application:** Apply removable tape with a mechanical applicator to provide pavement lines that are neat, accurate and uniform. Equip the mechanical applicator with a film cut-off device and with measuring devices that automatically and accumulatively measure the length of each line placed within an accuracy tolerance of plus or minus 2%. Ensure removable tape adheres to the road surface. Removable tape may be placed by hand on short sections, 500 feet or less, if it is done in a neat accurate manner.

**102-10.3.3 Retroreflectivity:** Apply white and yellow pavement markings that will attain an initial retroreflectivity of not less than 300 mcd/lx·m<sup>2</sup> for white and contrast

markings and not less than 250 mcd/lx·m<sup>2</sup> for yellow markings. Black portions of contrast tapes and black masking tapes must be non-reflective and have a reflectance of less than 5 mcd/lx m<sup>2</sup>. At the end of the six month service life, the retroreflectance of white and yellow removable tape shall not be less than 150 mcd/lx·m<sup>2</sup>.

**102-10.3.4 Removability:** Provide removable tape capable of being removed from bituminous concrete and portland cement concrete pavement intact or in substantially large strips, either manually or by a mechanical roll-up device, at temperatures above 40°F, without the use of heat, solvents, grinding or blasting.

**102-10.4 Temporary ~~Retroreflective~~ Raised Pavement Markers (RPM's):** Use Class B RPMs ~~for all locations,~~ except for work that consists of ground-in rumble strips at centerline rumble striping operations, where Class D and Class B RPMs are required locations. For ground-in rumble strips at centerline locations, use temporary RPMs in accordance with Section 710. All markers must be Provide only temporary RPMs listed on the APL. Install all markers in accordance with the manufacturer's recommendations, ~~the and in accordance with Design Standard Plans, Index Nos. 519, 600, 17345, and 17352, and Section 706 prior to opening the road to traffic.~~ After initial installation, replace ~~markers any time~~ broken or missing temporary RPMs in locations where more than three consecutive ~~markers fail or are~~ temporary RPMs are broken or missing at no expense to the Department.

## **102-11 Method of Measurement.**

**102-11.1 General:** Devices installed/used on the project on any calendar day or portion thereof, within the Contract Time, including time extensions which may be granted, will be paid for at the Contract unit price for the applicable pay item. Include the cost of any work that is necessary to meet the requirements of the Contract Documents for MOT under Maintenance of Traffic, lump sum when separate payment is not provided.

**102-11.2 Traffic Control Officers:** The quantity to be paid for will be at the Contract unit price per hour (4 hour minimum) for the actual number of officers certified to be on the project site, including any law enforcement vehicles and all other direct and indirect costs. Payment will be made only for those traffic control officers specified in the Plans and authorized by the Engineer. Cost for traffic control officers used for operations other than those specified in 102-7 will be paid for under Maintenance of Traffic, lump sum.

**102-11.3 Special Detours:** When a special detour is shown in the Plans, the work of constructing, maintaining, and subsequently removing such detour facilities will be paid for under Special Detour, lump sum. However, traffic control devices, warning devices, barriers, signing, pavement markings, and restoration to final configuration will be paid for under their respective pay items.

When the Plans show more than one special detour, each special detour will be paid for separately, at the Contract lump sum price for each.

**102-11.4 Commercial Material for Driveway Maintenance:** The quantity to be paid for will be the certified volume, in cubic yards, of all materials authorized by the Engineer, acceptably placed and maintained for driveway maintenance. The volume, which is authorized to be reused, and which is acceptably salvaged, placed, and maintained in other designated driveways will be included again for payment.

**102-11.5 Work Zone Signs:** The number of temporary post-mounted signs (temporary regulatory, warning and guide) certified as installed/used on the project will be paid for at the Contract unit price for work zone signs. When multiple signs are located on single or multiple

posts, each sign panel will be paid individually. Signs greater than 20 square feet and detailed in the Plans will be paid for under Maintenance of Traffic, lump sum.

Temporary portable signs (excluding mesh signs) and vehicular mounted signs will be included for payment under work zone signs, only if used in accordance with the [Design Standard Plans](#).

The number of temporary barrier mounted signs (temporary regulatory, warning and guide) certified as installed/used on the project will be paid for at the Contract unit price for barrier mounted work zone signs.

Work zone signs may be installed fourteen days prior to the start of Contract Time with the approval of the Engineer and at no additional cost to the Department.

**102-11.6. Business Signs:** The number of business signs certified as installed/used on the project will be paid for at the Contract unit price for business signs.

**102-11.7 Project Information Signs:** No separate payment will be made for project information signs. Payment will be included under Maintenance of Traffic, lump sum.

**102-11.8 Channelizing Devices:** The number of drums, vertical panels, and Type I, Type II, Type III, or direction indicator barricades, certified as installed/used on the project meeting the requirements of [Design Standard Plans](#), Index ~~No.~~ [102-600](#) and have been properly maintained will be paid for at the Contract unit prices for channelizing device.

Payment for drums, vertical panels, and Type I, Type II, Type III, and direction indicator barricades will be paid per each per day.

Payment for vehicular LCDs will be paid as the length in feet installed divided by the device spacing for barricades, vertical panels, and drums and certified as installed/used on the project meeting the requirements of [Design Standard Plans](#), Index ~~No.~~ [102-600](#) and have been properly maintained will be paid for at the Contract unit price for channelizing device.

Payment for pedestrian LCDs will be paid as the plan quantity length in feet, in place and accepted. For sidewalk closures, the plan quantity length will be based on the width of the sidewalk. The quantity of pedestrian LCDs will be paid for regardless of whether materials are new, used, or relocated from a previous installation on the project. Placement of pedestrian LCDs at locations not shown in the Plans, or not authorized by the Engineer, will be at the Contractor's expense. Payment for pedestrian LCD mounted signs will be made under Work Zone Signs, per each per day.

Payment will not be made for channelizing devices unsatisfactorily maintained, as determined by the Engineer. Payment will be made for each channelizing device that is used to delineate trailer mounted devices. Payment will be made for channelizing devices delineating portable changeable message signs during the period beginning 14 working days before Contract Time begins as authorized by the Engineer.

**102-11.9 Temporary Barrier:** ~~The Contract unit price for temporary barrier will be full compensation for furnishing, installing, maintaining, and removing the barrier. The quantity to be paid for will be the length, in feet, of freestanding units or anchored units constructed and certified as installed/used on the project. When called for, the Contract unit price for barrier (temporary/relocate) will be full compensation~~ quantity to be paid for relocating the barrier will be based on the relocated condition installation type. The certified quantity to be paid for will be determined by the number of sections times the nominal length of each section. No separate payment will be made for the asphalt pad.

**102-11.10 Barrier Delineators:** No separate payment will be made for barrier delineators installed on top of temporary barrier and vehicular LCDs. Include the cost for barrier delineators in the cost of the barrier or vehicular LCD.

**102-11.11 Temporary Glare Screen:** The certified quantity to be paid for will be determined by the number of sections times the nominal length of each section.

**102-11.12 Temporary Crash Cushions:** No separate payment will be made for the concrete or asphalt pad.

**102-11.12.1 Redirective:** The quantity to be paid for will be the number of temporary crash cushions (redirective) certified as installed/used and maintained on the project, including object marker anchoring of temporary barrier necessary for transition to the crash cushion and delineation.

**102-11.12.2 Gating:** The quantity to be paid for will be the number of temporary crash cushions (gating) certified as installed/used and maintained on the project, including object marker anchoring of temporary barrier necessary for transition to the crash cushion and delineation.

**102-11.13 Temporary Guardrail:** The quantity to be paid for will be the length, in feet, of temporary guardrail constructed and certified as installed/used on the project. The length of a run of guardrail will be determined as a multiple of the nominal panel lengths.

**102-11.14 Arrow Board:** The quantity to be paid at the contract unit price will be for the number of arrow boards certified as installed/used on the project on any calendar day or portion thereof within the Contract Time.

**102-11.15 Portable Changeable Message Sign:** The quantity to be paid at the Contract unit price will be for the number of PCMSs or truck mounted changeable message signs certified as installed/used on the project on any calendar day or portion thereof within the Contract Time. Payment will be made for each portable changeable message sign that is used during the period beginning fourteen working days before Contract Time begins as authorized by the Engineer.

**102-11.16 Portable Regulatory Signs:** The quantity to be paid for will be the number of portable regulatory signs certified as installed/used on the project on any calendar day or portion thereof within the Contract Time, will be paid for the Contract unit price for portable regulatory sign.

**102-11.17 Radar Speed Display Unit:** The quantity to be paid for will be the number of radar speed display units certified as installed/used on the project on any calendar day or portion thereof within the Contract Time, will be paid for the Contract unit price for radar speed display unit.

**102-11.18 Temporary Signalization and Maintenance:** For existing intersections, the certified quantity to be paid for will be the number of signalized intersections per day for the full duration of the Contract. For temporary intersections, the certified quantity to be paid for will be the number of signalized intersections per day for the duration of the temporary intersection. No separate payment will be made for temporary signalization and maintenance at new intersections.

**102-11.19 Temporary Traffic Detection and Maintenance:** For existing intersections, the certified quantity to be paid for will be the number of signalized intersections per day beginning the day Contract Time begins and ending the day the permanent detection is operational and the final lane configuration is in place. For temporary and new intersections, the certified quantity to be paid for will be the number of signalized intersections per day beginning the day the temporary detection is functional and ending the day: the permanent detection is

operational and the final lane configuration is in place for a new intersection; or, when the detection is removed for a temporary intersection.

**102-11.20 Work Zone Pavement Markings:** The quantities of work zone pavement markings authorized and acceptably applied under this Section and certified as installed/used on the project, will be paid for as follows:

1. The length in gross miles, of solid, 10'-30' skip, 3'-9' dotted, 6'-10' dotted, and 2'-4' dotted lines.

The gross mile measurement will be taken as the distance from the beginning of the painted line to the end of the painted line and will include the unmarked gaps for skip and dotted lines. The gross mile measurement will not include designated unmarked lengths at intersections, turn lanes, etc. Final measurement will be determined by plan dimensions or stations, subject to 9-1.3.1.

2. The length, in linear feet, of transverse lines, diagonal lines, chevrons, and parking spaces.

3. The number of pavement messages, symbols, and arrows. Each arrow is paid as a complete marking, regardless of the number of "points" or directions.

4. The number of temporary RPM's authorized and acceptably applied.

**102-11.21 Temporary Raised Rumble Strips:** The quantity to be paid for will be the number of calendar days, or portions thereof, that temporary raised rumble strips are certified as installed/used on the project within the Contract Time. The number of strips used must meet the requirements of ~~the Design-Standard Plans~~, Index-~~No.~~ 102-603. No adjustment will be made to the per day measurement for the number of strips or sets used, or for the number of times the sets are relocated.

**102-11.22 Temporary Lane Separator:** The quantity to be paid for will be the field measure, in feet, of temporary lane separator certified as installed/used on the project, including drainage gaps, completed and accepted.

**102-11.23 Temporary Signals for Lane Closures on Two-Lane, Two-Way Roadways:** The quantity to be paid for will be the number of temporary signals per day installed/used at the locations shown in the Plans. Temporary signals installed/used at the Contractor's option as an alternative to flaggers will be included in Maintenance of Traffic, lump sum.

## **102-12 Submittals.**

**102-12.1 Submittal Instructions:** Prepare a certification of quantities, using the Department's current approved form, for certified MOT payment items for each project in the Contract. Submit the certification of quantities to the Engineer. The Department will not pay for any disputed items until the Engineer approves the certification of quantities.

**102-12.2 Contractor's Certification of Quantities:** Request payment by submitting a certification of quantities no later than Twelve O'clock noon Monday after the estimate cut-off date or as directed by the Engineer, based on the amount of work done or completed. Ensure the certification consists of the following:

1. Contract Number, FPID Number, Certification Number, Certification Date and the period that the certification represents.

2. The basis for arriving at the amount of the progress certification, less payments previously made and less an amount previously retained or withheld. The basis will include a detail breakdown provided on the certification of items of payment in accordance with 102-13. After the initial setup of the MOT items and counts, the interval for recording the counts will be

made weekly on the certification sheet unless there is a change. This change will be documented on the day of occurrence. Some items may necessitate a daily interval of recording the counts.

### **102-13 Basis of Payment.**

**102-13.1 Maintenance of Traffic (General Work):** When an item of work is included in the proposal, price and payment will be full compensation for all work and costs specified under this Section except as may be specifically covered for payment under other items.

**102-13.2 Traffic Control Officers:** Price and payment will be full compensation for the services of the traffic control officers.

**102-13.3 Special Detours:** Price and payment will be full compensation for providing all detour facilities shown in the Plans and all costs incurred in carrying out all requirements of this Section for general MOT within the limits of the detour, as shown in the Plans.

**102-13.4 Commercial Materials for Driveway Maintenance:** Price and payment will be full compensation for all work and materials specified for this item, including specifically all required shaping and maintaining of driveways.

**102-13.5 Work Zone Signs:** Price and payment will be full compensation for all work and materials for furnishing signs, supports and necessary hardware, installation, relocating, maintaining and removing signs.

**102-13.6. Business Signs:** Price and payment will be full compensation for all materials and labor required for furnishing, installing, relocating, maintaining, and removing the signs as well as the cost of installing any logos provided by business owners.

**102-13.7 Project Information Signs:** Price and payment will be full compensation for all materials and labor for furnishing, installing, relocating, maintaining and removing signs.

**102-13.8 Channelizing Devices:** Prices and payment will be full compensation for furnishing, installing, relocating, maintaining and removing the channelizing devices.

**102-13.9 Temporary Barrier:** Price and payment will be full compensation for furnishing, installing, maintaining, and removing the barrier and asphalt pad. When called for, temporary barrier (relocate) will be full compensation for relocating the barrier.

**102-13.10 Temporary Glare Screen:** Price and payment will be full compensation for furnishing, installing, maintaining, and removing the glare screen certified as installed/used on the project. When called for, glare screen (relocate) will be full compensation for relocating the glare screen.

**102-13.11 Temporary Crash Cushion (Redirective or /Gating):** Price and payment will be full compensation for furnishing, installing, maintaining, and subsequently removing ~~such~~ crash cushions and concrete or asphalt pads.

**102-13.12 Temporary Guardrail:** Price and payment will be full compensation for furnishing all materials required for a complete installation, including end anchorage assemblies and any end connections to other structures and for installing, maintaining and removing guardrail.

**102-13.13 Arrow Board:** Price and payment will be full compensation for furnishing, installing, operating, relocating, maintaining and removing arrow boards.

**102-13.14 Portable Changeable Message Sign:** Price and payment will be full compensation for furnishing, installing, operating, relocating, maintaining and removing portable changeable message signs.

**102-13.15 Portable Regulatory Signs:** Price and payment will be full compensation for furnishing, installing, relocating, operating, maintaining and removing a completely functioning system as described in these Specifications.

(REV 12-19-17) (FA 1-4-18) (7-18) includes 1020200, 1020917, 1020000, DgnStds2StdPlans

Payment will include all labor, materials, incidentals, repairs and any actions necessary to operate and maintain the unit at all times that work is being performed or traffic is being affected by construction and/or MOT operations.

**102-13.16 Radar Speed Display Unit:** Price and payment will be made only for a completely functioning system as described in these Specifications. Payment will include all labor, hardware, accessories, signs, and incidental items necessary for a complete system. Payment will include any measurements needed to insure that the unit conforms to all specification requirements.

Payment will include all labor, materials, incidentals, repairs and any actions necessary to operate and maintain the unit at all times that work is being performed or traffic is being affected by construction and/or MOT operations. Price and payment will be full compensation for furnishing, installing, operating, relocating, maintaining and removing radar speed display unit.

**102-13.17 Temporary Signalization and Maintenance:** Price and payment will constitute full compensation for furnishing, installing, operating, maintaining and removing temporary traffic control signals including all equipment and components necessary to provide an operable traffic signal. Payment will be withheld for each day at each intersection where the temporary signalization is not operational within 12 hours after notification.

**102-13.18 Temporary Traffic Detection and Maintenance:** Price and payment will constitute full compensation for furnishing, installing, operating, maintaining and removing temporary traffic detection including all equipment and components necessary to provide an acceptable signalized intersection. Take ownership of all equipment and components. Payment will be withheld for each day at each intersection where the temporary detection is not operational within 12 hours after notification.

**102-13.19 Work Zone Pavement Markings:** Price and payment will be full compensation for all work specified including, all cleaning and preparing of surfaces, furnishing of all materials, application, curing and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work. Final payment will be withheld until all deficiencies are corrected.

Removable tape may be substituted for standard paint at no additional cost to the Department.

Payment for temporary RPMs used to supplement line markings will be paid for under temporary ~~retroreflective~~ raised pavement markers. Install these ~~marker~~ RPMs as detailed in the Design Standard Plans.

**102-13.20 Temporary Raised Rumble Strips:** Price and payment will be full compensation for all work and materials described in this Section, including all cleaning and preparing of surfaces, disposal of all debris, furnishing of all materials, application, curing, removal, reinstalling and protection of all items, protection of traffic, furnishing of all tools, machines and equipment, and all incidentals necessary to complete the work.

**102-13.21 Temporary Lane Separator:** Price and payment will be full compensation for all work specified in this Section.

**102-13.22 Temporary Signals for Lane Closures on Two-Lane, Two-Way Roadways:** Price and payment will be full compensation for furnishing, installing, operating, maintaining and removing temporary traffic signal including all equipment and components necessary to provide an operable portable traffic signal.

**102-13.23 Payment Items:** Payment will be made under:

- Item No. 102- 1- Maintenance of Traffic - lump sum.
- Item No. 102- 2- Special Detour - lump sum.
- Item No. 102- 3- Commercial Material for Driveway Maintenance - per cubic yard.
- Item No. 102- 14- Traffic Control Officer - per hour.
- Item No. 102- 60- Work Zone Sign - per each per day.
- Item No. 102- 61- Business Sign - each.
- Item No. 102- 62- Barrier Mounted Work Zone Sign – per each per day
- Item No. 102- 71- Temporary Barrier - per foot.
- Item No. 102- 75- Temporary Lane Separator - per foot
- Item No. 102- 73- Temporary Guardrail - per foot.
- Item No. 102- 74- Channelizing Devices
- Item No. 102- 76- Arrow Board - per each per day.
- Item No. 102- 78- Temporary ~~Retroreflective~~Raised Pavement Markers - each.
- Item No. 102- 81- Temporary Crash Cushion, Gating - per location.
- Item No. 102- 89- Temporary Crash Cushion, Redirective - per location.
- Item No. 102- 94- Glare Screen - per foot.
- Item No. 102- 99- Portable Changeable Message Sign - per each per day.
- Item No. 102-104- Temporary Signalization and Maintenance - per intersection per day.
- Item No. 102-107- Temporary Traffic Detection and Maintenance - per intersection per day.
- Item No. 102-120- Temporary Signal for Lane Closures on Two-Lane, Two-Way Roadways – per each per day.
- Item No. 102-150- Portable Regulatory Sign - per each per day.
- Item No. 102-150- Radar Speed Display Unit - per each per day.
- Item No. 102-909- Temporary Raised Rumble Strips - per day.
- Item No. 102-911- Removable Tape (White/Black) - per gross mile.
- Item No. 102-912- Removable Tape (Yellow) - per gross mile.
- Item No. 710- Painted Pavement Markings.
- Item No. 711- Thermoplastic Pavement Markings.