



ELEVATION

END OF PHASE I CONSTRUCTION

## PHASE I SEQUENCE OF CONSTRUCTION:

- I. CONSTRUCT TEMPORARY SHEET PILE WALL.
- 2. EXCAVATE TO PROPOSED GROUNDLINE ELEVATION.
- 3. CONSTRUCT TEMP.MSE WALL AND PHASE I PORTIONS OF PERMANENT WALL.

## BRIDGE NO. XXXXXX

REVISIONS				STRUCTURES DESIGN OFFICE XXX MM-		STATE OF FLORIDA		SHEET TITLE.		REF. DWG. NO.
DATE BY	DESCRIPTION	DATE BY	DESCRIPTION	3 STRUCTURES DESIGN OFFICE	XXX MM-YY CHECKED BY	DEPARTMENT OF TRANSPORTATION		1	CONSTRUCTION SEQUENCE (SHEET   OF  )	
				CENTRAL OFFICE	XXX MM-YY					
				605 Suwannee Street, MS 33	DESIGNED BY:	ROAD NO. COUNTY FINA	NANCIAL PROJECT ID	PROJECT NAME:	CONSTRUCTION SEQUENCE EXAMPLE 3	SHEET NO.
				Tallahassee, Florida 32399-0450	CHECKED BY				TEMPORARY CRITICAL SHEET PILE WALL	