



When Other Construction Or Maintenance Operations Occur Within 1 mile, Sign(s) To Be Omitted And Signing To Be Coordinated In Accordance With Index No. 600.

Cones Or Tubular Markers At 25' Centers For First 250' Thereafter At 50' Centers Or Either Type I Or Type II Barricades Or Vertical Panels Or Drums At 50' Centers For First 250' Thereafter At 100' Centers.

Maximum Spacing Between Cones And Tubular Markers Shall Be 25'. Maximum Spacing Between Type I Or Type II Barricades Or Vertical Panels Or Drums Shall Be Based On The Speed Limit As Follows: 15' Up To 25 MPH; 30' For 30 - 40 MPH; 50' For 45 MPH And Greater.

SYMBOLS

Work Area

Sign With 18" x 18" (Min.) Orange Flag And Type B Light

Type I Or Type II Barricade Or Vertical Panel Or Drum (With Steady Burning Light At Night Only). (Tubular Markers May Be Used During Daylight Only. Cones May Be Used -See Index 600).

Work Zone Sign

Advance Warning Arrow Panel

GENERAL NOTES

- All vehicles, equipment, workers and their activities are restricted at all times to one side of the highway.
- The first two warning signs, each side, shall have an 18" x 18" (min.) orange flag and a Type B light attached and operating at all times.
Mesh signs may be used for (Daylight Only) operations. Type B Lights and Orange Flags are not required.
- All signs shall be post mounted if closure time exceeds 12 hours.
- L (min.) = WS for speeds \geq 45 mph

$$* WS^2 \text{ for speeds } \leq 40 \text{ mph}$$

$$60$$

Where:

W = Width of lateral transition in feet
S = Posted speed limit (mph).

- The LEFT LANE CLOSED and lane reduction signs are to be removed or fully covered when no work is being performed and the inside lane is open to traffic.
- Advance warning arrow panels are required for both day and night operation. Either the right flashing arrow or the right sequential arrow modes may be used; the caution mode shall not be used.
- Arrows denote direction of traffic only and do not reflect pavement marking.
- Longitudinal dimensions are to be adjusted to fit field conditions. See Index No. 600.
- When a side road intersects the highway on which work is being performed additional traffic control devices shall be erected in accordance with other applicable TCZ indexes.
- For work performed in the outside lane refer to Indexes Nos. 612 and 613. For work performed in the center lane refer to Index No. 616.
- For general TCZ requirements and additional information refer to Index No. 600.

CONDITIONS

WHERE ANY VEHICLE, EQUIPMENT, WORKERS OR THEIR ACTIVITIES WILL ENCOACH ON ANY PORTION OF THE INSIDE LANE OF A MULTILANE HIGHWAY

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION
ROAD DESIGN

TRAFFIC CONTROL THROUGH WORK ZONES

MULTILANE DIVIDED - RURAL

Drawn By	Checked By	Date	Scale	Project No.	Sheet No.	Revision	Approved By
AWP	AWP	00			1 of 1		