



PLAN




SECTION
TYPE C

Recommended Maximum Pipe Size:
2'-0" Wall 18" Pipe
3'-1" Wall 24" Pipe (18" where an 18" pipe enters a 2'-0" wall)




PLAN




SECTION
TYPE D

Recommended Maximum Pipe Size:
3'-1" Wall-24" Pipe
4'-1" Wall-36" Pipe




PLAN




SECTION
TYPE E

Recommended Maximum Pipe Size:
3'-0" Wall-24" Pipe
4'-6" Wall-36" Pipe




PLAN




SECTION
TYPE H

Recommended Maximum Pipe Size:
3'-0" Wall-24" Pipe
7'-8" Wall-1-66" Pipe
2-30" Pipe


INLETS




TYPE C
Approx. Weight 235 Lbs.



HALF SECTION CAST IRON GRATES




TYPE E
Approx. Weight 465 Lbs.




TYPE H
Approx. Weight 725 Lbs.


CAST IRON GRATES




TYPE C
Straight Bars 2" x 1/4"
Reticuline Bars 1 1/4" x 3/16"
Bands 2" x 1/4"
Approx. Weight 104 Lbs.



TYPE D
Straight Bars 2" x 1/4"
Reticuline Bars 1 1/4" x 3/16"
Bands 2" x 1/4"
Approx. Weight 190 Lbs.



TYPE E
Straight Bars 2" x 1/4"
Reticuline Bars 1 1/4" x 3/16"
Bands 2" x 1/4"
Approx. Weight 215 Lbs.



TYPE H
Straight End-Bearing Bars 2" x 3/8"
Straight Bearing Bars 2" x 1/4"
Reticuline Bars 1 1/4" x 3/16"
Bandling Bars 2" x 1/4"
Approx. Total Weight 310 Lbs.

NOTICE: Steel Grates Are Required On Inlets With Traversable Slots And On Inlets where Bicycle Traffic Is Anticipated.

STEEL GRATES



GENERAL NOTES

- These inlets are suitable for bicycle and pedestrian areas and are to be used in ditches, medians and other areas subject to infrequent traffic loadings but are not to be placed in areas subject to any heavy wheel loads.
- Inlets subject to minimal debris should be constructed without slots. Where debris is a problem inlets should be constructed with slots. Slotted inlets located within roadway clear zones and in areas accessible to pedestrians shall have traversable slots. The traversable slot modification is not adaptable to Inlet Type H. Slots may be constructed at either or both ends as shown on plans.
- Steel grates are to be used on all inlets where bicycle traffic is anticipated. Steel grates are to be used on all inlets with traversable slots. Either cast iron or steel grates may be used on inlets without slots where bicycle traffic is not anticipated. Either cast iron or steel grates may be used on all inlets with non-traversable slots. Subject to the selection described above, when Alternate G grate is specified in the plans, either the steel grate, hot dipped galvanized after fabrication, or the cast iron grate may be used, unless the plans stipulate the particular type.
- Recommended maximum pipe sizes shown are for concrete pipe. Size for other types of pipe must be checked for fit.
- All exposed corners and edges of concrete are to be chamfered 3/4".
- Concrete inlet pavement to be used on inlets without slots and inlets with non-traversable slots only when called for in the plans; but required on all traversable slot inlets. Cost to be included in contract unit price for inlets. Quantities shown are for information only.
- Traversable slots constructed in existing inlets shall be paid for as inlets partial, and shall include the cost for slot openings, concrete inlet pavement and any required replacement grates.
- Sodding to be used on all inlets not located in paved areas and paid for under contract concrete inlet pavement unit price for Sodding, SY.
- For supplementary details see Index No. 201.


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

DITCH BOTTOM INLETS TYPES C, D, E & H


Designed By	Names	Dates	Approved By		
Drawn By			 State Drainage Engineer	Revision	Sheet No.
Checked By	EGR/JG	07/81		02	1 of 5



SECTION AA



SECTION BB



PAVEMENT AND SODDING QUANTITIES
FOR TRAVERSABLE SLOTS


Inlet	Pavement				Sod	
	Single Slot		Double Slot		Single Slot	Double Slot
	SY	CY	SY	CY	SY	SY
C	4.87	0.77	6.16	0.93	12	16
D	5.99	0.91	7.70	1.10	14	19
E	5.88	0.91	7.37	1.08	14	18

TRAVERSABLE SLOTS


STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

DITCH BOTTOM INLETS
TYPES C, D, E, & H


Names	Dates	Approved By <i>S. A. McHenry</i>		
Designed By EGR	02/80	State Drainage Engineer		
Drawn By JM	02/80	Revision	Sheet No.	Index No.
Checked By JVG	02/80	00	2 of 5	232




NOTE: See General Notes Nos. 6 and 7
SODDING AND PAVEMENT FOR INLETS WITHOUT SLOTS AND INLETS WITH NON-TRAVERSABLE SLOTS



DITCH BLOCK FOR INLETS WITH OR WITHOUT SLOTS




SECTION AA



SECTION BB

Inlet	PAVEMENT AND SODDING QUANTITIES FOR TRAVERSABLE SLOTS			
	Pavement		Sod	
	Single Slot SY	Double Slot CY	Single Slot SY	Double Slot SY
C	4.87	0.83	6.16	1.05
D	5.99	1.01	7.70	1.30
E	5.88	0.99	7.37	1.24



SINGLE SLOT SHOWN (DOUBLE SLOTS SYMMETRICAL ABOUT CENTERLINE) SECTION CC (CASE 1)

NOTE: For plan view and additional details see sheet 2 of 4.
 For payment see General Notes Nos. 6 and 7.

TRAVERSABLE SLOTS FOR EXISTING INLETS

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

DITCH BOTTOM INLETS TYPES C,D,E & H

Names	Dates	Approved By		
Designed By	EGR 07/84	S. A. McHenry State Roadway Design Engineer		
Drawn By	DAE 07/84			
Checked By	JBW/JVG 07/84	Revision	Sheet No.	Index No.
		00	3 of 5	232

DESIGN NOTES FOR TRAVERSABLE SLOT INLETS (PARTIAL) FOR EXISTING INLETS

1. The general purpose of these conversions is to remove the hazard of the protruding inlet top, while not creating a hazard by depressing the top too deeply.
2. The corrective procedure depends on the approach ditch grade and hydraulic requirements of the site. The selection of the appropriate case depends on the relationship between inlet top and ditch elevation, and, on the vertical clearance between the top of the uppermost pipe(s) and the grate. The purpose for the Case 1 conversion is to add the traversable slot to an existing inlet where top removal, change in grate elevation and ditch transitions are not required. Case 2 will normally be applicable to ditches with flatter grades adjoining the inlet. Case 3 will normally be applicable to ditches with steeper grades adjoining the inlet where buildup of the existing ditch is acceptable.
3. The designer shall stipulate in the plans which case is to be constructed at each individual inlet location.

Where the existing inlet top is above the existing ditch (Case 2) but borrow material will be required to adjust the ditch (Case 3), and vertical clearance or other conditions do not prevent removal of the inlet top, the designer should call for Case 2. The designer shall determine if ditch reconstruction is required more than 35 feet beyond any traversable slot side and shall include separate pay items in the plans to cover the cost for that portion of required ditch reconstruction exceeding the 35 foot limit. The designer shall also determine whether ditch pavement is required for ditch restoration within the 35 foot limit and include that pavement under a pay item separate from the inlets partial.

When the detention ditch concept is to be used with Case 3, the designer shall stipulate 'Case 3 (Detention)' in the plans.


The designer shall determine whether tight soil or other conditions at each individual inlet indicates the need for underdrain in Case 3 conversions and shall call for Underdrain, Type I in the plans.

METHOD OF PAYMENT FOR TRAVERSABLE SLOT INLETS (PARTIAL) FOR EXISTING INLETS


1. Existing inlets converted to traversable slot tops under Cases 1, 2 and 3 shall be paid for as inlets partial, each. Case shall not be included in the pay item description.
2. All ditch reconstruction work within 35 feet of each traversable slot conversion, whether required by these details or as a direct result of the conversion, shall be included as a part of the partial cost. Reconstruction work shall include excavation and removal of surplus materials or borrow materials in place, grading, compaction, shaping and seeding and mulching. Sodding, ditch pavement and underdrain are not included as part of the inlet partial cost and are to be paid for separately.
3. Concrete inlet pavement and sodding shall be in accordance with the sections on this detail and with the Plan on Sheet 2 and Sections AA, BB and CC (as Case 1) and tabular quantities on Sheet 3.
4. Unit price and payment shall constitute full compensation for inlet conversion (including concrete inlet paving and replacement grate (s)), ditch reconstruction, seeding and mulching, and shall be paid for under the contract price for Inlets (DT Bot) (Type ___) (Partial), each.

Sodding shall be paid for under the contract unit price for Sodding, SY.

Ditch pavement shall be paid for separate from the inlet by pavement type(s) and unit(s) as called for in the plans.



**SINGLE SLOT SHOWN (DOUBLE SLOTS SYMMETRICAL ABOUT CENTERLINE)
SECTION CC (CASE 2)**







**SINGLE SLOT SHOWN (DOUBLE SLOTS SYMMETRICAL ABOUT CENTERLINE)
SECTION CC (CASE 3)**

TRAVERSABLE SLOT INLETS (PARTIAL) FOR EXISTING INLETS

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

**DITCH BOTTOM INLETS
TYPES C, D, E & H**

Names	Dates	Approved By			
Designed By	JVG/EGR 3/10/86	 State Drainage Engineer			
Drawn By	HSD/dde 5/20/86				
Checked By	JVG/EGR 5/22/86				
Revision	00				Sheet No.




See Index No. 200 for structure bottom details and hole reinforcement.

ALT. B STRUCTURE BOTTOM FOR INLETS TYPE C, D & E

TOP SLAB OPENINGS		
DIAMETER	OPENING SIZE	
	MIN.	MAX.
4'-0"	2'-0" x 3'-1"	2'-0" x 3'-1"
5'-0"	2'-0" x 3'-1"	3'-1" x 4'-1"
6'-0"	2'-0" x 3'-1"	3'-0" x 4'-4"
8'-0"	2'-0" x 3'-1"	3'-0" x 4'-4"


TOP SLAB REINFORCING DIAGRAM



SECTION BB

TOP SLAB WITH CENTERED OPENING		
SLAB DEPTH	SLAB THICKNESS	REINFORCING (2 WAYS) SCHEDULE
SIZE: 4'-0"		
≥ 0.5'-40'	9 1/2"	C
SIZE: 5'-0"		
≥ 0.5' < 30'	9 1/2"	C
30'-40'	9 1/2"	D
SIZE: 6'-0"		
0.5' < 8'	9 1/2"	B
8' < 18'	9 1/2"	C
18' < 30'	9 1/2"	D
30' < 37'	9 1/2"	E
37'-40'	9 1/2"	G
SIZE: 8'-0"		
≥ 0.5' < 9'	11 1/2"	C
9' < 15'	11 1/2"	D
15' < 23'	11 1/2"	E
23' < 33'	11 1/2"	E
33'-40'	11 1/2"	G

TOP SLAB REINFORCING SCHEDULE	
SCHEDULE	GRADE 60 OR 65KSI OR (WIRE FABRIC) In ² /ft
A	0.20
B	0.24
C	0.37
D	0.53
E	0.73
F	1.06
G	1.45



SECTION AA

ALT. A STRUCTURE BOTTOM FOR INLETS TYPE C, D AND E

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

DITCH BOTTOM INLETS TYPES C, D, E & H

Names	Date	Approved By	S. A. McHenry	
Designed By		State Drainage Engineer		
Drawn By	JDP	02/99	Revision	Sheet No. 5 of 5
Checked By			00	Index No. 232