

Remove Overlying Material And Organic Material Within The Limits Shown And Backfill In Accordance With Index No. 505, Unless Otherwise Called For In The Plans Or Directed Otherwise By The District Geotechnical Engineer; The Limits Include Full Median Width When Applied To Divided Facilities With Median Widths Up To 64'; When Median Width Is Greater Than 64' And For Bifurcated Roadways The Organic Material Removal Limits Will Be Set By A 1: 2 Control Line Complimentary To The Outer Roadway That Will Accommodate One Future Median Lane On Each Roadway Unless Specified Otherwise By The Plans.



WITH OVERBURDEN - HALF SECTION

Remove Overlying Material And Organic Material Within The Limits Shown And Backfill In Accordance With Index No. 505, Unless Otherwise Called For In The Plans Or Directed Otherwise By The District Geotechnical Engineer; The Limits Include Full Median Width When Applied To Divided Facilities With Median Widths Up To 64'; When Median Width Is Greater Than 64' And For Bifurcated Roadways The Organic Material Removal Limits Will Be Set By A I: 2 Control Line Complimentary To The Outer Roadway That Will Accomodate One Future Median Lane On Each Roadway Unless Specified Otherwise By The Plans.




Back Of Proposed Or Future Sidewalk

WITHOUT OVERBURDEN - HALF SECTION

Outer Roadway


IN RURAL CONSTRUCTION

Remove Overlying Material And Organic
Material Within The Limits Shown And
Backfill In Accordance With Index No. 505,
Unless Otherwise Called For In The Plans
Or Directed Otherwise By The District
Geotechnical Engineer; The Limits Include
Full Median Width When Applied To Divided
Facilities With Median Widths Up To 64';
When Median Width Is Greater Than 64'
When Median Width Is Greater Than 64'
When Median Width Is Greater Than 64'
When Median Will Be Set By A
I: 2 Control Line Complimentary To The
Outer Roadway That Will Accomodate One
Future Median Lane On Each Roadway
Unless Specified Otherwise By The Plans.



WITH OVERBURDEN - HALF SECTION

Remove Overlying Material And Organic Material Within The Limits Shown And Backfill In Accordance With Index No. 505,—Unless Otherwise Called For In The Plans Or Directed Otherwise By The District Geotechnical Engineer; The Limits Include Full Median Width When Applied To Divided Facilities With Median Widths Up To 64'; When Median Width Is Greater Than 64' And For Bifurcated Roadways The Organic Material Removal Limits Will Be Set By A 1:2 Control Line Complimentary To The Outer Roadway That Will Accomodate One Future Median Lane On Each Roadway Unless Specified Otherwise By The Plans.



WITHOUT OVERBURDEN - HALF SECTION

IN URBAN CONSTRUCTION

REMOVAL OF ORGANIC MATERIAL

GENERAL NOTES

- I. All details shown on this index for removal of organic and plastic materials apply unless otherwise shown on the plans.
- 2. Utilization of excavated materials shall be in accordance with Index No. 505.
- 3. Where organic or plastic material is undercut, backfill shall be made of suitable material in accordance with Index No. 505, unless otherwise shown on the plans.
- The term "Plastic Material" used in this index in conjunction with removal of plastic soil is as defined under soil classifications for Plastic (P) and High Plastic (H) on Index No. 505.
- 5. The term "Organic Material" as used on this index is defined as any soil which has an average organic content greater than five (5.0) percent, or an individual organic content test result which exceeds seven (7.0) percent. Organic material shall be removed as shown on this index and the plans unless directed otherwise by the District Geotechnical Engineer.

Average organic content shall be determined from the test results from a minimum of three randomly selected samples from each stratum. Tests shall be performed in accordance with AASHTO T 267 on the portion of a sample passing the No. 4 sieve.

- 6. The normal depth of side ditches shall be 3.5' below the shoulder point except in special cases.
- 7. In municipal areas, where underdrain is to be constructed beneath the proposed pavement, the grade of the underdrain filter material will not extend above the bottom of the stabilized section of the subgrade. Gradation of the filter material shall conform to FDOT specifications. Minimum grade on underdrain pipe shall be 0.2%.
- 8. See Index No. 506 for miscellaneous earthwork details.


DESIGN NOTES

- I. At locations where organic material or other soft soil deposits persists to such depth that removal is impractical, the construction of a geosynthetic foundation over those soils should be considered. The Engineer of Record should request quidance from the District Geotechnical Engineer and make a geosynthetic foundatuion design in accordance with Index No. 50I when pursuing geosynthetic alternates.
- The designer shall take into consideration the expectancy of roadway widening to the outside, and where widening is anticipated specify in the plans the limits of removal of organic and plastic materials necessary to accommodate anticipated widening.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

REMOVAL OF ORGANIC AND PLASTIC MATERIAL

	Names	Dates	Approve	et By	00 -	
Designed By	GEOTECH	9/93	State Geotechnical Engineer			
Drawn By	НКН	9/93	Revision	Sheet No.	/ Index No.	
Checked By	BTD/FLS	9/93	02	1 of 2	500	



Inner And Outer Cut Limit For Preferable Removal Of Plastic Material. Where Preferable Method Of Removal Governs And It Is Impossible To Place The Underdrain At The Outer Cut Limit Due To Conflict With Storm Sewer Mains, Remove To Inner Limit And Place Underdrain At Location Shown For Minimum Removal.

Extended Undercut Slope When Underdrain Located At Outer Control Line Limit

0.02 Undercut Backslope When Underdrain Located At Back Of Curb Underdrain, See Index No. 286 Minimum Grade On Underdrain Pipe Shall Be 0.2%.

HALF SECTION

 ${\it NOTES:}\ Refer\ to\ roadway\ cross\ sections\ to\ determine\ whether\ minimum\ or\ preferable\ removal\ is\ used.$ *Where frequency of median breaks indicates that it is impractical to leave plastic material in the median, the designer may elect to indicate total removal of this material.

If during construction it becomes apparent, due to normal required construction procedures, that it is impractical to leave the plastic material in the median, total removal of this material shall be approved by the Engineer.

REMOVAL OF PLASTIC MATERIAL AND LOCATION OF UNDERDRAIN IN URBAN CONSTRUCTION




At locations where plastic material is being removed, the side ditches must be at least as deep as the undercut plane.


Where paved side ditches are used in areas of removal of plastic material, the top of the ditch pavement must be no higher than the undercut plane.

Undercut Line

MISCELLANEOUS DETAILS




TYPICAL CUT SECTION ON TANGENT



TYPICAL CUT SECTION ON SUPERELEVATION

REMOVAL OF PLASTIC MATERIAL ON INTERSTATE FACILITIES, FREEWAYS, DIVIDED ARTERIALS AND MAJOR COLLECTORS HAVING DEPRESSED MEDIANS



TYPICAL CUT SECTION

Note: When this detail is applied to minor collectors and local facilities, the undercut may be reduced to 18".

REMOVAL OF PLASTIC MATERIAL ON DIVIDED FREEWAYS, ARTERIALS AND MAJOR COLLECTORS HAVING FLUSH MEDIANS, AND, ON UNDIVIDED ARTERIALS AND MAJOR COLLECTORS

REMOVAL OF PLASTIC MATERIAL

Note: For GENERAL NOTES see Sheet I.

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION

REMOVAL OF ORGANIC AND PLASTIC MATERIAL

	Names	Dates	Approved-By			
Designed By	KHH/WNL	05/91	State Geotechnical Engineer			
Drawn By	нкн	05/91	Revision	Sheet No.	/ Index No.	
Checked By	JVG/WNL	05/91	00	2 of 2	500	