




NARROW MEDIAN WITH OR WITHOUT CURBED MEDIAN

WIDE MEDIAN WITH OR WITHOUT CURBED MEDIAN DIVIDED







DIVIDED CURBED

LEGEND

Concrete Sidewalk

- 1 Wildflower Group #1
- 2 Wildflower Group #2
- Grass-Seed/Seed & Mulch (To Limit of Construction)
- Selective Clearing SCG And Grubbing
- Limits Of Construction
- Seed, Seed And Mulch, Sod Or Seed, Sod

GRASS SEEDING RATES (Lbs/Ac)

5. II. 100 0111111 7 11 12 1 12 10 7 10 7									
TYPE OF SEED	ZONE I				ZONE II				
	COASTAL*		INLAND		COASTAL*		INLAND		
	Mar. to Nov.	Nov. to Mar.	Mar. to Nov.	Nov. to Mar.	Feb. to Dec.	Dec. to Feb.	Feb. to Dec.	Dec. to Feb.	
PERMANENT GRASSES									
Unhulled Bermuda**		90		20		90		20	
Hulled Bermuda **	60		15		60		<i>1</i> 5		
Bahia (Argentine Or Pensacola)			180	180			180	180	
QUICK GROWING GRASS									
Annual Rye Grass		90		90		90		90	
TOTAL POUNDS PER ACRE	60	180	195	290	60	180	195	290	

*Locations where salt sensitive plants may be adversely affected by high concentrations of salts in soils, water or air. This may include seaside locations, low-lying areas subjected to periodic saltwater inundation from storms or high tides, or where salt intrusion into groundwater supply has occurred.

Note: All seeding shall be performed meeting the requirements of Section 570 of the Standard Specifications.

GENERAL NOTE

Activities such as clearing, grading, and excavating that will disturb one or more acres of land require coverage under the Generic Permit for Stormwater Discharge from Large and Small Construction Activities from the Florida Department of Environmental Protection, and implementation of appropriate pollution prevention measures to minimize erosion and sedimentation and properly manage stormwater.

SEEDING RATE ZONES

UNDIVIDED CURBED



WILDFLOWER SEEDING RATES					
Common Name (Botanical Name)					
#I Group					
Black-Eyed Susan (Rudbeckia hirta)	2				
Lance-Leaf Tickseed (Coreopsis lanceolata)					
Goldenmane Tickseed (Coreopsis basalis)	10				
Leavenworth's Tickseed (Coreopsis leavenworthii)					
Fire Wheel (Gaillardia pulchella)	10				
Softhair Coneflower (Rudbeckia mollis)	2				
Crimson Clover (Trifolium incarnatum)	<i>1</i> 5				
#2 Group					
Annual Phlox (Phlox drummondii)	10				
Moss Verbena (Verbena tenuisecta)	6				
Leavenworth's Tickseed (Coreopsis leavenworthii)	10				
Fire Wheel(Gaillardia pulchella)	10				
Crimson Clover (Trifolium incarnatum)	15				

GENERAL NOTE

Confirm compatibility of wildflower with Grass Rate Zones.



2006 FDOT Design Standards

Sheet No.

07/01/05 1 of 2

PERMANENT EROSION CONTROL

104

^{**}Bermuda shall not be used in areas adjacent to existing or proposed landscaping.

