HIGHMAST LIGHTING NOTES:

- 1) High Mast materials:
- a. Pole: ASTM A1011 Grade 50, 55, 60 or 65 (Less than $\frac{1}{4}$ ") or ASTM A572 Grade 50, 55, 60, or 65 ($\frac{1}{4}$ " and over) or ASTM A595 Grade A (55 ksiyield) or Grade B (60 ksiyield).
- b. Steel Plates: ASTM A709 Grade 36 or ASTM A36
- c. Weld Metal: E70XX
- d. Anchor Bolts: ASTM F1554 Grade 55 with ASTM A563, Grade A heavy-hex nuts and ASTM F436 Type I washers.
- e. Handhole: ASTM A709 Grade 36 or ASTM A36 Frame with ASTM A36 cover.
- f. Caps: ASTM A1011 Grade 50, 55, 60 or 65 or ASTM B209.
- g. Nut Covers: ASTM B26 (319-F)
- h. Stainless Steel Screws: AISI Type 316
- 2) Reinforcing steel: ASTM A615, Grade 60.
- 3) Concrete: Class IV (Drilled Shaft) with a minimum 4,000 psicompressive strength at 28 days for all environmental classifications.
- 4) Grout: minimum 5,000 psi compressive strength at 28-days and meeting the requirements of Section 934.
- 5) Welding: American Welding Society Structural Welding Code (Steel) ANSI/AWS DI.1 (Current edition).
- 6) Galvanization:
- a. Nuts, Bolts, Washers and Threaded Bars/Studs: ASTM F2329.
- b. Other items (Including Pole): ASTM A123
- 7) Hole diameters for anchor bolts: not greater than the bolt diameter plus $\frac{1}{2}$ ".
- 8) Poles: Tapered with the diameter changing at a rate of 0.14 inch per foot with a minimum 16-sided pole shaft and only one longitudinal seam weld. Circumferentially welded pole shaft butt splices and laminated pole shafts are not permitted. Longitudinal seam welds within 6 inches of pole to base must be complete penetration welds. Longitudinal seam welds at telescopic field joints must be complete penetration welds for the splice length plus 6 inches.
- 9) If a grout pad is not installed, place wire cloth screen vertically between the base plate and top of foundation, wrap horizontally around the base plate with a 3" min. lap. Use standard grade, plain weave, \(\frac{1}{2} \)" x\(\frac{1}{2} \)" mesh, galvanized steel wire-cloth with 0.063" dia. wire. Attach the screen to the base plate with stainless steel self-tapping \(\frac{1}{4} \)" screws with stainless steel washers spaced at 9" centers.
- 10) One hundred percent of full-penetration groove welds and a random 25 percent of partial penetration groove welds shall be inspected. Full-penetration groove weld inspection shall be performed by nondestructive methods of radiography or ultrasonics.
- II) Furnish each pole with a 2"x4" (max.) aluminum identification tag. Submit details for approval. Secure to pole with 0.124" stainless steel rivets or screws. Locate identification tag on the inside of pole and visible from handhole. Include the following information: Financial Project ID, Pole Height, Manufacturer's Name, Certification Number and QPL Number.
- 12) Manufacturers seeking approval of a Highmast Lighting assembly for inclusion on the Qualified Products List must submit a QPL Production Evaluation Application along with drawings showing the product meets all specified requirements of this Index.

DESIGN CRITERIA:

- 1) Designed in accordance with the FDOT Structures Manual.
- 2) Poles are designed to support the following:
 - a. (1) cylindrical head assembly with a maximum effective projected area of 6 Sq. ft. (Cd=1) and 340 lbs (Max)
 - b. (8) cylindrical luminaires with a maximum effective projected area of 3.0 Sq. ft (Cd=0.5) and 77 lbs. each.
- 3). Foundation design based upon the following soil criteria:

Classification = Cohesionless (Fine Sand)

Friction Angle = 30 Degrees (30°)

Unit Weight = 50 lbs./cu. Ft. (assumed saturated)

Only in cases where the Designer considers the soil types at the specific site location to be of lesser strength properties should an analysis be required. Auger borings, SPT borings or CPT soundings may be utilized as needed to verify the assumed soil properties, and at relatively uniform sites, a single boring or sounding may cover several foundations. Furthermore, borings in the area that were performed for other purposes may be used to confirm the assumed soil properties.

- 4) Foundation applies only to slopes of 1:4 or flatter. Provide a minimum 24" shaft projection on the high side.
- 5) Poles are designed for 6 mil galvanization thickness.

STANDARD POLE DESIGN NOTES


REVISIONS

DATE BY DESCRIPTION DATE BY DESCRIPTION

01/01/08 DYW Changed Note 9, Renumbered Notes 10 thru 12. Added Notes 10 thru 13. Added Notes 10 thru 14. Added Notes 10 thru 14. Added Notes 10 thru 15. Added Notes 10 t



HIGHMAST LIGHTING



Pole Design Table∗

Design Wind	Pole Overall Height	Section 1 (Top)					Section 2				Section 3					
Speed		Length.	Wall Th.	Minimum Splice L.	Tip Dia.	Base Dia.	Length.	Wall Th.	Minimum Splice L.	Tip Dia.	Base Dia.	Length.	Wall Th.	Minimum Splice L.	Tip Dia.	Base Dia.
	80 ft	42'-0''	0.250"	2'-0"	5.313"	11.219"	40'-0''	0.250"		10.375"	16.000"					
110 mph	100 ft	24'-6"	0.179"	2'-0"	6.406"	9.844"	40'-0"	0.250"	2'-6"	9.188"	14.781''	40'-0"	0.250"		13.875"	19.500"
	120 ft	44'-9''	0.250"	2'-0"	6.250"	12.531"	40'-0''	0.250"	2'-9''	11.688''	17.313''	40'-0''	0.313"		16.375"	22.000"
	80 ft	42'-0"	0.250"	2'-0"	5.281"	11.188''	40'-0''	0.313"		10.375"	16.000"					
130 mph	100 ft	24'-6"	0.179''	2'-0"	6.906"	10.344"	40'-0''	0.250"	2'-6"	9.656"	15.281"	40'-0''	0.313"		14.375"	20.000"
	120 ft	45'-6"	0.250"	2'-6"	9.250"	15.625"	40'-0''	0.250"	3'-0''	14.719''	20.344"	40'-0''	0.313"		19.375"	25.000"
	80 ft	42'-3''	0.250"	2'-3"	7.281''	13.219"	40'-0''	0.313"		12.375"	18.000''					
150 mph	100 ft	24'-6"	0.250"	2'-0"	8.188''	11.625"	40'-0''	0.313"	2'-6"	10.781''	16.406"	40'-0''	0.375"		15.375"	21.000"
	120 ft	46'-6''	0.250"	3'-0"	12.406"	18.938''	40'-0''	0.313"	3'-6''	17.938''	23.563"	40'-0"	0.375"		22.375"	28.000"

^{*} Diameter Measured Flat to Flat

Base Plate and Bolts Design Table


Design Wind Speed.	Pole Overall Height	Base Plate Diameter	Base Plate Thickness	''TW''	''BW''	Bolt Circle	No. Bolts	Bolt Diameter	Bolt Embedment
	80 ft	30.0"	2.500"	0.375"	0.188''	23.0"	8	1.75"	38"
110 mph	100 ft	33.5"	2.500"	0.375"	0.188''	26.5"	8	1.75"	42"
	120 ft	36.0"	2.750"	0.375"	0.250"	29.0"	8	1.75"	45"
	80 ft	30.0"	2.500"	0.438''	0.250"	23.0"	8	1.75"	43''
130 mph	100 ft	34.0"	2.750"	0.438''	0.250"	27.0"	8	1.75''	50"
	120 ft	41.0''	3.250"	0.500"	0.250"	33.0"	8	2.00"	52"
	80 ft	32.0"	2.750"	0.500"	0.250"	25.0"	8	1.75"	49''
150 mph	100 ft	37.0"	3.000"	0.563"	0.313''	29.0"	8	2.00"	53"
	120 ft	46.0"	3.250"	0.563"	0.313"	37.0"	10	2.25"	57''


Shaft Design Table

Pole Overall Height	Shaft Diameter	Shaft Length	Longitudinal Reinforcement		
80 ft	4'-0''	13'-0''	16 - # 10		
100 ft	4'-0''	15'-0''	16 - # 10		
120 ft	4'-6''	16'-0''	20 - # 10		
80 ft	4'-0''	14'-0''	16 - # 10		
100 ft	4'-0''	16'-0''	16 - # 10		
120 ft	4'-6''	18'-0''	20 - # 10		
80 ft	4'-0''	16'-0''	16 - # 10		
100 ft	4'-6''	17'-0''	20 - # 10		
120 ft	5'-0''	20'-0''	24 - # 10		
	80 ft 100 ft 120 ft 80 ft 120 ft 120 ft 100 ft 120 ft 100 ft 120 ft 100 ft	Overall Height Shart Diameter 80 ft 4'-0" 100 ft 4'-0" 120 ft 4'-6" 80 ft 4'-0" 100 ft 4'-0" 80 ft 4'-6" 80 ft 4'-6" 100 ft 4'-6"	Overall Height Shart Diameter Shart Length 80 ft 4'-0" 13'-0" 100 ft 4'-0" 15'-0" 120 ft 4'-6" 16'-0" 80 ft 4'-0" 14'-0" 100 ft 4'-6" 18'-0" 80 ft 4'-6" 16'-0" 100 ft 4'-6" 17'-0"		

POLE DESIGN TABLES

	REVISIONS	THE OF FLORID	2008 Interim Design Standard	Interim Sheet No.
F	DATE BY DESCRIPTION DATE BY DESCRIPTION 01/01/08 DYW Added ID Plate to ELEVATION, Changed dimensions in 'Base			01/01/08 4 of 7
	Plate Thickness' column.	THE TRANSPORTE	HIGHMAST LIGHTING	17502





REVISIONS						THE OF FLORID	2008 Interim Design Standard	Interim Date	Sheet No.
01	DATE BY	DESCRIPTION Changed Wold symbol in SECTION A=A Added Radiock Tab to	DATE	BY	DESCRIPTION			01/01/08	5 of 7
017	01/08 DYW	Changed Weld symbol in SECTION A-A, Added Padlock Tab to HANDHOLE RING.				PARTITION OF TRAINS	HIGHMAST LIGHTING	1 7 lnde	502