

PRESTRESSED SLAB UNIT CAMBER AND OVERLAY NOTES:

The overlay values given in the table are based on theoretical unit cambers. The Contractor shall monitor unit cambers for the purpose of predicting camber values at the time of the deck pour. If the predicted cambers based on field measurements differ more than $\pm \frac{1}{2}$ " from the theoretical "Net Unit Camber @ 120 Days" shown in the table, propose modifed overlay dimensions as required and submit to the Engineer for approval a minimum of 21 days prior to casting overlay concrete.



DEAD LOAD DEFLECTION DIAGRAM





OVERLAY & DEFL	
FOR PRESTRESSE	l