


**PLAN (BRIDGE MOUNTED RAILING/SOUND BARRIER SHOWN, WALL OR FOOTING MOUNTED RAILING/SOUND BARRIER SIMILAR) (Reinforcing Steel not shown for clarity)**

**CROSS REFERENCE:**  
 For Detail "B" and V-Groove Lettering Detail see Sheet 2.  
 For Section A-A see Sheet 4.  
 For Section C-C and Detail "A" see Sheet 5.  
 For Wall mounted Railing/Sound Barrier Details see Index No. 5212.  
 For Footing mounted Railing/Sound Barrier Details see Index Nos. 5213 (T-Shaped), 5214 (L-Shaped) or 5215 (Trench).




**ELEVATION OF INSIDE FACE OF RAILING/SOUND BARRIER (BRIDGE MOUNTED RAILING/SOUND BARRIER SHOWN, WALL OR FOOTING MOUNTED RAILING/SOUND BARRIER SIMILAR) (Reinforcing Steel not shown for clarity)**

T-Shaped Spread Footing Shown, L-Shaped Spread Footing, Trench Footing Similar and Junction Slab similar

\* On Bridges see Superstructure and Approach Slab Sheets for actual dimensions and joint orientation. Open Railing/Sound Barrier Joints at Deck Expansion Joint locations shall match the dimensions of the Deck Joint. For treatment of Railing/Sound Barrier walls on skewed bridges see Index No. 420. Deck Joint at Begin Bridge or End Bridge shown, Deck Joint at  $\bar{C}$  Pier or Intermediate Bent, Junction Slab or Footing similar.

\*\*  $\frac{3}{4}$ " Intermediate Open Joints shall be constructed plumb and provided at :  
 (1) - Superstructure supports where slab is continuous.  
 (2) - Construction Joints for Junction Slabs and Footings.

REVISIONS				DATE		DESCRIPTION	
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION		
07/01/10	GJM	Deleted INSTRUCTIONS TO DESIGNER. Changed spacing of V-Grooves and Intermediate Open Joint.					
01/01/11	SJN	Changed note * reference to Index 490 and Mortar Plug to Pre-cured Silicone Sealant in ELEVATION.					



2010 Interim Design Standard

**TRAFFIC RAILING/SOUND BARRIER (8'-0")**

Interim Date	Sheet No.
01/01/11	1 of 5
Index No.	
<b>5210</b>	

**TRAFFIC RAILING/SOUND BARRIER NOTES**



This railing has been structurally evaluated to be equivalent or greater in strength to a safety shape/sound barrier combination railing which has been crash tested to NCHRP Report 350 TL-4 Criteria. The Transverse Design Force for the design of bridge deck overhang shall be 54 kips applied horizontally at 3'-6" height above the deck.

- CONSTRUCTION REQUIREMENTS :** The Traffic Railing/Sound Barrier and joints shall be constructed plumb, they shall not be constructed perpendicular to the roadway surface. Slip forming is not permitted.
- CONCRETE AND REINFORCING STEEL :** For Railing/Sound Barrier on bridges see General Notes. For Wall and Footing mounted Railing/Sound Barrier, concrete shall be Class II for slightly aggressive environments and Class IV for moderately or extremely aggressive environments. All reinforcing steel shall be Grade 60.
- NAME, DATE AND BRIDGE NUMBER :** For Railing/Sound Barrier on bridges, the Name and Bridge Number shall be placed on the Traffic Railing so as to be seen on the driver's right side when approaching the bridge. The Date shall be placed on the driver's left side when approaching the bridge. The Name shall be as shown in the General Notes in the Structures Plans. The Date shall be the year the bridge is completed. For a widening when the existing railing is removed, use both the existing date and the year of the widening. Black plastic letters and figures 3" in height may be used, as approved by the Engineer, in lieu of the letters and figures formed by 3/8" V-Grooves. V-Grooves shall be formed by preformed letters and figures.
- MARKERS :** For Railing/Sound Barrier on bridges, Elevation Markers shall be placed on top of the Traffic Railing/Sound Barrier or Bridge Deck at the end bents as directed by the Engineer. Markers are to be furnished by the Florida Department of Transportation and installed by the Contractor. The cost of installing the markers shall be included in the Contract Unit Price for the Railing/Sound Barrier.
- REFLECTIVE RAILING MARKERS :** Reflective Railing Markers shall meet Specification Section 993. Install markers 2'-4" above the riding surface at the spacing shown in the table below. Reflector color (white or yellow) shall match the color of the near edgeline. The cost of the reflective markers shall be included in the Contract Unit Price for the Traffic Railing/Sound Barrier.


REFLECTIVE RAILING MARKER SPACING	
Distance - Edge of Travel Lane to Face of Railing	Spacing (Ft.)
< 4'	40'
4' to 8'	80'
> than 8'	None Required

**INTERMEDIATE JOINT SEAL NOTES:**

- At Intermediate Open Joints, seal the lower 6" portion of the open joint with Pre-cured Silicone Sealant in accordance with Section 932 of the Specifications.
- Apply sealant prior to any Class V finish coating and remove all curing compound and loose material from the surface prior to application of bonding agent.
- The cost of the Pre-cured Silicone Sealant shall be included in the Contract Unit Price for the Traffic Railing.



**NEOPRENE DIAPHRAGM PLUG DETAIL**



**TYPICAL SECTION FIRE HOSE ACCESS DETAIL**

**NOTE:** Fire hose access holes are required at or near fire hydrant locations. Field cut reinforcement as required to maintain 2" minimum cover at access holes. Locate fire hose access holes a minimum of 10'-0" from 3/4" open joints when possible.

**DETAIL "B" - SECTION AT INTERMEDIATE OPEN JOINT**


ESTIMATED TRAFFIC RAILING/SOUND BARRIER QUANTITIES		
ITEM	UNIT	QUANTITY
Concrete (Railing)	CY/LF	0.104
Concrete (Sound Barrier)	CY/LF	0.145
Reinforcing Steel (Typical)	LB/LF	78.57
Additional Reinf. @ Open Joint	LB	430.24

(The above quantities are based on the bridge mounted typical section, 2% deck cross slope and railing on low side of deck.)


**REINFORCING STEEL BENDING DIAGRAMS**

BILL OF REINFORCING STEEL		
MARK	SIZE	LENGTH
P	5	5'-7"
R	5	7'-9"
S1	5	As Req'd.
S2	5	7'-3"
V (Bridge and Wall)	5	5'-1"
V (Footing)	5	7'-7"

		BRIDGE CROSS-SLOPE		LOW GUTTER		HIGH GUTTER	
		ØA	ØB	ØA	ØB	ØA	ØB
BRIDGE MOUNTED	0% to 2%	90°	90°	90°	90°	90°	90°
	2% to 6%	93°	87°	87°	93°	87°	93°
	6% to 10%	96°	84°	84°	96°	84°	96°
WALL & FOOTING MOUNTED		90°	90°	90°	90°	90°	90°




**BARS 5S1 & 5S2**




**BAR 5R (Field Cut for End Taper)**

**STIRRUP BAR 5P**




**STIRRUP BAR 5V**



**END STIRRUP BAR 5V To Be Field Cut (One Required per Railing End Transition)**

**REINFORCING STEEL NOTES:**

- All bar dimensions in the bending diagrams are out to out.
- All reinforcing steel at the open joints shall have a 2" minimum cover.
- Bars 5S1 may be continuous or spliced at the construction joints. Lap splices for Bars 5S1 shall be a minimum of 2'-2".
- The Contractor may use Welded Wire Reinforcement when approved by the Engineer. Welded Wire Reinforcement shall conform to ASTM A 497.
- Bars 5R shall be one continuous bar. No mechanical couplers or lap splices are permitted.
- See Index Nos. 5214 and 5215 for Bars 5V and 5T in L-shaped and Trench footings.




**SECTION THRU RECESSED "V" GROOVE TO FORM INSCRIBED LETTERS AND FIGURES**

**CROSS REFERENCE:** For locations of Detail "B", see Sheet 1.

**REVISIONS**

DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION
01/01/09	SJN	Changed "NAME, DATE AND BRIDGE NUMBER" note and "Ribbed" to "Slotted" in NEOPRENE DIAPHRAGM PLUG DETAIL. Added "REFLECTIVE RAILING" note and "REFLECTIVE RAILING MARKER SPACING" table.	01/01/11	SJN	Changed Detail "B" to Pre-cured Silicone Sealant.



2010 Interim Design Standard

**TRAFFIC RAILING/SOUND BARRIER (8'-0")**

Interim Date: 01/01/11  
Sheet No.: 2 of 5

Index No.: **5210**