


REINFORCING STEEL BENDING DIAGRAMS - JUNCTION SLAB


BILL OF REINFORCING STEEL

MARK	SIZE	LENGTH		
		PRECAST COPING		C.I.P. COPING
		(32" F-SHAPE)	(42" F-SHAPE)	
A	5	7'-8"	7'-8"	7'-8"
B1	5	9'-6"	9'-6"	N/A
B2	5	AS REQD.	AS REQD.	AS REQD.
C	5	7'-8"	7'-8"	N/A
D	4	2'-0"	2'-0"	N/A
F	5	8'-3"	8'-3"	8'-3"
L	6	5'-4"	5'-7"	10'-2"
U1	6	3'-8"	3'-8"	3'-8"
1" ϕ Dowel	Smooth Steel Bar	2'-0"	2'-0"	2'-0"



REINFORCING STEEL NOTES:

- All bar dimensions in the bending diagrams are out to out.
- All reinforcing steel at expansion joints will have a 2" minimum cover.
- Lap splices for Bars 5B2 will be a minimum of 2'-2".
- For Precast Coping only, lap splice Bars 6L with Bars 5C. Lap splices will be a minimum of 2'-9".
- See Index No. 420 and Index No. 425 for Bars 5S and 5V.
- Dimension shown is for lap splice option. For mechanical coupler option, this dimension is 1'-4 1/2" (32" F-Shape) or 1'-7" (42" F-Shape).
- Dimension shown is for lap splice option. For mechanical coupler option, this dimension is 7'-9".
- The Contractor may use Welded Wire Reinforcement when approved by the Engineer. Welded Wire Reinforcement will conform to ASTM A 497.



TYPICAL SECTION THRU C.I.P. COPING AND JUNCTION SLAB AND RETAINING WALL AT EXPANSION JOINTS

ESTIMATED QUANTITIES FOR C.I.P. COPING		
ITEM	UNIT	QUANTITY
Concrete	CY/Ft.	0.468
Reinforcing Steel (Typical) excluding Bars 5V and 5S (Typ.)	Lb./Ft.	64.20
Additional Reinf. @ Expansion Joint	Lb./Ft.	42.72

(The above concrete quantities are based on a superelevation of 6.25% and a 5" wide retaining wall panel, beneath a 32" F-Shape Traffic Railing.)

- JUNCTION SLAB NOTES:
- Match Cross Slope of Travel Lane or Shoulder.
 - The minimum dimension of 6" corresponds to a superelevation of 6.25%. For superelevations exceeding 6.25%, increase this dimension (i.e., shift control points down) as required to match roadway superelevation.
 - Actual width varies depending on type of Retaining Wall used.
 - See Index No. 420 and Index No. 425 for Bars 5S and 5V.
 - Increase the width (1'-2 1/2") of Bars 6U1 as required to maintain 2" minimum cover when recess width exceeds 8".

PRECAST OR C.I.P. COPING WITH C.I.P. JUNCTION SLAB DETAILS (F-SHAPE TRAFFIC RAILINGS)

REVISIONS				
DATE	BY	DESCRIPTION	DATE	BY
01/01/10	SJN	Changed "Continuous Neoprene Strip" to "Preformed Joint Filler" in TYPICAL SECTION detail.		

2010 Interim Design Standard

PERMANENT RETAINING WALL SYSTEMS

Interim Date: 01/01/10


Sheet No. 7 of 19

Index No. 5300


REINFORCING STEEL BENDING DIAGRAMS - RAISED SIDEWALK

BILL OF REINFORCING STEEL


MARK	SIZE	LENGTH	
		PRECAST COPING	C.I.P. COPING
A	5	5'-7"	6'-0"
B1	5	9'-6"	N/A
B2	5	AS REQD.	AS REQD.
C	5	5'-5"	N/A
D	4	2'-0"	N/A
F	5	5'-0"	5'-0"
L	5	5'-0"	8'-1"
U1	5	3'-8"	3'-8"
1" Ø Dowel	Smooth Steel Bar	2'-0"	2'-0"



BARS 5A, 5B1, 5B2, 5C & 5F



1" Ø DOWEL



DOWEL BAR 4D

BAR 5L

BAR 5U1


REINFORCING STEEL NOTES:

- All bar dimensions in the bending diagrams are out to out.
- All reinforcing steel at expansion joints will have a 2" minimum cover.
- Lap splices for Bars 5B will be a minimum of 2'-2".
- Lap splice Bars 5L with Bars 5C. Lap splices will be a minimum of 2'-2".
- See Index No. 422 and Index No. 423 for Bars 5S, 5T and 5X. Adjust vertical dimensions of Stirrup Bars 5T and 5X to 3'-0" for 32" Vertical Shape or 3'-10" for 42" Vertical Shape.
- Dimension shown is for lap splice option. For mechanical coupler option, this dimension is 1'-8".
- Dimension shown is for lap splice option. For mechanical coupler option, this dimension is 5'-8".
- The Contractor may use Welded Wire Reinforcement when approved by the Engineer. Welded Wire Reinforcement will conform to ASTM A 497.

ESTIMATED QUANTITIES FOR C.I.P. COPING

ITEM	UNIT	QUANTITY
Concrete	CY/Ft.	0.538
Reinforcing Steel (Typical) excluding Bars 5T, 5X and 5S (Typ.)	Lb./Ft.	51.63
Additional Reinf. @ Expansion Joints	Lb.	32.04

The above concrete quantities are based on a 5" wide retaining wall panel and a Type D Concrete Curb (See Note 2).




TYPICAL SECTION THRU C.I.P. COPING AND RAISED SIDEWALK AND RETAINING WALL AT EXPANSION JOINTS

RAISED SIDEWALK NOTES:

- Actual width varies depending on type of Retaining Wall used.
- Match roadway curb shape (Type) and height. See Roadway Plans and Index No. 300. 6'-8" dimension is based on a 32" Vertical Shape Traffic Railing with a Type D curb adjacent to a 6'-0" wide sidewalk. Adjust this dimension as required for other curb types or transitions at Begin or End Retaining Wall.
- See Index No. 422 and Index No. 423 for Bars 5S, 5T & 5X and Bullet Railing details. Adjust vertical dimension of Bars 5T and 5X, see Reinforcing Steel Note 5.
- Increase the width (1'-2 1/2") of Bars 5U1 as required to maintain 2" minimum cover when recess width exceeds 8".

PRECAST OR C.I.P. COPING WITH C.I.P. RAISED SIDEWALK DETAILS (VERTICAL SHAPE TRAFFIC RAILINGS)


REVISIONS			
DATE	BY	DESCRIPTION	DATE
01/01/10	SJN	Changed "Continuous Neoprene Strip" to "Preformed Joint Filler" in TYPICAL SECTION detail.	



2010 Interim Design Standard

PERMANENT RETAINING WALL SYSTEMS

Interim Date	Sheet No.
01/01/10	13 of 19
Index No.	
5300	



LIGHT PILASTER NOTES:

- The pilaster and junction slab are designed to resist the following working loads from the light pole applied at the top of the Pilaster:

Axial Deadload	=	1.560 kip
Windload Moment about Transverse Axis (*)	=	40.60 kip-ft
Windload Moment about Longitudinal Axis (*)	=	28.30 kip-ft
Deadload Moment about Longitudinal Axis (*)	=	1.690 kip-ft
Maximum Shear	=	1.380 kip
Torsion about Pole Axis	=	3.560 kip-ft


(*) - Axis refers to Bridge Axis.
- See Index No. 21200 for anchor bolt design and notes.
- The Contractor is responsible for ensuring the anchor bolt design is compatible with the light pole base plate. Modifications to the anchor bolt design must be signed and sealed by the Contractor's Specialty Engineer and submitted to the Engineer for approval prior to construction.
- Install Anchor Bolts plumb.
- For conduit, pullbox and expansion/deflection fitting details, see Utility Conduit Detail Drawings.
- The cost of wire screen, anchor bolts, nuts, washers and anchor plates will be included in the Bid Price for Light Poles. Include the cost of all labor, concrete and reinforcing steel required for construction of the pilasters, pullboxes and miscellaneous hardware required for the completion of the electrical system in the Bid Price for either the Traffic Railing or Concrete Parapet that the pilaster is behind.
- Field Cut Bars 4M2 as required to maintain clearance.
- Anchor Bolt pattern orientation will be as shown.
- Slip Forming Method of construction requires the Engineer's approval within the limits shown.
- Reinforcing shown for light pole pilasters is in addition to typical reinforcing for C.I.P. Junction Slabs and Raised Sidewalks (Bars 5A and 5B2). Omit Junction Slab Bars 6U1 and Raised Sidewalk Bars 5U1 within light pole pilaster limits.
- Work this Sheet with the following as appropriate:
 - Sheet Nos. 5 thru 10 of 19 - Precast or C.I.P. Coping with C.I.P. Junction Slab Details
 - Sheet Nos. 11, 12 and 13 of 19 - Precast or C.I.P. Coping with C.I.P. Raised Sidewalk Details
 - Sheet Nos. 14 and 15 of 19 - Precast Coping/Parapet or C.I.P. Coping with C.I.P. Sidewalk Details

CROSS REFERENCE: For Estimated Quantities, see Sheet No. 18 of 19.

PLAN VIEW
 (Junction Slab reinforcing not shown for clarity)
 (Junction Slab Shown, Raised Sidewalk or Sidewalk Similar)


C.I.P. LIGHT POLE PILASTER DETAILS

REVISIONS					
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION
01/01/10	SJN	Changed Notes 2, 3, & 9, and Spacing of Bars 4G. Deleted 1" Ø PVC Conduit Weep Hole.			



2010 Interim Design Standard
PERMANENT RETAINING WALL SYSTEMS

Interim Date 01/01/10	Sheet No. 16 of 19
Index No. 5300	




TYPICAL SECTION AT LIGHT POLE PILASTER
 (Traffic Railing Shown, Concrete Parapet Similar)
 (Junction Slab Shown, Raised Sidewalk or Sidewalk Similar)

- NOTES:**
1. The 8'-0" dimension shown is for Junction Slabs. This dimension must be a minimum of 5'-0" for all applications.
 2. For junction slabs, increase the 1'-0" depth dimension to 1'-6". For raised sidewalks, increase the 2'-0" depth dimension to 2'-6". For sidewalks, increase 6" depth dimension to 1'-6". The minimum length of the Junction Slabs, Raised sidewalks and Sidewalks is 50'-0", measured along the Gutter Line.
 3. Bars 4J are only required when pilasters are behind a Traffic Railing.
 4. Match the slope of the adjoining junction slab and shoulder or roadway pavement, raised sidewalk or sidewalk.
 5. Actual width varies depending on type of Retaining Wall used.
 6. See Index No. 420 for Bars 5V and 5S.


C.I.P. LIGHT POLE PILASTER DETAILS

REVISIONS						2010 Interim Design Standard		Interim Date	Sheet No.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION			01/01/10	17 of 19
01/01/10	SJN	Deleted 1" Ø Weep Hole (PVC Conduit). Changed "Continuous Neoprene Strip" to "Preformed Joint Filler".							




PERMANENT RETAINING WALL SYSTEMS

Index No.
5300



ELEVATION VIEW
 (Junction Slab Reinforcing & Bars 4J not Shown for Clarity)
 (Traffic Railing Shown, Concrete Parapet Similar)
 (Junction Slab Shown, Raised Sidewalk or Sidewalk Similar)



DETAIL "A"


- NOTES:**
1. Field Cut Bars 4M2 as required to maintain minimum cover.
 2. Maximum clearance between leveling nut and top of pilaster will not exceed anchor bolt diameter.

ESTIMATED QUANTITIES		
ITEM	UNIT	QUANTITY
Concrete (Pilaster)	CY	0.926
Concrete (Thickened Junction Slab)	CY	1.180
Reinforcing Steel	Lb.	428


(The quantities above are for one C.I.P. Light Pole Pilaster. The concrete quantity for the thickened junction slab is based on a 6" increase in thickness and a 5" wide retaining wall panel. Adjust thickened concrete quantity as required for raised sidewalks and sidewalks.)

REINFORCING STEEL BENDING DIAGRAMS - LIGHT PILASTER


BILL OF REINFORCING STEEL			
MARK	SIZE	NO. REQD.	LENGTH
B3	5	8	7'-2"
G1	4	16	5'-8"
G2	4	4	4'-8"
G3	4	4	4'-2"
G4	4	6	8'-10"
G5	4	4	7'-4"
H1	4	3	9'-8"
H2	4	2	13'-8"
J	4	24	6'-0"
M1	4	12	8'-10"
M2	4	10	3'-8"




BARS 5B3 & 4J




BAR 4H2



BAR 4H1



BARS 4G1, 4G2, 4G3, 4G4 & 4G5




BAR 4M1 & 4M2

REINFORCING STEEL NOTES:

1. All bar dimensions in the bending diagrams are out to out.
2. Lap splices for Bars 4G1, 4G2 & 4G3 will be a minimum of 1'-4". Lap splices for Bars 4G4 & 4G5 will be a minimum of 1'-8".
3. The Contractor may use Welded Wire Reinforcement when approved by the Engineer. Welded Wire Reinforcement will conform to ASTM A 497.

C.I.P. LIGHT POLE PILASTER DETAILS

REVISIONS			
DATE	BY	DESCRIPTION	DATE
01/01/10	SJN	Deleted Grout Pad and 1" Ø PVC Conduit Weep Hole in Detail "A" and ELEVATION VIEW. Changed Length of Bars 4G4 and 4G5.	



2010 Interim Design Standard
PERMANENT RETAINING WALL SYSTEMS

Interim Date: 01/01/10
 Sheet No.: 18 of 19
 Index No.: **5300**