2' Min. Full

Height Curb

See Note Below

Note:

CURB RAMP NOMENCLATURE

Back Of Sidewalk

Alignment Variations

When crosswalk markings are required ramp runs must fall

within crosswalk limits and where practical, be parallel with the projected crosswalk alignment. The bottom of the ramp

beyond the curb line shall have a clear space 48" minimum

□ Crosswalk widths and configuration vary; must conform

to Index No. 17344 and 17346.

DESCRIPTION:

within the markings of a marked crosswalk. If no crosswalk

markings are present, the bottom of the ramp beyond the curb ramp shall have a clear space 48" minimum outside active traffic

PICTORIAL VIEW



TYPICAL PLACEMENT OF PUBLIC SIDEWALK CURB RAMPS AT CURBED RETURNS



## GENERAL NOTES

- public right of way and to accessible pedestrian routes on adjacent sites. Curbed facilities with sidewalks and those without sidewalks are to have curb ramps constructed at all street intersections
- 2. The location and orientation of curb ramps shall be as shown in the plans.

Ramp

Omit Joints On

urnout Or

Side Street

Curb Ramps

Where Curb Ramps Are Constructed in Existing Sidewalks of Utility Structed for Reduce Than 0.02

UTILITY

STRIP

Where Curb Ramps Are Constructed in Sidewalk or O.02 Are Ramps Are Constructed in Existing Sidewalks STRIP

STRIP

Where Curb Ramps Are Constructed in Existing Sidewalks STRIP

The Sidewalks Structed To Reduce Than 0.02 The Sidewalks Sidewalks STRIP

Utility Strip

LINEAR SIDEWALK RAMPS

For BACK OF SIDEWALK CURB

And For RAMP AND SIDEWALK

CURB OPTIONS See Sheet 4.

Note: A portion of one or both ramps

may extend outside the return.

OR BUFFER TRANSITIONS

3. Curb ramp running slopes at unrestrained sites shall not be steeper than 1:12 and cross slope shall be 0.02 or flatter. Transition slopes shall not be steeper than 1:12.

When altering existing pedestrian facilities where existing site development precludes the accommodation of a ramp slope of 1:12, a running slope between 1:12 and 1:10 is permitted for a rise of 6" maximum and a running slope of between 1:10 and 1:8 is permitted for a rise of 3" maximum. Where compliance with the requirements for cross slope cannot be fully met, the minimum feasible cross slope shall be

Ramp running slope is not required to exceed 8' in length, except at sites where the plans specify a

- 4. If a curb ramp is located where pedestrians must walk across the ramp, then the walk shall have transition slopes to the ramp; the maximum slope of the transitions shall be 1:12. Ramps with curb returns may be used at locations where other improvements provide guidance away from that portion of curb perpendicular to the sidewalk; improvements for guidance are not required at curb ramps for linear nedestrian traffic
- 5. Curb ramp detectable warning surfaces shall extend the full width of the ramp and 24" deep. Detectable warning surfaces shall be constructed in accordance with Specification 527. See Sheet 6 for detectable warning layouts. Transition slopes are not to have detectable warnings. Detectable warnings are required on sidewalks at intersecting roads, streets and railroads. For requirements for detectable warnings on sidewalks at intersecting driveways, see Index 310.
- 6. Where a curb ramp is constructed within existing curb, curb and gutter and/or sidewalk, the existing curb or curb and gutter shall be removed to the nearest joint beyond the curb transitions or to the extent that no remaining section of curb or curb and gutter is less than 5' long. The existing sidewalk shall be removed to the nearest joint beyond the transition slope or walk around or to the extent that no remaining section of sidewalk is less than 5' long. For details of Concrete Sidewalk See Index 310.
- 7. Alpha-numeric identifications are for reference (plans, permits, etc.).
- 8. Public sidewalk curb ramps are to be paid for as follows:

Ramps, reconstructed sidewalks, walk around sidewalks, sidewalk landings and sidewalk curbs are to be paid for under the contract unit price for Sidewalk Concrete, ( " Thick), SY. Curb transitions and reconstructed curbs are to be paid for under the contract unit price for the parent curb, i.e., Concrete Curb (Type \_\_), LF or Concrete Curb and Gutter (Type \_\_), LF.


When a separate pay item for the removal and disposal of existing curb, curb and gutter, and/or sidewalk is not provided in the plans, the cost of removal and disposal of these features shall be included in the contract unit price for new curb, curb and gutter and/or sidewalk respectively.

- 9. Acceptance Criteria for Detectable Warnings:
  - a. The ramp detectable warning surface shall be complete and uniform in color and texture
  - b. 90% of the individual truncated domes must comply with the design criteria
  - c. There may be no more than 4 non-complying domes in any one square foot of surface
  - d. No two adjacent domes may be non-compliant
- e. Surface may not deviate more than 0.10" from a true plane
- 10. All sidewalk surfaces, ramp surfaces, and landings with a cross slope shown in this Index to be 0.02 shall be 0.02 maximum. All ramp surfaces and ramp transition slopes with a slope shown in this Index to be 1:12 shall be 1:12 maximum.


1. Public sidewalk curb ramps shall be constructed in the public right of way at locations that will provide continuous unobstructed pedestrian circulation paths to pedestrian areas, elements and facilities in the and at turnouts that have curbed returns. Partial curb returns shall extend to the limit prescribed by Index No. 515 to accommodate curb ramps. Ramps constructed at locations without sidewalks shall have a landing constructed at the top of each ramp, see Sheet 5.

0.02 Max

2' Min. Full



LAST REVISION 01/01/11



01/01/11









≥ DESCRIPTION:



FDOT DESIGN STANDARDS


FY 2012/2013





□ Crosswalk width and configuration vary; must conform to Index No. 17344 and 17346.


PLAN




SECTION AA

DIMENSIONAL FEATURES FOR
PUBLIC SIDEWALK COMBINED CORNER
RAMPS UNDER CONDITIONS OF INFEASIBILITY

## DIMENSIONAL FEATURES FOR PUBLIC SIDEWALK CURB RAMPS FOR LINEAR PEDESTRIAN TRAFFIC



RAMP AND SIDEWALK CURB OPTIONS




Construct Sidewalk Curb In Absence Of Adequate Buffer, Maintainable Surface Contour, Abutting Structure, Or When Called For In The Plans Or Standards


BACK OF SIDEWALK CURB OR BUFFER TRANSITION

LAST

REVISION


01/01/11





PLAN - (ALTERNATE DETAIL)

## MEDIAN CROSSWALKS



LANDINGS FOR RAMPS WITHIN PUBLIC RIGHT OF WAY CONSTRUCTED AT LOCATIONS WHERE FUTURE SIDEWALKS ARE PROPOSED, WHERE STABLE SURFACES OTHER THAN SIDEWALKS ARE PART OF A CONTINUOUS PASSAGE OR WHERE A CURB FALLS ALONG THE CIRCULATION PATH TO PEDESTRIAN ROUTES ON ADJACENT SITES

> FDOT DESIGN STANDARDS FY 2012/2013

