

 $e_{max.} = 0.05$

SUPERELEVATION FOR URBAN HIGHWAYS AND HIGH SPEED URBAN STREETS

LAST DESCRIPTION: REVISION 00




FDOT DESIGN STANDARDS FY 2012/2013


SUPERELEVATION URBAN HIGH

GENERAL NOTES

- 1. Maximum rate of superelevation for urban highways and high speed urban streets shall be 0.05.
- 2. Superelevation shall be obtained by rotating the plane successively about the break points of the section until the plane has attained a slope equal to that required by the chart. Should the rotation traverse the entire section and further superelevation be required, the remaining rotation of the plane shall be about the low edge of the inside travel lane. Crown is to be removed in the auxiliary lane to the outside of the curve only when the adjoining travel lanes require positive superelevation.
- 3. When positive superelevation is required, the slope of the gutter on the high side shall be a continuation of the slope of the superelevated pavement.
- 4. In construction, short vertical curves shall be placed at all angular profile breaks within the limits of the superelevation transition.
- 5. The variable superelevation transition length "L" shall have a minimum value of 50 feet for design speeds under 40 MPH and 75 feet for design speeds of 40 MPH or greater.
- 6. Roadway sections having lane arrangements different from those shown, but composed of a series of planes, shall be superelevated in a similar manner.
- 7. For superelevation of lower speed urban streets, see the FDOT 'Manual Of Uniform Minimum Standards For Design, Construction And Maintenance For Streets And Highways'. For superelevation of curves on rural highways, urban freeways and high speed urban highways, see Index No. 510.

WAYS AND STREE	ΓS INDEX NO. 511	sнеет NO. 1





FY 2012/2013



LINE	DESCRIPTION	
A	Inside Travel Lane	
В	Inside Lane Line	
С	Inside Median Edge Pavement	
D	€ Construction	
E	Outside Median Edge Pavement	
F	Outside Lane Line	
G	Outside Travel Lane	
Inside And Outside Are Relative		
To Curve Center		

*d (Slope Ratio)		
30 MPH	1: 100	
40 MPH	1: 125	
45-50 MPH △	1: 150	
∧ 1:125 May Be Used For		

125 May Be Used For 45 MPH Under Restricted Conditions.

/- Theoretical Grade Line

	INDEX	SHEET
SUPERELEVATION URBAN HIGHWAYS AND STREETS	NO.	NO.
SUPEREE ATTOM UNDAN INCHWATS AND STREETS	511	3