
## GENERAL NOTES


- 1. Temporary concrete barrier systems on roadways may be any of the following:
- a. The FDOT Type K Temporary Concrete Barrier system (Design Standard Index 414). F-Shape Units. For temporary concrete barrier systems on bridges see Design Standard Index No. 414.
- b. Proprietary temporary concrete barrier systems meeting NCHRP Report 350 Test Level 3 criteria which are included on the Qualified Products List.
- 2. Barrier units of dissimilar types may be interconnected within a single line barriers using transition units.
- 3. Alignment, length of need, anchorage and end treatment shall be in accordance with this Index.
- 4. Temporary concrete barrier units shown herein shall not be used for permanent barrier wall construction regardless of unit length.
- 5. If the plans specify Barrier (Temporary) (Type K), substitution with other barrier types is not permitted.
- 6. If the plans specify temporary concrete barrier system, substitution with water filled barriers is not permitted.
- 7. Where existing pavement is not present, construct an Asphalt Pad using Miscellaneous Asphalt Pavement. Cost of the Asphalt Pad to be included in the cost of the Barrier system.
- 8. Type C Steady-Burn Lights are to be mounted on top of temporary concrete barriers that are used as barriers along traveled ways in work zones. The lights are to be spaced at 50' centers in transitions, 100' centers on curves and 200' centers on tangent roadways. For additional information refer to Index 600.
- 9. Barrier units used for work zone traffic control and other temporary applications shall be paid for under the contract unit price for Barrier (Temporary), LF. Type C Steady-Burn Lights shall be paid for under the contract unit price for Lights, Temporary, Barrier Mount (Steady-Burn), ED.
- 10. Deflection space shall be clear of any construction debris, stockpiled materials, equipment, and objects.






END VIEWS

REINFORCEMENT AND OTHER UNIT FABRICATION DETAILS NOT SHOWN. PERMITTED BARRIER UNIT END VIEWS





DESCRIPTION:

LAST


REVISION


01/01/12

OFFSET AND DEFLECTION SPACE REQUIREMENTS							
Installation	Shielding	Work Zone Speed Offset to Travelway		Deflection Space			
Right Shoulder	Above Ground Hazards	45 mph or Less	1' min, 2' preferred	2' min.			
		50 mph and Greater	2' min, 4' preferred	4' min.			
	Drop-Off Hazards	45 mph or Less	1' min, 2' preferred	2' min.			
		50 mph and Greater					
		a. Drop-offs 4' or Less and NO traffic below	2' min, 4' preferred	2' min.			
		b. All drop-off conditions other than 'a'	2' min, 4' preferred	4' min.			
Separating Traffic	Adjacent Opposing Traffic	45 mph or Less	1' min, 2' preferred	1' min., 2' prefered			
		50 mph and Greater	2' min, 4' preferred	2' min., 4' preferred			


FDOT DESIGN STANDARDS 2013








CLEAR ZONE WIDTHS FOR WORK ZONES							
WORK ZONE SPEED (MPH)	TRAVEL LANES & MULTILANE RAMPS (feet)	AUXILIARY LANES & SINGLE LANE RAMPS (feet)					
60-70	30	18					
55	24	14					
45-50	18	10					
30-40	14	10					
ALL SPEEDS CURB & GUTTER	4' BEHIND FACE OF CURB	4' BEHIND FACE OF CURB					




07.00.01	
7107/07/0	
	LAST REVISIO


.AST	N	DESCRIPTION
ISION/	SIC	
01/12	EVI	





6/28/2012 10:06:20 AM rd960rh C:\d\projects\standards\roadway\004





LAST

ON)		
E BARRIER	index no. <b>415</b>	sheet NO. <b>7</b>