



GENERAL NOTES:

1. If no guardrail or barrier wall exists, structure shall be outside the clear zone. Clear zone shall be measured to edge of the drilled shaft if drilled shaft is more than 4" above adjacent grade.
2. Extend Catwalk from DMS to outer edge of paved shoulder but not less than four feet in length.
3. Clear zone distance and setbacks from edge of travel lane shall be in accordance with Plans Preparation Manual Volume 1, Chapters 2 and 4.




Note: Actual number and direction of travel lanes varies.

**TYPICAL PLAN VIEW
DMS CANTILEVER SIGN STRUCTURE**




Note: Actual number and direction of travel lanes varies.

**TYPICAL PLAN VIEW
SPAN SIGN STRUCTURE**




**TYPICAL ELEVATION VIEW
CANTILEVER SIGN STRUCTURE**




**TYPICAL ELEVATION VIEW
SPAN SIGN STRUCTURE**

GENERAL LAYOUT


C:\projects\standards\18300-s\18300-01.dgn 6/24/2013 7:39:22 PM sm970re

LAST REVISION 01/01/12	REVISION	DESCRIPTION:	 <p>FDOT 2014 DESIGN STANDARDS</p>	<p>DYNAMIC MESSAGE SIGN WALK-IN</p>	<p>INDEX NO. 18300</p>	<p>SHEET NO. 1 of 10</p>
---------------------------	----------	--------------	--	--	-----------------------------------	-------------------------------------

C:\projects\standards\18000-s\18300-02.dgn
smg70re
7:39:24 PM
6/24/2013



SPAN DMS



CANTILEVER DMS

GENERAL NOTES:

1. Conductors for grounding shall be connected to steel framework that have been cleaned to base metal, by use of bonding plates having contact area of not less than 8 square inches or by welding or brazing. Drilling and tapping the steel structure to accept a threaded connector is also an acceptable method.
2. If steel framework is to be drilled and tapped to accept threaded connector, the threaded connector shall have at least 5 threads fully engaged and secured with a jam nut to the steel framework.
3. Bends in the conduit shall not be less than the minimum bending radius for the cable contained in the conduit.
4. Catwalk and handrail design and installation shall comply with AISC, AASHTO, and OSHA requirements as applicable.
5. All data, fiber-optic and power cable for the DMS shall be completely encased within the sign structure or in conduit.
6. Permanently stamp/mark foundation to conduit locations.
7. Transition conduit in foundation to underground conduit with appropriate reducer outside the limits of the foundation.

LAST REVISION	01/01/10
---------------	----------

REVISION	DESCRIPTION:
----------	--------------





DYNAMIC MESSAGE SIGN WALK-IN

INDEX NO.	18300
-----------	-------


SHEET NO.	2 of 10
-----------	---------

GENERAL NOTES:


1. DMS Cabinet may be pole or ground mounted depending on project requirements.
2. See sheet 7 for additional conduits for grounding. The number and placement of conduits are approximate.
3. Field adjust pole-mounted DMS cabinet height to achieve best access for maintenance personnel given site conditions as directed by the Engineer. Avoid conflicts with stiffeners, hand-hole and maintenance of anchor bolts.




HANDHOLE COVER




HANDHOLE FRAME




**SECTION A-A
(Thru Handhole)**



C:\projects\standards\18300-18300-03.dgn
 sm970re
 7:39:26 PM
 6/24/2013

LAST REVISION 01/01/13	DESCRIPTION:	 <p>FDOT 2014 DESIGN STANDARDS</p>	<p>DYNAMIC MESSAGE SIGN WALK-IN</p>	INDEX NO. 18300	SHEET NO. 3 of 10
---------------------------	--------------	--	--	--------------------	----------------------



HANGER LOCATION DETAIL


(Cantilever Sign Structure Shown, Span Sign Structure Similar)

GENERAL NOTES

1. Design Specifications: FDOT Structures Manual (current edition) and AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals.
2. DMS and Hanger Design Wind Speed: 150 miles per hour. Maximum DMS weight for design: 4500 lb.
3. Shop drawings including the DMS connection are required and fabrication shall not begin until these shop drawings are approved.
4. Locate the sign laterally on the structure as shown in the plans. Vertically center the sign enclosure with the centerline of the truss.
5. Before erection, after both the delivery of the DMS and the steel truss, the contractor shall carefully measure the exact locations for field drilling the $\frac{1}{2}$ " bolt holes in the vertical hangers and horizontal mounting member attached to the sign enclosure. Field locate holes to allow vertical hanger placement as shown on the plans with no conflicts with gusset or splice plates.
6. All steel items shall be galvanized as follows:
All nuts, bolts and washers ASTM F2329
All other steel items ASTM A123
7. All bolt holes shall be equal to the bolt diameter plus $\frac{1}{16}$ ", prior to galvanizing.
8. All bolts shall have single self-locking nuts, or locking nut system, installed in accordance with the manufacturer's recommendations.
9. Cost of the installation of the DMS on truss including the vertical hanger, associated members, and hardware shall be incidental to the cost of the sign structure.
10. Threaded couplings shall be located on sign side of column above the sign truss.

6/24/2013 7:39:28 PM sm970re C:\projects\standards\18000-s\18300-04.dgn

LAST REVISION	DESCRIPTION:
07/01/13	




**FDOT 2014
DESIGN STANDARDS**

DYNAMIC MESSAGE SIGN WALK-IN


INDEX NO.
18300

SHEET NO.
4 of 10


C:\projects\standards\18300-s\18300-05.dgn
sm970re
7:39:30 PM
6/24/2013




END VIEW



SECTION A-A



SECTION B-B



SECTION C-C

LAST REVISION
07/01/10

REVISION

DESCRIPTION:




FDOT 2014
DESIGN STANDARDS

DYNAMIC MESSAGE SIGN WALK-IN


INDEX NO.
18300

SHEET NO.
5 of 10


6/24/2013 7:39:32 PM sm970re C:\projects\standards\18300-18300-06.dgn




SPAN DMS



CANTILEVER DMS



DETAIL A



DETAIL B

GENERAL NOTES:

1. All grounding materials shall meet the requirements of Section 620.
2. Exothermically weld all connections to ground rods.
3. The contractor may, upon approval of the Engineer, install a 30-foot sectional ground rod for instances when conditions will not allow for the installation of the 3 auxiliary ground rods.
4. Install marker tape directly above all grounding electrodes and conductors.
5. Copper flat surfaces shall be bolted, welded, or brazed securely to framework to maintain electrical continuity.
6. All air terminals must meet UL-96A.
7. Grounding system shall be placed within right of way.
8. See Sheet 7 for ground rod placement detail.
9. Lightning protection shall conform to NFPA 780. Spacing between air terminals shall not exceed 20 feet.

LAST REVISION
07/01/13

REVISION

DESCRIPTION:






FDOT 2014
DESIGN STANDARDS


DYNAMIC MESSAGE SIGN WALK-IN

INDEX NO.
18300


SHEET NO.
6 of 10

C:\projects\standards\18300-18300-07.dgn
smg70re
7:39:34 PM
6/24/2013



LAST REVISION 01/01/12	DESCRIPTION:  FDOT 2014 DESIGN STANDARDS	DYNAMIC MESSAGE SIGN WALK-IN	INDEX NO. 18300	SHEET NO. 7 of 10
---------------------------	---	------------------------------	--------------------	----------------------

6/24/2013 7:39:36 PM sm970re C:\projects\standards\18300-s\18300-08.dgn



GENERAL NOTES:


1. Provide single ethernet connection from the managed field ethernet switch to either the sign controller interface in cabinet or sign controller in sign enclosure.
2. Locate cabinet as shown in plans.
3. Serial data link is for communications directly to the DMS controller.
4. Cabinet must include at least one breaker to control all cabinet power.
5. AC service entrance may be located in cabinet or sign housing.
6. UPS equipment location may vary. Diagram indicates functional requirements that uninterrupted power must be available in cabinet and sign housing.

LEGEND

- ◆ - - - ◆ - - - ◆ - - - ◆ - - - ◆ - - - Data
- - - - - Ethernet
- - - - ● - - - Power
- SPD Surge Protection Device

SIGN AND CABINET WIRING DIAGRAM

LAST REVISION 07/01/10	REVISION	DESCRIPTION:	 FDOT 2014 DESIGN STANDARDS	DYNAMIC MESSAGE SIGN WALK-IN	INDEX NO. 18300	SHEET NO. 8 of 10
---------------------------	----------	--------------	---	-------------------------------------	--------------------	----------------------



LEFT SIDE VIEW

FRONT VIEW
POLE MOUNTED DMS CABINET


RIGHT SIDE VIEW

GENERAL NOTES:


1. Cabinet layout is for pole or ground mounted installations.
2. All dimensions and equipment locations are approximate.
3. Conduit entrances are at bottom of cabinet.
4. Minimum number of duplex outlets is three, (2) SPD protected and (1) GFI protected.
5. Either an access controller or local access panel shall be provided to provide full access to DMS sign for control, programming and troubleshooting.
6. Load center shall be sized for connected equipment and convenience outlets with at least one main disconnect and three circuit breakers.
7. Batteries and UPS may be located in sign housing or cabinet.
8. Power Distribution Assembly component layout, orientation and location may vary.

CABINET LAYOUT 1


C:\projects\standards\18300-s\18300-09.dgn sm970re 7:39:37 PM 6/24/2013

LAST REVISION 07/01/10	REVISION	DESCRIPTION:	 <p>FDOT 2014 DESIGN STANDARDS</p>	<p>DYNAMIC MESSAGE SIGN WALK-IN</p>	<p>INDEX NO. 18300</p>	<p>SHEET NO. 9 of 10</p>
---------------------------	----------	--------------	--	--	-----------------------------------	-------------------------------------

C:\projects\standards\18300-s\18300-10.dgn
 sm970re
 7:39:39 PM
 6/24/2013



CABINET LAYOUT 2

LAST REVISION 07/01/10	DESCRIPTION: 18300-10	 FDOT 2014 DESIGN STANDARDS	DYNAMIC MESSAGE SIGN WALK-IN	INDEX NO. 18300	SHEET NO. 10 of 10
---------------------------	--------------------------	---	------------------------------	--------------------	-----------------------