SUMMARY OF LUMP SUM ITEMS								
PAY ITEM NO.	PAY ITEM DESCRIPTION		TITY	DESIGN NOTES	CONSTRUCTION REMARKS			
0101 1	MOBILIZATION	1	,		712.77.00			

	SUMMARY OF MONITOR EXISTING STRUCTURES										
SITE	LOCATION	STRUCTURE	INSPEC SETTL MONIT		VIBRATION MONITORING		GROUNDWATER MONITORING		DESIGN	CONSTRUCT I ON	
NO.		USAGE	0108	1	0108	3 2	0108 3		NOTES	REMARKS	
	ADDRESS AND			5	LS		L5		1		
	/OR STA.		Р	F	P	F	P	F			
1	230 WALNUT ST	MUSEUM					Х		CULVERT EXTENTION		
2		HISTORIC CEMETERY WALL	х						SHEET PILE INSTALLATION		
3	624 OAK DRIVE	ANTIQUE SHOP			х				MILLING AND RESURFACING		
4	888 OAK DRIVE	LASIK EYE SURGERY			Х				PILE DRIVING OPERATIONS		
5	648 OAK DRIVE	BED & BREAKFAST	х		х				MILLING AND RESURFACING		
		TOTAL:	1		1		1				

THIS LIST INCLUDES EXISTING STRUCTURES (AS DETERMINED BY THE DEPARTMENT) LOCATED OUTSIDE THE LIMITS SPECIFIED IN ARTICLE 108-2 OF THE FOOT SPECIFICATIONS THAT ARE REQUIRED TO BE MONITORED. THIS LIST SHOULD NOT BE CONSIDERED ALL INCLUSIVE AND DOES NOT CONTAIN EXISTING STRUCTURES TO BE MONITORED THAT ARE LOCATED WITHIN THE DISTANCES SPECIFIED IN ARTICLE 108-2.

PAY	ITEN	1 NO	TES
-----	------	------	-----

CC	ST	0F	THE	REM	OVA	L OF	EXI	STII	VG	MSE	WA	LL A	ND	CONCRETE	RETAINING	WALL
TC) BE	IN	CLUD	ED.	IN T	ΗE	COST	0F	CL	EARI	NG	AND	GR	UBBING.		

ALL SALVAGEABLE MATERIAL DESIGNATED TO BE DELIVERED BY THE CONTRACTOR SHALL BE DELIVERED TO: 5301 NE 39TH AVE GAINESVILLE, FL 32609 110- 86

CONTACT GAINESVILLE OPERATIONS PROGRAM ENGINEER: (352) 381-4316

520- 1 COST OF ASPHALT BASE CURB PAD AND ADDITIONAL CURB THICKNESS REQUIRED TO BE INCLUDED IN THE COST OF CURB AND GUTTER.

EXISTING GUARDRAIL IS TO BE DISMANTLED AND STOCKPILED WITHIN THE RIGHT OF WAY IN AREAS DESIGNATED BY THE ENGINEER FOR REMOVAL BY FDOT MAINTENANCE FORCES.

110- 1- 1

536- 73

50-44

SQ-50

50-45 - 50-49

SQ-51 - SQ-53

THIS IS TO INCLUDE REPLACEMENT OF 10 PANELS, 1390 REGULAR POSTS AND 1 SPECIAL POST WHICH HAVE BEEN DETERMINED TO BE NON SALVAGEABLE. ADDITIONAL POSTS AND PANELS DETERMINED TO BE NON SALVAGEABLE DURING RESETTING SHALL BE PAID FOR UNDER 538-5 OF THE SPECIFICATIONS. 538- 1

570- 1 - 1 INCLUDES APPROXIMATELY 94 SY TURF FOR TEMPORARY EROSION CONTROL.

570- 1 - 2 INCLUDES APPROXIMATELY 357 SY SOD FOR TEMPORARY EROSION CONTROL.

ADDITIONAL PAY ITEM NOTES MAY BE CONTAINED WITH THE OTHER COMPONENTS OF THE CONTRACT PLANS SET.

INDEX OF SUMMARY OF QUANTITIES

	THEE OF SOMMAN OF COANTIFIES
SHEET NO.	SHEET DESCRIPTION
50-1	SUMMARY OF LUMP SUM ITEMS, SUMMARY OF MONITOR EXISTING STRUCTURES, SUMMARY OF LITTER REMOVAL AND MOWING
50-2 - 50-6	SUMMARY OF TEMPORARY TRAFFIC CONTROL PLAN ITEMS
SQ-7	SUMMARY OF TEMPORARY SIGNALIZATION & DETECTION
SQ-8 - SQ-13	SUMMARY OF EROSION AND SEDIMENT CONTROL DEVICES
SQ-14 - SQ-19	SUMMARY OF LITTER REMOVAL AND MOWING
SQ-20	SUMMARY OF REMOVAL ITEMS
SQ-21	SUMMARY OF EARTHWORK
SQ-22	SUMMARY OF GEOTECHNICAL ITEMS
SQ-23 - SQ-35	SUMMARY OF PAVEMENT
SQ-36	SUMMARY OF MISCELLANEOUS ASPHALT PAVEMENT
SQ-37 - SQ-38	SUMMARY OF STRUCTURE QUANTITIES
SQ-39	SUMMARY OF UTILITY ADJUSTMENTS
SQ-40	SUMMARY OF MISCELLANEOUS DRAINAGE ITEMS
SQ-41	SUMMARY OF PERMANENT BARRIER WALL
50-42	SUMMARY OF CURB & GUTTER AND/OR TRAFFIC SEPARATORS
SQ-43	SUMMARY OF SIDEWALK & DETECTABLE WARNINGS

SUMMARY OF DITCH PAVEMENT

SUMMARY OF PERFORMANCE TURF

SUMMARY OF PERMANENT CRASH CUSHIONS

SUMMARY OF GUARDRAIL

AN INDEX IS OPTIONAL

	SUMMARY OF LITTER REMOVAL AND MOWING															
							LITTER REMOVAL				MOW I NG					
CONCT	LOCATION		DUD AT LON	EDECHENCY			0107 1		4054	0107 2						
CONST .		SIDE	DURATION (DAYS)	FREQUENCY (DAYS)	AREA ID			AREA		AREA ID			AREA		DESIGN NOTES	CONSTRUCTION REMARKS
' '''	STA. TO STA.		(5/1/3)	(DAI 3)	''		AC/CYCLE	TOTAL	(AC)] ''	CYCLES	AC/CYCLE	TOTAL	(AC)	NOTES	TE PIPATOS
	37A: 10 37A:						AC/CICLL	Р	F			AC/C/CLL	Ρ	F		
1	159+44 TO 305+20	Lt.	42	30	35005	1	8.700	8.700		35005	1	8.700	8.700			
2	159+44 TO 305+20	Lt.	98	30	35120	3	7.300	21.900		35120	3	7.300	21.900			
3	159+44 TO 305+20	Rt.	114	30	35301	4	5.800	23.200		35301	4	5.800	23.200			
4	159+44 TO 305+20	Rt.	68	30	35301	2	5.800	11.600		35301	2	5.800	11.600			
							SUB-TOTAL:	65.400				SUB-TOTAL:	65.400			
							TOTAL:	65.40				TOTAL:	65.40			

EXHIBIT SQ-1 Date: 1/1/16

REVISIONS								
DATE	DESCRIPTION	DATE	DESCRIPTION					
		l						
		l						
		ı						

STATE OF FLORIDA DEPARTMENT OF TRANSPORTATION							
ROAD NO.	COUNTY	FINANCIAL PROJECT ID					
SR 10	LEON	123456-1-52-01					

SUMMARY OF QUANTITIES

SHEET NO.

SQ-1