



Florida Department of Transportation

RON DESANTIS
GOVERNOR

801 N. Broadway Avenue
Bartow, FL 33830

KEVIN J. THIBAUT, P.E.
SECRETARY

September 11, 2019

ACKNOWLEDGMENT REQUESTED
FAX NUMBER (863) 519-2661

NOTICE TO CONTRACTORS
Fixed Capital Outlay Program
District Contracts
September 24, 2019 Letting

ADDENDUM NUMBER ONE

FINANCIAL PROJECT NO.: 444795-1-52 -01
DISTRICT CONTRACT NO.: E1S91
HILLSBOROUGH COUNTY

Contractor,

Please replace Attachment A-1 with the attached A-1, Addendum 1:

All changes are highlighted.

Acknowledge receipt of this addendum in the space provided on the proposal.

Don Naylor
District Contracts Administrator

ER/er

**PLEASE SIGN BELOW AND ACKNOWLEDGE RECEIPT OF THIS NOTICE VIA
FAX OR E-MAIL.**

Signature

Date

Company Name

- ALL EXISTING BUILDING STRUCTURE AND ENVELOPE TO REMAIN UNLESS OTHERWISE NOTED.
- REMOVE ALL DETERIORATED BUILDING COMPONENTS AS NOTED.
- CONTRACTOR TO NOTIFY OWNER OF ANY DAMAGE TO COMPONENTS SCHEDULED TO REMAIN.
- FIELD VERIFY ALL DIMENSIONS
(ROOF DIMENSIONS 75'x40'
ROOF PITCH 4/12)

EXISTING STRUCTURE TO REMAIN

REPLACE EXISTING PLYWOOD AS NEED (UP TO 10% OF ROOF SURFACE)
AS REQUIRED. MATCH EXISTING THICKNESS

SELF-ADHERING SHEET UNDERLAYMENT

NEW 1 1/4" 24 GAUGE METAL R-PANEL

INSIDE CLOSURE PER MANUFACTURER RECOMMENDED PRACTICE

NEW FASCIA WITH DRIP
EDGE EXTENDED BEYOND PANEL CLOSURE

24 GAUGE GUTTER AND DOWNSPOUT

PAINT EXPOSED BLOCKING TO MATCH EXISTING

REPLACE EXISTING BLOCKING
AS REQUIRED. MATCH EXISTING THICKNESS

24 GAUGE FASCIA AND DRIP EDGE BEHIND GUTTER

NEW ALUMINUM PERFORATED SOFFIT

