

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01200611	Call Order: 001	Proposal: E1S53	District:01
Counties:	OKEECHOBEE			
Road Name:	SR 15/700			
Limits:	91050000			
Project(s):	43890215201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.207 Miles	Contract Days:	250	
Total Bridge Length:	0.000 Miles	Letting Date:	06/11/20	
Total Proposal Length:	0.207 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days (Aqui Time)	
Proposal Budget Estimate:	\$1,521,181.00			

Please read the full advertisement

Description:

The improvements under this Contract consist of roundabout construction, milling and resurfacing, drainage improvements, sidewalk, curb and gutter, signing and pavement markings and lighting on SR15/700 in Okeechobee County, Florida from MP 1.339 to MP 1.546.

Call Order: 001 Proposal: E1S53

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43890215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43890215201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (43890215201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	32.000
	0102- 60-	WORK ZONE SIGN	ED	8,895.000
	0102- 61-	BUSINESS SIGN	EA	12.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	876.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	768.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,191.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	224.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	881.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	750.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	260.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,546.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000
	0107- 1-	LITTER REMOVAL	AC	28.910
	0107- 2-	MOWING	AC	10.480
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43890215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43890215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	166.000

Call Order: 001 Proposal: E1S53

ALT	Item	Description	Unit	Quantity
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	1,745.000
	0120- 6-	EMBANKMENT	CY	2,822.000
	0160- 4-	TYPE B STABILIZATION	SY	4,732.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	3,443.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	414.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1,140.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	1,013.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	840.900
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	330.500
	0350- 30- 13	CONCRETE PAVEMENT FOR ROUNDABOUT APRON, 12" DEPTH	SY	367.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	12.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	159.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	185.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,050.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	46.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	237.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	317.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	74.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	161.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,286.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	135.000
	0527- 2-	DETECTABLE WARNINGS	SF	244.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	5,898.000
	0591- 1- 74	IRRIGATION SLEEVE, 2" DIAMETER, PROJECT NUMBER 438902-1 -52-01	LF	60.000
	0591- 1- 75	IRRIGATION SLEEVE, 4" DIAMETER, PROJECT NUMBER 438902-1 -52-01	LF	357.000
	0591- 1- 76	IRRIGATION SLEEVE, 6" DIAMETER, PROJECT NUMBER 438902-1 -52-01	LF	115.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.684
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	205.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	70.000
	0710- 11-144	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE FOR ROUNDABOUT, 12"	GM	0.025
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	3.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.281

Call Order: 001 Proposal: E1S53

ALT	Item	Description	Unit	Quantity
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	53.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43890215201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	32.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0705- 11- 3	DELINEATOR, FLEXIBLE HIGH VISIBILITY MEDIAN	EA	3.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	8.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	6.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43890215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	205.000
	0711- 11-144	THERMOPLASTIC, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE, 12" FOR ROUNDABOUT	GM	0.025
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	53.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	180.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.607
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.645
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	918.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	160.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	11.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,810.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	2,380.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,950.000
	0715- 4- 12	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT	EA	7.000
	0715- 4- 60	LIGHT POLE COMPLETE, RELOCATE	EA	2.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	7.000