

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	01200611	Call Order: 002	Proposal: E1S54	District:01
Counties:	CHARLOTTE			
Road Name:	SR 31			
Limits:	01030000			
Project(s):	44334015201(*)	Federal Aid No: N/A		
Total Roadway Length:	1.193 Miles	Contract Days:	160	
Total Bridge Length:	0.000 Miles	Letting Date:	06/11/20	
Total Proposal Length:	1.193 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$1,728,446.00

Please read the full advertisement

**Description:**

The improvements under this Contract consist of milling and resurfacing, shoulder reconstruction, base work, drainage improvements, guardrail, and highway signing and pavement markings on State Road 31 from Myrtle Slough, northerly approximately 1.193 miles, to south of the DeSoto County Line in Charlotte County.

**Call Order: 002 Proposal: E1S54**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44334015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44334015201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (44334015201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (44334015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,647.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,218.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	214.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	522.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	60.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	30.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,438.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	92.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	102.000
	0107- 1-	LITTER REMOVAL	AC	70.890
	0107- 2-	MOWING	AC	62.340
	0110- 1- 1	CLEARING & GRUBBING (44334015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	84.000
	0120- 1-	REGULAR EXCAVATION	CY	5,579.700
	0120- 6-	EMBANKMENT	CY	2,381.400
	0160- 4-	TYPE B STABILIZATION	SY	12,898.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	6,815.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	165.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	900.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	5,204.000

**Call Order: 002 Proposal: E1S54**

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	12,426.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	3,701.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,994.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	48.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	676.000
	0430-174-230	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 30"SD	LF	310.000
	0430-174-236	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 36"SD	LF	99.000
	0430-175-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"S/CD	LF	150.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	6.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	22.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	8.000
	0430-984-638	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 36" SD	EA	2.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	81.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	248.700
	0530- 74-	BEDDING STONE	TN	88.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,175.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	29.000
	0536- 73-	GUARDRAIL REMOVAL	LF	800.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	48,266.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.726
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.230
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.006
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44334015201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	2.363
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.615
	0701- 18-221	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	1.003
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44334015201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	28.000