Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 01201015 Call Order: 001 Proposal: E1T68 District:01
Counties: POLK
Road Name: SR 35
Limits: 16060000
Project(s): 43980115201(*) Federal Aid No: N/A

Total Roadway Length:	0.273 Miles	Contract Days:	75
Total Bridge Length:	0.000 Miles	Letting Date:	10/15/20
Total Proposal Length:	0.273 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Days (Aqui Time)

Proposal Budget Estimate: $217,635.00

Please read the full advertisement

Description:

The improvements under this Contract consist of pond construction, desilting pipes and sodding along SR 35/700 (US 98) in Polk County.

Call Order: 001 Proposal: E1T68

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43980115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43980115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	375.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,725.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	89.000
	0104- 10- 3	SEDIMENT BARRIER	LF	856.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	40.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	578.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	13.000
	0107- 1-	LITTER REMOVAL	AC	5.700
	0107- 2-	MOWING	AC	5.310
	0110- 1- 1	CLEARING & GRUBBING (43980115201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	6,663.000
	0120- 6-	EMBANKMENT	CY	1,382.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0430- 94-100	DESILTING PIPE, 0 - 24", PROJECT 439801-1-52-01	LF	158.000
	0430- 94-102	DESILTING PIPE, 25-36", PROJECT 439801-1-52-01	LF	187.000
	0430- 94-103	DESILTING PIPE, 37-48", PROJECT 439801-1-52-01	LF	774.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	8.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	24.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	25.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,679.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43980115201)	LS	1.000