

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 01210415 Call Order: 006 Proposal: E1U46-R0 District:01
Counties: DIST/ST-WIDE, POLK
Road Name: Pipe Video, Desilting, Sealing, and Lining.
Limits: Midpoint
Project(s): 43272727223(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 365
Total Bridge Length: 0.000 Miles Letting Date: 04/15/21
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time:

Proposal Budget Estimate: \$200,000.00

Please read the full advertisement

Description:

The work under this contract consists of Pipe Video, Desilting, Sealing, and Lining.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E1U46-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PRESSURE GROUTING (CF)				
	0173- 76-	GROUT PIPE INSTALLATION	LF	150.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	12.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	3.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	3.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	10.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	20.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	25.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	25.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	15.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	15.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	10.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	10.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	5.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	5.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	25.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	1.000
	E425- 73- 8	MANHOLE COVER	EA	1.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	2,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	1,500.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	1,000.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	1,000.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	1,000.000
	E430-949- 13	DESILTING PIPE (UNDERDRAIN) (4")	LF	250.000
	E430-949- 16	DESILTING PIPE (UNDERDRAIN) (6")	LF	250.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	125.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	175.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	100.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	75.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	50.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	6,500.000