Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 01210819 Call Order: 001 Proposal: E1U27 District:01

Counties: MANATEE

Road Name: SR 55

Limits: 13130000

Project(s): 44430815201(*) Federal Aid No: N/A

Total Roadway Length:	0.421 Miles	Contract Days:	170
Total Bridge Length:	0.423 Miles	Letting Date:	08/19/21
Total Proposal Length:	0.844 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days (Aqui Time)

Proposal Budget Estimate: $559,972.00

Please read the full advertisement

Description:

The improvements under this Contract consist of structural repairs to Bridge No. 130053 (State Road 55 over Manatee River) in Manatee County.

Call Order: 001 Proposal: E1U27

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	630.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	266.000
	0457- 2-121	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	26.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	32.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,116.000
	0460-112-	ANCHOR BOLT REPLACEMENT	EA	15.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44430815201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44430815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44430815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,920.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,510.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	310.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	164.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	5,800.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44430815201)	LS	1.000