

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	01210121	Call Order: 002	Proposal: E1T43	District:01
Counties:	COLLIER			
Road Name:	SR 951			
Limits:	03030000			
Project(s):	43485715201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.302 Miles	Contract Days:	200	
Total Bridge Length:	0.302 Miles	Letting Date:	01/21/21	
Total Proposal Length:	0.604 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	
Proposal Budget Estimate:	\$1,304,836.00			

Please read the full advertisement

**Description:**

The improvements under this Contract consist of structural repairs to Bridge No. 030148 (State Road 951 Northbound over Big Marco Pass) in Collier County.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E1T43**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43485715201)	LS	1.000
	0110- 73-	REMOVE EXISTING BULKHEAD	LF	131.000
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	14.100
	0400-142- 3	CATHODIC PROTECTION SYSTEM, ZINC ALUMINUM SPRAY	SF	470.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	10,270.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	95.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	8.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	70.000
	0413-151-	METHACRYLATE MONOMER	GA	104.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	10,400.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	2,115.000
	0457- 2-121	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	60.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	84.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	529.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	22.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43485715201)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43485715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43485715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,000.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	96.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	214.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,950.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43485715201)	LS	1.000