

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 01210916                      Call Order: 001      Proposal: E1U11                      District:01  
Counties: MANATEE  
Road Name: MANATEE COUNTY SCOUR COUNTERMEASURE AT VARIOUS LOCATIONS  
Limits: 13010001  
Project(s): 43503825201(\*)                      Federal Aid No: N/A  
Total Roadway Length: 1.278 Miles                      Contract Days: 200  
Total Bridge Length: 1.264 Miles                      Letting Date: 09/16/21  
Total Proposal Length: 2.542 Miles                      Contract Execution Days:  
Special Start Date: N/A  
Aquis/Flexible Start Time: 60 Days (Aqui Time)  
Proposal Budget Estimate: \$1,990,016.00

Please read the full advertisement

Description:

The improvements under this Contract consist of bridge repairs to Bridge No. 130006 (State Road 684 over Sarasota Pass), Bridge No. 130060 (State Road 64 over Wares Creek), Bridge No. 130132 (State Road 45 over Manatee River), and Bridge No. 130142 (State Road 64 over Manatee River) in Manatee County.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E1U11**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	105.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	10.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	200.000
	0457- 2-121	CATHODIC PROTECTION INTEGRAL PILE JACKET, NON-STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	16.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	21.000
	0465- 20-	MOVABLE BRIDGE- PREVENTATIVE MAINTENANCE & ROUTINE REPAIR (43503825201 - Bridge No. 130006)	LS	1.000
	0465- 21-	MOVABLE BRIDGE OPERATOR	DA	112.000
	0465- 71- 3	MOVABLE BRIDGE FUNCTIONAL CHECKOUT, PHASE C (43503825201 - Bridge No. 130006)	LS	1.000
	0508- 73- 1	SUBMARINE CABLE ASSEMBLY, FURNISH & INSTALL (43503825201 - Bridge No. 130006)	LS	1.000
	0508- 73- 4	SUBMARINE CABLE ASSEMBLY, REMOVE (43503825201 - Bridge No. 130006)	LS	1.000
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	670.000
	0530- 74-	BEDDING STONE	TN	1,173.000
	0920-530- 4	FABRIC FORMED CONCRETE RIPRAP, PROJECT 435038-2-52-01	SY	1,600.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43503825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43503825201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,140.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	440.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	284.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	9,150.000
	0110- 1- 1	CLEARING & GRUBBING (43503825201)	LS	1.000
	0120- 5-	CHANNEL EXCAVATION	CY	390.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43503825201)	LS	1.000