

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 01220519 Call Order: 009 Proposal: Z1100-R0 District:01  
 Counties: DIST/ST-WIDE  
 Road Name: Emergency Lighting Permanent Repair and Replacement  
 Limits: Midpoint  
 Project(s): 4506111F201(\*) Federal Aid No: N/A  
 Total Roadway Length: 0.000 Miles Contract Days: 365  
 Total Bridge Length: 0.000 Miles Letting Date: 05/19/22  
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time:

Proposal Budget Estimate: \$ .00

Please read the full advertisement

Description:

Emergency Lighting Permanent Repair and Replacement  
 PRE-QUALIFICATION IS REQUIRED

**Call Order: 009 Proposal: Z1100-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 EMERGENCY LIGHTING REPAIRS (MH)</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	500.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	50.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	50.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	5.000
	0635- 2- 50	PULL & SPLICE BOX, REPAIR	EA	10.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	5.000
	0639- 10-	ELECTRICAL POWER SERVICE DIAGNOSTIC AND MISCELLANEOUS REPAIR	EA	25.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	500.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	500.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	500.000
	0715- 1- 16	LIGHTING CONDUCTORS, F&I, NO.4/0 (0000) OR LARGER	LF	500.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	50.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	50.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	10.000
	0715- 10- 3	LIGHT POLE FOUNDATION, REPAIR	EA	100.000
	0715- 10- 4	LIGHT POLE FOUNDATION, STRAIGHTEN EXISTING FOUNDATION	EA	100.000
	0715- 10- 5	LIGHT POLE FOUNDATION, REMOVE FOUNDATION- NO EXISTING POLE	EA	10.000
	0715- 11-118	LUMINAIRE, F&I, ROADWAY, FLOOD	EA	10.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	10.000
	0715- 11-128	LUMINAIRE, F&I, UNDER DECK, FLOOD	EA	10.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	300.000

**Call Order: 009 Proposal: Z1100-R0**

ALT	Item	Description	Unit	Quantity
	0715- 11-213	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, POLE TOP	EA	200.000
	0715- 11-216	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, PENDANT/TEARDROP	EA	100.000
	0715- 11-400	LUMINAIRE, RELOCATE	EA	50.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	25.000
	0715- 16- 5	LIGHTING - BALLAST, REPLACE	EA	500.000
	0715- 19- 3	LIGHTING - REPLACE EXISTING SURGE PROTECTOR	EA	500.000
	0715- 36- 12	LIGHT POLE, FRANGIBLE BASE, F&I, TRANSFORMER BASE	EA	100.000
	0715- 36- 14	LIGHT POLE, FRANGIBLE BASE, F&I, DOOR ASSEMBLY	EA	200.000
	0715-100- 1	LIGHT POLE COMPLETE- 30' TO 50 STANDARD FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	200.000
	0715-100- 2	LIGHT POLE COMPLETE- 30' TO 50 SPECIAL FOUNDATION, PRE-EVENT CONTRACT ONLY	EA	100.000
	0715-100- 3	LIGHT POLE REPLACE ON EXISTING FOUNDATION- 30' TO 50', PRE-EVENT CONTRACT ONLY	EA	500.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	500.000
	E715- 16- 1	BALLAST (F&I)	EA	300.000
	E715- 16- 2	BALLAST ASSEMBLY (F&I)	AS	100.000
	E715- 17- 1	LAMP (HPS)	EA	100.000
	E715- 17- 2	LAMP (MERCURY VAPOR)	EA	100.000
	E715- 17- 3	LAMP (METAL HALIDE)	EA	100.000
	E715- 17- 5	LAMP (LPS)	EA	100.000
	E715- 17- 9	LAMP (LED)	EA	100.000
	E715- 18-101	LOAD CENTER PART (F&I) (SGL POLE BREAKER)	EA	10.000
	E715- 18-102	LOAD CENTER PART (F&I) (DBL POLE BREAKER)	EA	10.000
	E715- 18-104	LOAD CENTER PART (F&I)(BREAKER PANEL & ENCLOSURE)	EA	10.000
	E715- 18-105	LOAD CENTER PART (F&I) (CONTACTOR)	EA	10.000
	E715- 18-107	LOAD CENTER PART (F&I) (PHOTOCELL)	EA	10.000
	E715- 18-108	LOAD CENTER PART (F&I) (PHOTOCELL SOCKET)	EA	10.000
	E715- 18-110	LOAD CENTER PART (F&I)(SYSTEM SWITCH AUTO-OFF/ON)	EA	10.000
	E715- 18-111	LOAD CENTER PART (F&I) (LIGHTNING ARRESTOR)	EA	10.000
	E715- 18-112	LOAD CENTER PART (F&I) (CIRCUIT FUSE)	EA	10.000
	E715- 18-113	LOAD CENTER PART (F&I) (MAIN FUSE)	EA	10.000
	E715- 18-114	LOAD CENTER PART (F&I) (DUMMY SLUG)	EA	10.000
	E715- 18-115	LOAD CENTER PART(SFTY DIS SWTCH BOX,600V)(F&I)	EA	10.000
	E715- 18-116	LOAD CENTER PART (F&I) (COVER PLATE)	EA	10.000
	E715- 19- 99	LIGHTING - CABLE REMOVAL DETERRENT SYSTEM	EA	10.000
	E715- 22- 1	GROUND ROD	EA	25.000
	E715- 23- 1	REFRACTER (F&I) (STANDARD COBRA HEAD)	EA	100.000
	E715- 24- 1	FUSE (F&I) (POLE BASE)	EA	100.000
	E715- 24- 2	FUSE (F&I) (SIGN)	EA	100.000
	E715- 24- 4	DUMMY SLUG (F&I) (POLE BASE)	EA	100.000
	E715- 25- 1	FUSE HOLDER (F&I) (POLE BASE)	EA	100.000
	E715- 25- 2	FUSE HOLDER / DISCONNECT PLUG (F&I)	EA	100.000
	E715- 25- 41	FUSE HOLDER POLE BASE INSTALL ONLY	EA	100.000

**Call Order: 009 Proposal: Z1100-R0**

ALT	Item	Description	Unit	Quantity
	E715- 26- 4	QUICK DISCONNECT PLUG (MODULAR POLE BASE)	EA	100.000
	E715- 26- 13	SWITCH BOX (INSTALL) (FOR SIGN STRUCTURE)	EA	100.000
	E715- 32- 1	DIAGNOSTIC WORK (SHOULDER SINGLE ARM)	LO	500.000
	E715- 32- 2	DIAGNOSTIC WORK (SHOLDER DOUBLE ARM)	LO	500.000
	E715- 32- 3	DIAGNOSTIC WORK (MED SGL ARM WALL MTD)	LO	500.000
	E715- 32- 4	DIAGNOSTIC WORK (MED DBL ARM WALL MTD)	LO	500.000
	E715- 32- 5	DIAGNOSTIC WORK (BRIDGE MTD)	LO	500.000
	E715- 32- 6	DIAGNOSTIC WORK (UNDERDECK)	LO	500.000
	E715- 32- 7	DIAGNOSTIC WORK (LOAD CENTER)	LO	500.000
	E715- 32- 10	DIAGNOSTIC WORK (CIRCUIT)	LO	500.000
	E715- 32- 13	DIAGNOSTIC WORK (TOP MOUNT)	LO	500.000
	E715- 34- 03	LIGHT POLE (HANDHOLE) (DOOR ASSEMBLY) (F&I)	EA	200.000
	E715- 43- 1	ARRESTOR (HIGH VOLTAGE PRIMARY LIGHTING)	EA	100.000
	E715- 50-220	LIGHTING TRANSFORMER (F&I)(PAD MOUNT)	EA	10.000
	E715-561-101	LIGHT POLE-LEVELING (ALUM/STEEL, CONCRETE FOUNDATION)	EA	10.000