

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 01220519 Call Order: 012 Proposal: Z1103-R0 District:01
 Counties: CHARLOTTE, COLLIER, DESOTO, DIST/ST-WIDE, GLADES, HARDEE, HENDRY, HIGHLANDS, LEE, OKEECHOBEE

Road Name: Pre-Event Single and Multi-Post Sign
 Limits: Midpoint

Project(s): 4506123E201(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	05/19/22
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$.00

Please read the full advertisement

Description:

Pre-Event Single and Multi-Post Sign
 Experience Form Required

Call Order: 012 Proposal: Z1103-R0

ALT	Item	Description	Unit	Quantity
Section 0001 EMER.DELINEATOR/ATTENUATOR/SIGN REPR(EA)				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	500.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,000.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	340.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	600.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	600.000
	0634- 4-142	SPAN WIRE ASSEMBLY, F&I, SINGLE POINT, DIAGONAL	PI	4.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	20.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	20.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 1-113	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER NOT REQUIRED	AS	4.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	4.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	4.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	5.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	4.000
	0670- 4- 1	INTERSECTION CONTROL BEACON CONTROLLER ASSEMBLY, FURNISH & INSTALL	AS	10.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	50.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	50.000

Call Order: 012 Proposal: Z1103-R0

ALT	Item	Description	Unit	Quantity
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	30.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	10.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	6.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	3.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	2.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	2.000
	0700- 1- 80	SINGLE POST SIGN, REPAIR	AS	100.000
	0700- 1- 87	SINGLE POST SIGN, REPAIR- REPLACE POST, USE EXISTING SIGN PANEL	AS	100.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	30.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	60.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	60.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	10.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	30.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	30.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	30.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	10.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	50.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	50.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	30.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	10.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	10.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	30.000
	0700- 3-107	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 201-300 SF	EA	30.000
	0700- 3-108	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 301-400 SF	EA	30.000
	0700- 3-109	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 401-500 SF	EA	10.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	10.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	10.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	10.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	10.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	10.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	10.000
	0700- 3-208	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF	EA	10.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	10.000
	0700- 3-210	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 501-600 SF	EA	10.000
	0700- 3-211	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 601 SF AND GREATER	EA	10.000
	0700- 3-301	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	EA	5.000
	0700- 3-302	SIGN PANEL, FURNISH & INSTALL SINGLE POST BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	EA	5.000

Call Order: 012 Proposal: Z1103-R0

ALT	Item	Description	Unit	Quantity
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	30.000
	0700- 3-402	SIGN PANEL, INSTALL, 12-20 SF	EA	30.000
	0700- 3-403	SIGN PANEL, INSTALL, 21-30 SF	EA	30.000
	0700- 3-404	SIGN PANEL, INSTALL, 31-50 SF	EA	30.000
	0700- 3-405	SIGN PANEL, INSTALL, 51-100 SF	EA	30.000
	0700- 3-406	SIGN PANEL, INSTALL, 101-200 SF	EA	30.000
	0700- 3-407	SIGN PANEL, INSTALL, 201-300 SF	EA	30.000
	0700- 3-408	SIGN PANEL, INSTALL, 301-400 SF	EA	30.000
	0700- 4-111	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, UP TO 20 FT	EA	3.000
	0700- 4-112	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 21-30 FT	EA	3.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	3.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	3.000
	0700- 4-121	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, UP TO 20 FT	EA	3.000
	0700- 4-122	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, SPAN, 21-30 FT	EA	3.000
	0700- 5- 11	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	50.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	100.000
	0700- 11-121	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, ELECTRONIC REGULATORY SIGN, UP TO 12 SF	AS	5.000
	0700- 11-321	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, REGULATORY SIGN, UP TO 12 SF	AS	25.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	5.000
	0700- 12- 12	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, TWO BEACONS	AS	5.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	20.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	20.000
	0700- 12- 31	SIGN BEACON, F&I OVERHEAD MOUNT, ONE BEACON	AS	10.000
	0700- 12- 32	SIGN BEACON, F&I OVERHEAD MOUNT, TWO BEACONS	AS	30.000
	0700- 12- 60	SIGN BEACON, REMOVE BEACON- SIGN TO REMAIN	AS	1.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	75.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	50.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	50.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	50.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	50.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	25.000
	E700- 46- 32	REPAIR EXISTING SIGN (MULTI POST)	AS	200.000