

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	01221103	Call Order:	001	Proposal:	E1V20	District:	01
Counties:	DESOTO						
Road Name:	SR 72						
Limits:	04060000						
Project(s):	44620315201(*)	Federal Aid No:	N/A				
Total Roadway Length:	4.085 Miles	Contract Days:	185				
Total Bridge Length:	0.000 Miles	Letting Date:	11/03/22				
Total Proposal Length:	4.085 Miles	Contract Execution Days:	10				
		Special Start Date:	N/A				
		Aquis/Flexible Start Time:	15 Days				
Proposal Budget Estimate:	\$4,052,109.26						

Please read the full advertisement

**Description:**

The improvements under this Contract consist of cross slope correction, milling and resurfacing, shoulder reconstruction, miscellaneous drainage and signing and pavement markings along SR 72 from Sarasota County Line to Bridge Over Horse Creek in DeSoto County

**Call Order: 001 Proposal: E1V20**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44620315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,550.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,395.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	15.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	398.000
	0102-115-	TYPE III BARRICADE	ED	83.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	185.000
	0104- 10- 3	SEDIMENT BARRIER	LF	42,268.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	48.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	76.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	238.920
	0107- 2-	MOWING	AC	212.220
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44620315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44620315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,109.600
	0120- 6-	EMBANKMENT	CY	3,836.300
	0160- 4-	TYPE B STABILIZATION	SY	4,206.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,835.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	17,310.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	24,163.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	1,083.000

**Call Order: 001 Proposal: E1V20**

ALT	Item	Description	Unit	Quantity
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	22,015.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	2,762.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	2,889.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	349.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	268.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	5,072.000
	0327- 70- 22	MILLING EXISTING ASPHALT PAVEMENT, 4 1/4" AVG DEPTH	SY	1,894.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1,205.400
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	7,081.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	6,556.400
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	102.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	33,489.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	540.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620315201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	12.242
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	46.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	8.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	12.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	540.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620315201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	8.157
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.504
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	3.781