# Florida Department of Transportation
## Bid Solicitation Notice and Approximate Quantities

Letting: 01221103 Call Order: 002 Proposal: E1V82-R0 District:01

Counties: POLK

Road Name: Handline Thermoplastic

Limits: Midpoint

Project(s): 43272727231(*) Federal Aid No: N/A

| | | | |
|---|---|---|---|
| Total Roadway Length: | 0.000 Miles | Contract Days: | 365 |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 11/03/22 |
| Total Proposal Length: | 0.000 Miles | Contract Execution Days: | 10 |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | |

Proposal Budget Estimate: $325,000.00

Please read the full advertisement

Description:

The work under this Contract consists of Handline Thermoplastic.

**Call Order: 002 Proposal: E1V82-R0**

| ALT | Item | Description | Unit | Quantity |
|---|---|---|---|---|
| **Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)** | | | | |
| | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND | GM | 5.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 8,000.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 1,000.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 1,000.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 5.000 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 200.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 200.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 1,000.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 5.000 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 150.000 |
| | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW | EA | 150.000 |
| | 0711- 16-202 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8" | GM | 5.000 |
| | 0711- 17- 1 | THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN | SF | 1,000.000 |
| | E711- 11-121 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" | LF | 1,000.000 |