

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01220915	Call Order: 002	Proposal: E1V07	District:01
Counties:	DESOTO			
Road Name:	SR 70			
Limits:	04040000			
Project(s):	44023115201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.023 Miles	Contract Days:	75	
Total Bridge Length:	0.023 Miles	Letting Date:	09/15/22	
Total Proposal Length:	0.046 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$302,829.71

Please read the full advertisement

Description:

The improvements under this Contract consist of repairs to Bridge #040027 including spall repairs to substructure and superstructure, non-structural pile jackets and slope protection repairs on SR 70 over Joshua Creek in Desoto County.

Call Order: 002 Proposal: E1V07

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	0.600
	0457- 1- 11	STANDARD INTEGRAL PILE JACKET, NON-STRUCTURAL, UP TO 16"	LF	154.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	5.900
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	77.600
	0530- 74-	BEDDING STONE	TN	4.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44023115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44023115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	750.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	178.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	150.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	150.000
	0104- 10- 3	SEDIMENT BARRIER	LF	260.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	396.000
	0110- 1- 1	CLEARING & GRUBBING (44023115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44023115201)	LS	1.000