

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01230420	Call Order: 006	Proposal: E1W34	District:01
Counties:	POLK			
Road Name:	Milling, Resurfacing, Shoulder Reconstruction, Guardrail Rep			
Limits:	16120000			
Project(s):	44463515201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.236 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	04/20/23	
Total Proposal Length:	0.236 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	0	

Proposal Budget Estimate: \$249,613.00

Please read the full advertisement

Description:

The work under this Contract consists of Milling and Resurfacing, Shoulder and front slope reconstruction due to ongoing erosion, Increase/widen the radius at 24th Street, MP 1.983 in the SE and SW quadrant due to off-tracking, Remove and replace existing guardrail and end anchorage assemblies and install to a new FDOT specifications.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 006 Proposal: E1W34

ALT	Item	Description	Unit	Quantity
Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)				
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	60.000
	0120- 1-	REGULAR EXCAVATION	CY	72.210
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	52.470
	0160- 4-	TYPE B STABILIZATION	SY	310.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	114.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	43.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,805.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	4,661.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	304.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	548.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	13.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	325.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	12.000
	0536- 73-	GUARDRAIL REMOVAL	LF	325.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,500.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	300.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.450
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	50.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	36.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	5.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.430
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.110
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.140
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	50.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	36.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.450
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.430
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.110
	E577- 70-	SHOULDER REWORK	SY	2,500.000