Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 01230817 Call Order: 001 Proposal: E1W15 District:01

Counties: POLK

Road Name: SR 60 BRIDGE # 160129 AND # 160130

Limits: 16110000

Project(s): 44464315201(*) Federal Aid No: N/A

Total Roadway Length:	0.148 Miles	Contract Days:	180
Total Bridge Length:	0.148 Miles	Letting Date:	08/17/23
Total Proposal Length:	0.296 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days (Aqui Time)

Proposal Budget Estimate: $515,022.43

Please read the full advertisement

Description:

The improvements under this Contract consist of rehabilitation of Bridge Nos. 160129 & 160130, including the cleaning and coating existing steel bearings and steel girders, bridge deck expansion joint replacement, methacrylate deck repair and the repair of concrete diaphragm spalls along SR 60 in Polk County.

Call Order: 001 Proposal: E1W15

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	11.100
	0413-151-	METHACRYLATE MONOMER	GA	168.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	26,027.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	660.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44464315201)	LS	1.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	181.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44464315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44464315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,160.000
	0102- 60-	WORK ZONE SIGN	ED	3,060.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,502.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	90.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	478.000
	0102-115-	TYPE III BARRICADE	ED	2,610.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44464315201)	LS	1.000