

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	01230216	Call Order: 003	Proposal: E1V17	District:01
Counties:	CHARLOTTE			
Road Name:	SR 776			
Limits:	01050000			
Project(s):	44547515201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.496 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	02/16/23	
Total Proposal Length:	3.496 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$3,388,273.21

Please read the full advertisement

**Description:**

The improvements under this Contract consist of milling and resurfacing, median widening, sidewalk replacement, drainage improvements, signing and pavement markings along SR 776 from Myakka River to Willowbend Drive in Charlotte County, Florida.

**Call Order: 003 Proposal: E1V17**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44547515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44547515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	10,236.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,146.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,440.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	22.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	22.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	300.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	16,474.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	81.000
	0107- 1-	LITTER REMOVAL	AC	173.750
	0107- 2-	MOWING	AC	120.750
	0110- 1- 1	CLEARING & GRUBBING (44547515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,945.000
	0120- 1-	REGULAR EXCAVATION	CY	196.100
	0120- 6-	EMBANKMENT	CY	9.200
	0160- 4-	TYPE B STABILIZATION	SY	739.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	560.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	28,180.000

**Call Order: 003 Proposal: E1V17**

ALT	Item	Description	Unit	Quantity
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	29,848.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,420.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,957.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,701.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.300
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	796.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	978.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	22.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	798.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	436.000
	0527- 2-	DETECTABLE WARNINGS	SF	534.000
	0538- 1-	GUARDRAIL RESET	LF	36.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,384.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	47.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	42.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	792.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.154
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.355
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,415.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	235.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	370.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.437
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.082
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	72.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.716
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	206.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.284
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44547515201)	LS	1.000
<b>Section 0002 Signing</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.748
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	150.000

**Call Order: 003 Proposal: E1V17**

ALT	Item	Description	Unit	Quantity
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	64.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	38.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	83.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	39.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	17.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	986.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	30.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	829.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44547515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,415.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	235.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	370.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.082
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	72.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	14.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	206.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.284
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.164
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.357
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	3.438
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.718