

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01230119	Call Order: 003	Proposal: E1V15	District:01
Counties:	POLK			
Road Name:	SR 700			
Limits:	16040000			
Project(s):	44547015201	Federal Aid No:	N/A	
Project(s):	44547115201(*)	Federal Aid No:	N/A	
Total Roadway Length:	8.453 Miles	Contract Days:	225	
Total Bridge Length:	0.000 Miles	Letting Date:	01/19/23	
Total Proposal Length:	8.453 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	
Proposal Budget Estimate:	\$8,189,129.82			

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, shoulder gutter, tree removal, guardrail, and signing and pavement markings on State Road 700 (US 98) from Keller Road to west of Ridge Road and SR 700 (US 98) from east of Mount Zion Road to east of Old Stokes Road, in Polk County.

Call Order: 003 Proposal: E1V15

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44547015201)	LS	1.000
	0101- 1-	MOBILIZATION (44547115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44547015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44547115201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	22.300
	0102- 60-	WORK ZONE SIGN	ED	24,145.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	84,449.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	946.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	60.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	395.000
	0104- 10- 3	SEDIMENT BARRIER	LF	74,689.000
	0107- 1-	LITTER REMOVAL	AC	453.060
	0107- 2-	MOWING	AC	368.620
	0110- 1- 1	CLEARING & GRUBBING (44547015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44547115201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	71.000
	0110- 23-	TREE REMOVAL	EA	9.000
	0120- 1-	REGULAR EXCAVATION	CY	2,007.100
	0120- 6-	EMBANKMENT	CY	749.600
	0160- 4-	TYPE B STABILIZATION	SY	1,572.000

Call Order: 003 Proposal: E1V15

ALT	Item	Description	Unit	Quantity
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	97.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	5,114.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	321.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	33,172.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	17,070.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	71,737.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	1,695.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	8,969.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	13,797.000
	0327- 70- 21	MILLING EXISTING ASPHALT PAVEMENT, 7" AVG DEPTH	SY	4,809.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	14,178.700
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	448.900
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	4,279.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	8,947.100
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, HIGH POLYMER	TN	3,936.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	189.900
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	16.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	2,800.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,794.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	32.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,584.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	20.000
	0550- 10-118	FENCING, TYPE A, 0.0-5.0', TYPE A STANDARD, RESET EXISTING	LF	464.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,468.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	24,042.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,672.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	16.843
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	122.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.582
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	9.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.644
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44547015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44547115201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	35.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	28.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	16.804
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	8.448

Call Order: 003 Proposal: E1V15

ALT	Item	Description	Unit	Quantity
	0701- 18-221	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	4.587
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	18.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,672.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44547015201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44547115201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	122.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	9.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.039
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.134