

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01230720	Call Order: 003	Proposal: E1V22	District:01
Counties:	HARDEE			
Road Name:	SR 64			
Limits:	06030000			
Project(s):	44620615201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.307 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	07/20/23	
Total Proposal Length:	3.307 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$4,835,264.23

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, base work, drainage improvements, and signing and pavement marking work on State Road 64 from Prescott Road to Morgan Grice Road in Hardee County.

Call Order: 003 Proposal: E1V22

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44620615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620615201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44620615201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	95.300
	0102- 60-	WORK ZONE SIGN	ED	7,920.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,280.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	392.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,006.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,126.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	42.000
	0107- 1-	LITTER REMOVAL	AC	174.490
	0107- 2-	MOWING	AC	149.650
	0110- 1- 1	CLEARING & GRUBBING (44620615201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	8.000
	0120- 1-	REGULAR EXCAVATION	CY	313.200
	0120- 6-	EMBANKMENT	CY	1,151.200
	0160- 4-	TYPE B STABILIZATION	SY	1,673.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,307.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	216.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	450.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	23,751.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	19,862.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	20,005.000

Call Order: 003 Proposal: E1V22

ALT	Item	Description	Unit	Quantity
	0327- 70- 23	MILLING EXISTING ASPHALT PAVEMENT, 6" AVG DEPTH	SY	2,628.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	9,396.800
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, HIGH POLYMER	TN	5,459.900
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	275.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	98.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	78.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	50.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	24.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	14.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	2.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	14.600
	0530- 74-	BEDDING STONE	TN	10.500
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,168.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	10,307.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.474
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.392
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.760
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620615201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	9.613
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	24.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	20.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	17.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	1.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	695.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620615201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	151.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	39.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.054
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.474
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.392
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.760