

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	01230316	Call Order: 001	Proposal: E1V18	District:01
Counties:	HIGHLANDS			
Road Name:	SR 700			
Limits:	09110000			
Project(s):	44620815201(*)	Federal Aid No: N/A		
Total Roadway Length:	10.801 Miles	Contract Days:	300	
Total Bridge Length:	0.174 Miles	Letting Date:	03/16/23	
Total Proposal Length:	10.975 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (Aqui Time)	
Proposal Budget Estimate:	\$11,293,976.07			

Please read the full advertisement

**Description:**

The improvements under this Contract consist of milling and resurfacing, widening, reconstruction, guardrail & traffic railing, turnout construction and signing and pavement marking on SR 700 (US 98) from East of CR 621 to Bridge No. 090016 in Highlands County.

**Call Order: 001 Proposal: E1V18**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44620815201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44620815201)	LS	1.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	12.800
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	2.000
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	28.500
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	834.000
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	821.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	523.000
	0460- 71- 1	METAL TRAFFIC RAILING, THRIE BEAM RETROFIT	LF	1,342.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44620815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44620815201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44620815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	13,500.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	800.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	3,525.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	500.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	48,600.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	6,824.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	20.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	628.000
	0102-115-	TYPE III BARRICADE	ED	3,900.000

**Call Order: 001 Proposal: E1V18**

ALT	Item	Description	Unit	Quantity
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	224.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	1,200.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.405
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.085
	0104- 10- 3	SEDIMENT BARRIER	LF	11,632.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	900.000
	0107- 2-	MOWING	AC	780.000
	0110- 1- 1	CLEARING & GRUBBING (44620815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,676.000
	0120- 6-	EMBANKMENT	CY	505.000
	0160- 4-	TYPE B STABILIZATION	SY	5,204.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,114.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	472.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	645.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	54.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	198,099.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	27,843.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	16,784.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	86.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,011.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	8.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,775.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	15.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	32,600.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	23.846
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.038
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	507.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	87.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.338
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.415
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	584.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	8.670
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.097
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620815201)	LS	1.000

**Call Order: 001 Proposal: E1V18**

ALT	Item	Description	Unit	Quantity
<b>Section 0003 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	28.672
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	49.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	4.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	50.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	8.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	7.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	16.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	36.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,064.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	507.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	39.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.338
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	25.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	584.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.097
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	19.979
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.038
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.979
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	8.670
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.107
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.107