

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01230316	Call Order: 002	Proposal: E1V21	District:01
Counties:	SARASOTA			
Road Name:	SR 789			
Limits:	17030201			
Project(s):	44782415201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.586 Miles	Contract Days:	165	
Total Bridge Length:	0.587 Miles	Letting Date:	03/16/23	
Total Proposal Length:	1.173 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$1,666,013.18

Please read the full advertisement

Description:

The improvements under this Contract consist of bridge rehabilitation and repair including methacrylate deck sealing and concrete spall repair, as well as signing and pavement markings on SR 789 (John Ringling Causeway) - Bridge No 170176 in Sarasota County.

Call Order: 002 Proposal: E1V21

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	114.000
	0413-151-	METHACRYLATE MONOMER	GA	3,061.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	306,067.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44782415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44782415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,980.000
	0102- 60-	WORK ZONE SIGN	ED	4,485.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,398.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	7,008.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	165.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	542.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	9.496
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	11.472
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	9.496
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	9.368
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44782415201)	LS	1.000
Section 0003 Signing				
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.334
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.347
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.334
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	12.000

Call Order: 002 Proposal: E1V21

ALT	Item	Description	Unit	Quantity
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.206
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	7.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	4.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	174.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.092
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	36.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.150
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.129
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.129
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	720.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	2.945
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.982
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.982
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.982