

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 01231019 Call Order: 002 Proposal: E1W20 District:01

Counties: DESOTO

Road Name: SR 70

Limits: 04040000

Project(s): 44620215201(*)

Federal Aid No: N/A

Total Roadway Length:	2.332 Miles	Contract Days:	150
Total Bridge Length:	0.000 Miles	Letting Date:	10/19/23
Total Proposal Length:	2.332 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 Days (Aqui Time)

Proposal Budget Estimate: \$2,845,365.49

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, signalization and signing and pavement markings on SR 70 from Turner Avenue to east of the Ford dealership in Desoto County.

Call Order: 002 Proposal: E1W20

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44620215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,500.000
	0102- 60-	WORK ZONE SIGN	ED	9,010.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,300.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	666.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	300.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	11,836.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	86.200
	0107- 2-	MOWING	AC	109.550
	0110- 1- 1	CLEARING & GRUBBING (44620215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	1,452.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	8,575.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	25,310.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,752.000
	0327- 70- 17	MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH	SY	9,279.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2,118.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,241.100
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	16.000
	0527- 2-	DETECTABLE WARNINGS	SF	186.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,356.000

Call Order: 002 Proposal: E1W20

ALT	Item	Description	Unit	Quantity
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,301.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.058
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.989
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	905.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,328.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,056.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.625
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.111
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	95.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.574
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	421.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.184
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620215201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.760
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	54.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	15.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	74.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	6.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	28.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	20.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	51.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	17.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,323.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	2.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	56.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620215201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	905.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,328.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	521.000

Call Order: 002 Proposal: E1W20

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.111
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	95.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	421.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.184
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	571.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.058
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.989
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	1.761
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.589
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,242.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	15.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	4.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	19.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	30.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	2.000