

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01240418	Call Order: 001	Proposal: E1W18	District:01
Counties:	POLK			
Road Name:	SR 700 (US 98)			
Limits:	16040000			
Project(s):	44743115201(*)	Federal Aid No: N/A		
Total Roadway Length:	1.872 Miles	Contract Days:	170	
Total Bridge Length:	0.000 Miles	Letting Date:	04/18/24	
Total Proposal Length:	1.872 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	
Proposal Budget Estimate:	\$2,711,978.24			

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, signing and pavement marking, modification and replacement of the traffic separator, and drainage improvements along SR 700 (US 98) from E. of Old Stokes Road and to SR 25 (US 27) slip lane in Polk County.

Call Order: 001 Proposal: E1W18

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44743115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44743115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	528.000
	0102- 60-	WORK ZONE SIGN	ED	12,329.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,370.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	340.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	894.000
	0102-115-	TYPE III BARRICADE	ED	450.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,094.000
	0107- 1-	LITTER REMOVAL	AC	74.280
	0107- 2-	MOWING	AC	64.920
	0110- 1- 1	CLEARING & GRUBBING (44743115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	273.000
	0120- 1-	REGULAR EXCAVATION	CY	300.700
	0120- 6-	EMBANKMENT	CY	656.900
	0160- 4-	TYPE B STABILIZATION	SY	2,488.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	1,021.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,138.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	22,397.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	7,832.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	3,647.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	2,635.400
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	12.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	180.000

Call Order: 001 Proposal: E1W18

ALT	Item	Description	Unit	Quantity
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	62.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	6.000
	0430-982-629	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	3.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	410.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	412.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	122.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,121.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,366.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.988
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	292.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.184
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	26.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.532
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	388.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.614
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.076
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44743115201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	3.462
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	14.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	9.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	1.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	11.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	683.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44743115201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	146.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.092
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	13.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	194.000

Call Order: 001 Proposal: E1W18

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.038
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	38.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	282.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.994
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.766
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.307