

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01240815	Call Order: 001	Proposal: E1W76	District:01
Counties:	OKEECHOBEE			
Road Name:	SR 700 (US 98)			
Limits:	91090000			
Project(s):	44897215201(*)	Federal Aid No: N/A		
Total Roadway Length:	6.165 Miles	Contract Days:	140	
Total Bridge Length:	0.000 Miles	Letting Date:	08/15/24	
Total Proposal Length:	6.165 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$4,602,285.86			

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, and pavement markings on State Road 700 (US 98) from bridge #910090 northwesterly to NW 80th Avenue in Okeechobee County.

Call Order: 001 Proposal: E1W76

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44897215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44897215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,480.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,500.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	308.000
	0102-115-	TYPE III BARRICADE	ED	280.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	140.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,350.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	358.000
	0107- 2-	MOWING	AC	328.100
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	87,158.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	27,184.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,992.100
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	7,861.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	18,739.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,163.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	12.235
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	445.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	24.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.023
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	4.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.221
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	5.598
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44897215201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	18.075
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,163.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44897215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	445.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.023
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	12.235
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.221
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	5.598
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.101
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.101