

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 01241205	Call Order: 008	Proposal: E1W89	District: 01
Counties: POLK			
Road Name: SR 25 (US 27)			
Limits: 16180000			
Project(s): 44927515201(*)	Federal Aid No: N/A		
Total Roadway Length: 7.794 Miles	Contract Days: 200		
Total Bridge Length: 0.000 Miles	Letting Date: 12/05/24		
Total Proposal Length: 7.794 Miles	Contract Execution Days: 10		
	Special Start Date: N/A		
	Aquis/Flexible Start Time: 60 Days (Aqui Time)		

Proposal Budget Estimate: \$11,780,638.00

Please read the full advertisement

**Description:**

The improvements under this Contract consist of milling and resurfacing, shoulder treatment, pavement markings and signalization on SR 25 (US 27) from north of Holly Hill Cut-off Road to north of Deer Creek Blvd in Polk County.

**Call Order: 008 Proposal: E1W89**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44927515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44927515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,734.000
	0102- 60-	WORK ZONE SIGN	ED	21,600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,200.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	100.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	270.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	428.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-115-	TYPE III BARRICADE	ED	240.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	400.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	400.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,444.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	667.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	66.000
	0107- 1-	LITTER REMOVAL	AC	385.430
	0107- 2-	MOWING	AC	350.240
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,531.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	82,513.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	144,992.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	26,711.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	9,128.600

**Call Order: 008 Proposal: E1W89**

ALT	Item	Description	Unit	Quantity
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	1,116.300
	0527- 2-	DETECTABLE WARNINGS	SF	220.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	19,470.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	115.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	60.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	175.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0695- 2- 1	TRAFFIC MONITORING SITE NON-INTRUSIVE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	6.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,703.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.901
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.767
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,308.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,780.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	3,851.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	14.524
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.258
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	295.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	11.184
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	788.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.674
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44927515201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	7.144
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	38.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,562.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	692.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44927515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,646.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,780.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,122.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.258
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	295.000

**Call Order: 008 Proposal: E1W89**

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	788.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.674
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,170.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	11.916
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.767
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	14.524
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	7.456
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3,621.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,016.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	20.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	42.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	24.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	72.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	14.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	4.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	4.000