

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	01241205	Call Order: 002	Proposal: E1W92	District:01
Counties:	COLLIER			
Road Name:	SR 90 (US 41)			
Limits:	03010000			
Project(s):	44892915201	Federal Aid No:	N/A	
Project(s):	44893015201(*)	Federal Aid No:	N/A	
Total Roadway Length:	10.314 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	12/05/24	
Total Proposal Length:	10.314 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	
Proposal Budget Estimate:	\$11,363,552.46			

Please read the full advertisement

**Description:**

The improvements under this Contract consist of milling and resurfacing, pavement markings, curb and gutter, sidewalk, and signalization on SR 90 from N. of Thomasson Dr to S. of Southwest Blvd and SR 29 from N. of Wagon Wheel Rd to S. of I-75 in Collier County.

**Call Order: 002 Proposal: E1W92**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44892915201)	LS	1.000
	0101- 1-	MOBILIZATION (44893015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44892915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44893015201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44893015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,200.000
	0102- 60-	WORK ZONE SIGN	ED	10,424.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	72,612.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,087.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	800.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,348.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,000.000
	0102-115-	TYPE III BARRICADE	ED	7,680.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	400.000
	0104- 7-	SEDIMENT BASIN / CONTAINMENT SYSTEM	EA	8.000
	0104- 10- 3	SEDIMENT BARRIER	LF	55,829.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	833.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	69.000
	0107- 1-	LITTER REMOVAL	AC	923.810

**Call Order: 002 Proposal: E1W92**

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	572.140
	0110- 1- 1	CLEARING & GRUBBING (44893015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	190.000
	0120- 6-	EMBANKMENT	CY	3.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	105,161.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	111,007.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	64,669.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	16,622.400
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	7,049.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	8,325.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	114.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	163.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,114.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,142.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	12,258.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,313.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.860
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	7,015.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,209.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	10.630
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	247.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.410
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44892915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44893015201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	16.074
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	90.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,071.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	25.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	212.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44892915201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44893015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,016.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,062.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,251.000

**Call Order: 002 Proposal: E1W92**

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.672
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	247.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	991.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.356
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,911.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	8.616
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.982
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	10.651
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.624
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.617
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.009
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.009
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.541
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	1,358.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.119
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.115
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.119
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	320.000
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	8.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	137.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	36.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000