

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01240321	Call Order: 001	Proposal: E1W12	District:01
Counties:	MANATEE			
Road Name:	SR 37			
Limits:	13070000			
Project(s):	44738215201(*)	Federal Aid No:	N/A	
Total Roadway Length:	5.397 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	03/21/24	
Total Proposal Length:	5.397 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$4,550,050.36

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing, signing and pavement marking, and guardrail on SR 37 from SR 62 to Polk County Line in Manatee County.

Call Order: 001 Proposal: E1W12

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44738215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44738215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,750.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	450.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	492.000
	0102-115-	TYPE III BARRICADE	ED	30.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	450.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	450.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	364.000
	0104- 10- 3	SEDIMENT BARRIER	LF	57,100.000
	0107- 1-	LITTER REMOVAL	AC	120.250
	0107- 2-	MOWING	AC	122.850
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44738215201)	LS	1.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	75,217.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	30,141.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	6,205.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	7,457.400
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	22.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	16,837.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	801.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.931

Call Order: 001 Proposal: E1W12

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	19.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	9.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.527
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	5.118
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44738215201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	15.848
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	15.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	16.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	11.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-112	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, 12-20 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-140	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	2.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	1.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	28.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	15.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	801.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44738215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	19.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.931
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.527
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	5.118